



WALWORTH[®]
Since 1842



CAST STEEL PLUG VALVE
CATALOG

INDEX

INTRODUCTION

ENGINEERING CONTROL.....	5
QUALITY SYSTEM	5
QUALITY CONTROL EQUIPMENT.....	9

COMPENSATOR, TOP ENTRY, AND GAS SERVICE STEEL PLUG VALVES

WALWORTH LUBRICATED PLUG VALVES, ADVANTAGES AND PATTERNS	11
WALWORTH COMPENSATOR PLUG VALVES	12
COMPENSATOR PLUG VALVES SHORT PATTERN.....	13
COMPENSATOR PLUG VALVES SHORT PATTERN CLASS 150	14
COMPENSATOR PLUG VALVES SHORT PATTERN CLASS 300	18
COMPENSATOR PLUG VALVES REGULAR PATTERN	22
COMPENSATOR PLUG VALVES REGULAR PATTERN CLASS 150	23
COMPENSATOR PLUG VALVES REGULAR PATTERN CLASS 300	27
COMPENSATOR PLUG VALVES REGULAR PATTERN CLASS 600	31
COMPENSATOR PLUG VALVES REGULAR PATTERN CLASS 900	35
COMPENSATOR PLUG VALVES REGULAR PATTERN CLASS 1500	39
COMPENSATOR PLUG VALVES REGULAR PATTERN CLASS 2500	43
COMPENSATOR PLUG VALVES VENTURI PATTERN	47
COMPENSATOR PLUG VALVES VENTURI PATTERN CLASS 150	48
COMPENSATOR PLUG VALVES VENTURI PATTERN CLASS 300	50
COMPENSATOR PLUG VALVES VENTURI PATTERN CLASS 600	54
COMPENSATOR PLUG VALVES VENTURI PATTERN CLASS 900	58
TOP ENTRY PLUG VALVES SHORT PATTERN	60
TOP ENTRY PLUG VALVES SHORT PATTERN CLASS 150	61
TOP ENTRY PLUG VALVES SHORT PATTERN CLASS 300	63
TOP ENTRY PLUG VALVES REGULAR PATTERN	65
TOP ENTRY PLUG VALVES REGULAR PATTERN CLASS 600	66
TOP ENTRY PLUG VALVES VENTURI PATTERN	68
TOP ENTRY PLUG VALVES VENTURI PATTERN CLASS 150	69
GAS SERVICE PLUG VALVES	72
GAS SERVICE PLUG VALVES FIGURA 1966	73
GAS SERVICE PLUG VALVES FIGURA 1967	73
GAS SERVICE PLUG VALVES FIGURA 1968	73
TECHNICAL INFORMATION: WRENCHES	78
TECHNICAL INFORMATION: 2" OPERATING NUTS.....	79
TECHNICAL INFORMATION: WALSEAL PLUGS SEALANT.....	80
TECHNICAL INFORMATION: LUBRICANT ACCESSORIES	82
TECHNICAL INFORMATION: LUBRICANT FITTINGS	83
TECHNICAL INFORMATION: BUTT WELD DIMENSIONS	84
TECHNICAL INFORMATION: FLANGE DIMENSIONS AND TEMPLATES.....	85
PRESSURE-TEMPERATURE RATINGS	88
DESIGN BASIS.....	90
HOW TO ORDER.....	91
GENERAL TERMS AND CONDITIONS	92



6D-0097



YARMOUTH RESEARCH AND TECHNOLOGY



WALWORTH

WALWORTH is one of the world's most comprehensive industrial valve manufacturers. Founded in 19th century by James Walworth, the Company has consistently dedicated itself to improvements in design and manufacturing of an array of valves exceptionally suited for the world's fluid control sector. We satisfy all end use industries and comprehensive customer requirements by adhering to the most demanding quality standards.

WALWORTH relies on its broad experience in supplying valves to the petrochemical, oil & gas, petroleum, power generation, pulp and paper, cryogenic and geothermal industries, among others.

Over the years, Walworth has produced over 40,000 different types of products and serves as a global supplier to various markets utilizing the expertise of over 500 trained employees.

Our manufacturing system includes: utilization of Company directed raw material warehouses; modern and newly acquired specialized machinery; welding processes such as SMAW, GMAW, SAW, PAW; assembly testing for all low pressure, high pressure, and at low or high temperatures; painting and coating processes; export crating and shipment.

WALWORTH is capable of providing the world's most comprehensive industrial valve line to the North American, Central American, South American, European and African markets. WALWORTH is proud to meet and satisfy the precise demands of our customers throughout the world by providing a quality product, competitive cost, and excellent service.



WALWORTH VALUES

MISSION

WALWORTH manufactures and supplies world-class valves and components for the flow control industry through exceptional service, competitive pricing, and consistently, on-time deliveries.



VISION

To be the world leader of unparalleled valve manufacturing and supply, WALWORTH:

- Set the standard for product quality in the flow control industry.
- Exceed the service expectations of our customers.
- Forge enduring relationships with customers, team members, and community.
- Hire, develop, and retain experienced and dedicated team members.



WALWORTH ENGINEERING CONTROL

WALWORTH products are manufactured following the strict international standards recognized all over the world, such as API, ANSI, ASME, ASTM, MSS, NACE, AWWA, BSI, CSA, among others. Our Engineering team consistently monitors updates to these standards and incorporates any applicable changes that affect the design, regulations and/or performance of our products.

Our designs are made using the most advanced technology and equipment, finite elements, and CAD system programs to ensure proper assembly and performance. From conception to calculation to detailed drawings for manufacturers, WALWORTH is a leader in development of new products that meet the needs of the current valve market."




WALWORTH QUALITY SYSTEM

Throughout the years, WALWORTH has developed its Quality System which is an integral part of our manufacturing policy. Our primary goal is to provide products that meet and exceed market standards. In this sense, WALWORTH is an ISO-9001 Audited and Certified Company that has achieved major certifications worldwide. Our system includes the selection of raw materials from approved vendors, and rigorous oversight of our manufacturing process that is vital to quality control. The use of serial numbers allows WALWORTH the ability to not only ensure the quality of components used but to monitor and trace the fabrication process as well.



Certificate API-6D No. 6D-0097

Issued by American Petroleum Institute to apply on Gate valves, Plug valves, Ball valves and Check valves manufactured in accordance with API-6D specification.



Certificate API-6A No. 6A-0234

From American Petroleum Institute to apply on valves at PSI, 1 through 4.



Certificate API-594 No. 594-0007


Issued by American Petroleum

Institute to apply on Check Valves-Type A; Check Valves Type B manufactured in accordance with API-594 specification.



API-600 Certificate No. 600-0109

Issued by American Petroleum Institute to apply on Bolted Bonnet Steel Gate Valves manufactured in accordance with API-600 specification.



API-602 Certificate No. 602-0024

Issued by American Petroleum Institute to apply on Compact Steel Gate Valves, Compact Steel Globe Valves, and Compact Steel Check Valves manufactured in accordance with API-602 specification.



Certificate ISO-9001 No. 0038

Issued by American Petroleum Institute since April 1999.



Certificate as per PED 97/23/EC Module H
To stamp CE products.



Supplier Qualification Certificate NO. 279/13
 Issued by the Equipment and Materials Testing Laboratory, CFE (LAPEM in Spanish)



Certificate NMX-CC-9001 (Mexican Standards ISO-9001) No. 0552/2007
 Issued by PEMEX in accordance with ISO-9001 Quality Assurance System.

PRODUCT CERTIFICATIONS



Emissions after 500 cycles at ambient and 350 °F
 Issued by Yarmouth Research and Technology Lab for 3 inch Class 300 Gate Valve After 500 cycles the measurement result was less than 50 ppm.



Emissions after 500 cycles at ambient and 350 °F
 Issued by Yarmouth Research and Technology Lab for 8 inch Class 300 Gate Valve After 500 cycles the measurement result was less than 50 ppm.



Emissions after 500 cycles at ambient and 350 °F
 Issued by Yarmouth Research and Technology Lab for 16 inch Class 150 Gate Valve After 500 cycles the measurement result was less than 50 ppm.



YARMOUTH RESEARCH AND TECHNOLOGY

PROJECT SUMMARY

Project Number: 00008

Customer: The Walworth Company

Contact: David Cornelien

Date(s) of Test: 12/9/99 - 12/23/99

Product(s) Tested: One 8" Class 300 Gate Valve with Empak-Mex EAF-100-001 packing.

Purpose of Test: The test was conducted to evaluate the valve's stem sealing performance at ambient and at 350° F as related to the 1990 Amendments to the Clean Air Act requirements. Leakage measurements were conducted in accordance with 40 CFR Part 60, Appendix A, Method 21.

Conclusion: Three thermal cycles from ambient to 350 deg. F were conducted throughout 5000 open/close cycles with the valve presented to 640 psig. The valve was cycled with a 43 RPM gear motor coupled to the handwheel. One packing seal adjustment was required on cycle number 300 to maintain leakage levels below 100 PP50.

At cycle number 3500, the packing leakage was 25-29 PP50s with the stem static. The packing nuts were tightened from 12/13 B.B. back to 28 B.B. and leakage decreased to about 1 PP50s.

See the attached data sheets for more information.

Test Witness: Matthew J. Wasieleski, P.E., President
YARMOUTH RESEARCH AND TECHNOLOGY

Phone or Fax (202) 946-3646
42 East Elm Street P.O. Box 110 Yarmouth, Maine 04096-0110

TÜV Rheinland Argentina S.A.
Servicios Industriales
Certificación Control
San José 53 - 7° Piso
2222BAAU Buenos Aires

TÜVRheinland®

Certificate

Certificate No. TRASA 700-13-0019

Customer: WALWORTH METCO - Industrial de Valinox S.A. de C.V.

Product Tested: API 6D Trunnion mounted body ball valves, carbon steel (A105-WCB) construction, double block and bleed service, primarily used for oil and gas standard and severe applications.

Trademark: WALWORTH

Model / Type:

00001-1	Trunnion mounted body ball valve, carbon steel (A105-WCB) construction, double block and bleed service, primarily used for oil and gas standard and severe applications.
00001-2	Trunnion mounted body ball valve, carbon steel (A105-WCB) construction, double block and bleed service, primarily used for oil and gas standard and severe applications.
00001-3	Trunnion mounted body ball valve, carbon steel (A105-WCB) construction, double block and bleed service, primarily used for oil and gas standard and severe applications.
00001-4	Trunnion mounted body ball valve, carbon steel (A105-WCB) construction, double block and bleed service, primarily used for oil and gas standard and severe applications.
00001-5	Trunnion mounted body ball valve, carbon steel (A105-WCB) construction, double block and bleed service, primarily used for oil and gas standard and severe applications.

Applicable Standard: ASME B16.34

TUV Report No.: 700-13-0019

Results: Successful testing. 100% Pass.

Safety Function: The Trunnion Ball Valve will meet the design and construction requirements for the intended application. The valve is designed and constructed in accordance with the applicable standards.

Specific Requirements: The valve is designed and constructed in accordance with the applicable standards.

Ing. Mauricio Schwaner

Page 1 of 5

Certificates of Ultra Low Fugitive Emissions No. 20985-3, 8 & 16 in accordance with ISO-15848-1 "Industrial Valves" Measurement, Test and Qualification Procedures for Fugitive Emissions "Part 1: Classification System and Qualification Procedures for Type Testing of Valves".

TÜV Rheinland Certificate No. TRASA 700-13-0019
API-6D Trunnion mounted bolted body ball valves, carbon steel (A105-WCB) construction, double block and bleed service, primarily used but not limited to the oil and gas standard and severe applications.

DACOR SERVICES
CONSULTANTS
ENGINEERING • QUALITY ASSURANCE • MANUFACTURING
DAVID J. CORNELIEN, P.E., PRESIDENT

January 22, 2005

Ruben Parades
Walworth - Inval Facility
Av. De la Industria Lote 16 Fracc. Industrial de Trebol
Tepozotlan, Edo. De Mexico
CP 54600, Mexico

Reference: Witness Report - API Spec 6FA Fire Test Number 01-1/05

This will certify that the following listed valve successfully passed all requirements of API Specification 6FA Fire Test for Valves, Third Edition dated April 1999 and API Standard 607 Fire Test for Self-Seated Quarter-Turn Valves, Fourth Edition dated May 1993. The tests were made and verified on January 21, 2005.

API 6D Trunnion Mounted Ball Valve, 12-inch Class 150 Figure 8122, Serial Number V05B01.

The successful test of the 12-inch Class 150 API 6D Ball Valve qualifies this design/type of valve as meeting the requirements of API Spec 6FA / API Std 607 for sizes 12-inch through 24-inch in pressure classes 150 and 300.

Sincerely,

David J. Cornelien P.E.
President

24802 Mathews Drive • Katy, Texas 77494
Telephone (281) 395-5275 • Telex (281) 395-5275

tuv CERT **TÜVRheinland®**
Precisely Right.

CERTIFICATE
Certificate No.: 01 202 USA-TA-00-79704

Concerning the Agreement with the Technical Requirements in:
TA-Luft 2002, VDI 2440 Nov. 2000, Sec. 3.3.1.3

Test report: 209140 **Date:** 01 December, 2000

Client: Industrial de Valinox, S.A. de C.V.

Manufacturer's Address: Av. De la Industria Lote 16
Fracc. Industrial de Trebol,
Tepozotlan, Edo. De Mexico, CP 54600

The stem sealing system and internal flange connection have been successfully tested to meet the tightness criteria of 0.10⁻⁶ mbar x l/s at a helium mass spectrometer under the following conditions. The SPV Valve with the measured mechanical stuff seals fulfills the requirements of Section 3.3.1.3 of The German Clean Air Act (TA-Luft, Leakage Verification) in accordance with Section 3.3.1.3 of VDI 2440 (Nov. 2000).

Kind of Valve:	Walworth API 6D Gate Valve	
Valve Type:	4 inch, Class 150, Figure 8122	
Sealing System:	WCB Body / CR 13 Stem & Stem / HP Seat	
Sealing System:	Graphite Seals	
Nominal Size, Nominal Pressure:	4 inch, ANSI 300	
Inspection Media/Pressure:	Helium / 01 Bar	Temperature = Ambient
Switching Cycles (times):	8 Cycles	Total Cycles 800
Leakage Rate (mbar x l/s):	5.2e-7 (mbar x l/s)	5.7e-8 (mbar x l/s)
Testing Method:	Helium Leak Test - VDI 2440, Appendix A	

Testing Laboratory: TÜV Rheinland North America, Inc.
Industrial Services Division, Redwood, CT, USA
Matthew J. Wasieleski, PE
404 Walnut Hill Road, N. Yarmouth, ME USA
www.yarmouthresearch.com

Matthew J. Wasieleski, PE

Fire Test Certificate No. 01-1/05
In accordance with API-6FA and API Standard API-607 for Trunnion Ball Valves in accordance with API-6D.

TA Luft Certificate (Fugitive Emission) Approval
ISO-5211 Top Flange, Anti-Static Device.

QUALITY CONTROL EQUIPMENT

In order to assure that WALWORTH products comply with international quality standards, in-house equipment is kept for monitoring control. Some of this equipment includes:



X-Ray Examination Equipment. WALWORTH has its own Ir-92 source in-house for the radiographic examination (RT) of castings from 0.100" up to 2 1/2" wall thickness to verify the soundness of the casting raw material.

PMI Equipment. A new generation of Positive Material Identification Equipment gives WALWORTH the capability to perform quick chemical analysis on incoming raw materials and on pieces after assembly, to certify that materials used were produced and assembled in accordance with WALWORTH's and our Customer's specifications.



Magnetic Particle Test. On a random basis for standard products or when a Customer requests MT Certification, WALWORTH has Magnetic Particle Test Equipment to perform on ferromagnetic materials.

Penetrant Test Examination. WALWORTH has the personnel and materials to perform PT examination by solvent removable or water washable techniques. NDT personnel are ASNT Certified.



Test Loop. A complete Laboratory Test loop exists for design validation of WALWORTH products. The test is performed at maximum design pressure, advances the valves from 3000 to 5000 cycles, and requires more than four months to complete.

Pressure Gradient Test Loop. This test exposes Plug valves to the extremes of both positive and negative pressure gradients to verify that the plug in a balanced plug design will prevent lock-up in the body.





Metrology Laboratory. WALWORTH developed a calibration and/or verification system in all of the equipment used in its facilities. This ensures our ability to trace measurements, control products, and comply with international standards.

Fire Test Facilities. WALWORTH has the facilities to perform fire tests in accordance with API requirements. The test exposes the valve to a fire flame at 1400 to 1800 °F (761 to 980 °C) to verify proper seal of the valve.



Low Fugitive Emissions Test. This test is performed when a Customer requires low fugitive emissions certification. Our Lab has its own LFE test equipment that is capable of measuring less than 20 ppm in both static and mechanical conditions at either ambient temperature or thermal cycle operations.

Ultrasonic Testing Equipment. Using ultrasonic techniques, we can detect sub surface flaws in materials and evaluate castings and forgings that cannot be radiographed. In addition, we utilize these techniques to measure the wall thickness of castings and forgings.



Tensile Test Equipment. We use this equipment to verify the mechanical properties of materials used for manufacturing. WALWORTH tests samples on a random basis even though we receive MTRs from our suppliers and foundries.

Hardness Test Equipments.- In both lab and shop tests, WALWORTH uses hardness tester equipment, such as Rockwell B, C Brinell or Vickers, to ensure compliance with specifications.



WALWORTH LUBRICATED PLUG VALVES

ADVANTAGES

Plug Valves have inherent advantages over the other conventional types of Valves, especially when used in corrosive or erosive service. Some of these advantages are:

1. Sealing surfaces are not exposed

The vital surfaces of the plug are self protecting and self cleaning. When fully open, all machined seating surfaces of the plug are protected from erosion or corrosive materials. When closed, only a small area, which is not needed to effect a positive shut off, is exposed to the line fluid.

2. Self cleaning seating surfaces

The shearing action of the plug valve scrapes off any abrasive ingredient which may touch the plug in a closed position.

3. Smooth Flow

The straightway passage through the plug port affords a smooth unobstructed flow, offering no opportunity for sediment or scale to collect.

4. Bubble tight shutoff

The lubricated plug and sealant system assure positive bubble tight shut off when properly maintained.

5. Ease of operation

Positive quarter turn operation is quick and sure.

6. Plug Adjustment

A WALWORTH lubricated plug valve can be adjusted with the valve in line, helping to extend the service life of the valve.

PATTERNS

WALWORTH plug valves are available in three different patterns to provide the efficiency and flexibility to meet the valve need of most piping systems.



SHORT PATTERN

Provides face to face dimensions that match gate valves.



REGULAR PATTERN

Offers the largest port opening in a trapezoidal configuration – close to a full pipe size.



VENTURI PATTERN

Has a smaller port than the other two patterns. Is lower in cost and flow contours maximize hydraulic efficiency.

WALWORTH LUBRICATED PLUG VALVES

THE WALWORTH COMPENSATOR

The plug valve eliminates taper lock, for years of dependable service with little or no maintenance, even in hostile environments.

“Positive Bias” Balance Plug Design

The COMPENSATOR plug valve design is based on a load compensating, mechanically balanced tapered plug, which cannot bind or lock. Maintenance is virtually eliminated; lower operating torque is achieved, and size and weight are reduced by 20% to 25%. The COMPENSATOR provides these major benefits, while retaining the positives attributes of automatic shut-off, fire safety, and resistance to corrosion and erosion not found in conventional tapered plug valves.

How it works

Unlike other lubricated plug valve designs, WALWORTH's COMPENSATOR plug valve does not rely on sealant or line pressure to keep the plug from wedging or binding in the valve body. Instead, the COMPENSATOR utilizes SS-304 long life spring-type helicoidal and an adjusting screw to mechanically balance the plug and compensate for line pressure. The function of the sealant, therefore, is to provide a backup to the tight seal between the plug and body. The sealant chamber is isolated from the line media. A sealant fitting is provided to permit injection of sealant into the isolated chamber to assure a bubble tight seal and to lubricate internal parts.

Positive Downward Bias Pressure Balance


There is a passageway with a ball check between the flow port of the plug and the lower chamber. When a pressure rise occurs in the flow port area, the ball check is held shut, forcing pressure equalization to take place through the annular clearance gap at the top and bottom of the lubricated plug. Since the net differential plug area is greater at the bottom, the result is a net downward force acting on the plug. In the event of a sudden drop in flow port pressure, the positive bias downward is maintained because the upper sealant chamber is forced to equalize through the annular gap, while the lower cavity equalizes through both the gap and the ball check valve. Thus, the lower chamber reaches equilibrium with the flow port well before the upper chamber, causing the plug to stay against the ball at its base.



Ball Check Valves



THE WALWORTH COMPENSATOR PLUG VALVE SHORT PATTERN



Design Features


- ① Open/Close Indicator - quarter turn stop collar also functions as an indicator of the plug's position.
- ② Stem Sealing System - the stem is protected two ways. The weather seal protects it from external attack. High temperature soft packing protects the stem against internal leakage.
- ③ Balancing Spring - the mechanical spring type grade 304 Stainless Steel is under compression and holds the plug in an equalized pressure position, thus eliminating the possibility of plug taper lock.
- ④ Isolated Sealant Chamber - the sealant's function is to provide a backup to the positively biased surface between the plug and the body.
- ⑤ Plug - the mechanically balanced plug has a permanently bonded PERFLO coating for a very low coefficient of friction. Operating torque remains low over the 4,000 cycle test life of the valve.
- ⑥ Plug Adjustment - the steel plug is mechanically loaded into the body to put tension on the balance spring and is then adjusted for optimum balance and performance. The adjustment screw is covered to prevent tampering and possible misadjustment.

*End to End Dimension as per ASME B16.10 to meet Short Pattern Length

COMPENSATOR PLUG VALVE SHORT PATTERN CLASS 150 (WRENCH OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Ball	Cr. Steel Gr. 200, A295 Type 52100
9	Thrust Ball Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Stem Environmental Seal	Elastomer
22	Cover Studs Environmental Seals	Buna N
23	Stop Collar	Carbon Steel
24	Stop Pin	Carbon Steel
25	Retainer	Carbon Steel
26	Adjustment Cover	Carbon Steel
27	Adjustment Cover Gasket	Natural Fiber
28	Adjustment Cover Screw	Carbon Steel
29	Identification Plate*	Stainless Steel 304
30	Sealant*	Walseal #10
31	Balance Spring Ball	A295 Type 52100
32	Wrench	Carbon Steel



*Not Shown



(1) Valves from ½" to 1 ½" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WC6.

COMPENSATOR PLUG VALVE SHORT PATTERN CLASS 150 (WRENCH OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Design as per API 6D
- Fire Test as per API 6FA

Figure no.	Operation	Type of ends
1412	Wrench	RF
1414	Wrench	WE



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions						Approx Weight				Wrench No.
										E						RF/RTJ		WE		
		A		B		C		D		RF		RTJ		WE						
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb	
2	50	5.9	150	3.78	96	1.37	35	4.125	105	7	178	7.5	191	10.5	267	16	35	-	-	IB-2
3	76	6.84	174	4.53	115	1.37	35	4.62	117	8	203	8.5	216	13	330	30	66	-	-	IB-2
4	100	7.37	187	5.05	128	1.37	35	5.25	133	9	229	9.5	241	14	356	35	77	31	68	IB-2
6	150	9.51	242	6.25	159	1.99	51	8.12	206	10.5	267	11	279	18	457	64	141	45	99	IB-3
8	200	11.75	298	9	229	1.99	51	9.75	248	11.5	292	12	305	20.5	521	89	196	70	154	IB-3

Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figure: 1415


COMPENSATOR PLUG VALVE SHORT PATTERN CLASS 150 (GEAR OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Ball	Cr. Steel Gr. 200, A295 Type 52100
9	Thrust Ball Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Cover Studs Environmental Seals	Buna N
22	Adjustment Cover	Carbon Steel
23	Adjustment Cover Gasket	Natural Fiber
24	Adjustment Cover Screw	Carbon Steel
25	Identification Plate*	Stainless Steel 304
26	Sealant*	Walseal #10
27	Balance Spring Ball	A295 Type 52100
28	Gear Box	Commercial Steel
29	Top Socket Screw	Carbon Steel A449 Gr. 5

*Not Shown

(1) Valves from ½" to 1 ½" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WC6.





COMPENSATOR PLUG VALVE SHORT PATTERN CLASS 150 (GEAR OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Design as per API 6D
- Fire Test as per API 6FA

Figure no.	Operation	Type of ends
1422	Gear operator	RF
1424	Gear operator	WE



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions						Approx Weight			
										E						RF/RTJ		WE	
		A		B		C		D		RF		RTJ		WE					
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb
4	100	10.18	259	5.05	128	12	305	5.25	133	9	229	9.5	241	14	356	62	136	54	119
6	150	11.4	290	6.38	162	20	508	8.12	206	10.5	267	11	279	18	457	87	191	65	143
8	200	13.11	333	9	229	20	508	9.75	248	11.5	292	12	305	20.5	521	116	255	87	191
10	250	14.83	377	9.5	241	20	508	11.5	292	13	330	13.5	343	22	559	205	451	170	374
12	300	16.5	419	11.69	297	20	508	12	305	14	356	14.5	368	25	635	272	598	190	418

Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figure: 1425


COMPENSATOR PLUG VALVE SHORT PATTERN CLASS 300 (WRENCH OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Ball	Cr. Steel Gr. 200, A295 Type 52100
9	Thrust Ball Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Stem Environmental Seal	Elastomer
22	Cover Studs Environmental Seals	Buna N
23	Stop Collar	Carbon Steel
24	Stop Pin	Carbon Steel
25	Retainer	Carbon Steel
26	Adjustment Cover	Carbon Steel
27	Adjustment Cover Gasket	Natural Fiber
28	Adjustment Cover Screw	Carbon Steel
29	Identification Plate*	Stainless Steel 304
30	Sealant*	Walseal #10
31	Balance Spring Ball	A295 Type 52100
32	Wrench	Carbon Steel

*Not Shown

(1) Valves from ½" to 1 ½" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WC6.





COMPENSATOR PLUG VALVE SHORT PATTERN CLASS 300 (WRENCH OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Design as per API 6D
- Fire Test as per API 6FA

Figure no.	Operation	Type of ends
3412	Wrench	RF
3413	Wrench	RTJ
3414	Wrench	WE



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions						Approx Weight				Wrench No.
										E						RF/RTJ		WE		
		A		B		C		D		RF		RTJ		WE						
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb	
2	50	4.5	114	3.78	96	1.37	35	4.37	111	8.5	216	9.12	232	10.5	267	20	44	13	29	IB-2
3	76	6.84	174	4.41	112	1.37	35	4.62	117	11.12	283	11.75	298	13	330	35	77	26	57	IB-2
4	100	7.37	187	5.05	128	1.37	35	5.25	133	12	305	12.62	321	14	356	41	90	36	79	IB-2
6	150	9.51	242	6.38	162	1.99	51	8.12	206	15.87	403	16.50	419	18	457	91	200	73	161	IB-3
8	200	11.72	298	9.19	233	1.99	51	9.75	248	16.5	419	17.12	435	20.5	521	150	330	115	253	IB-3

Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figure: 3415


COMPENSATOR PLUG VALVE SHORT PATTERN CLASS 300 (GEAR OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Ball	Cr. Steel Gr. 200, A295 Type 52100
9	Thrust Ball Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Cover Studs Environmental Seals	Buna N
22	Adjustment Cover	Carbon Steel
23	Adjustment Cover Gasket	Natural Fiber
24	Adjustment Cover Screw	Carbon Steel
25	Identification Plate*	Stainless Steel 304
26	Sealant*	Walseal #10
27	Balance Spring Ball	A295 Type 52100
28	Gear Box	Commercial Steel
29	Top Socket Screw	Carbon Steel A449 Gr. 5

*Not Shown

(1) Valves from ½" to 1 ½" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WC6.





COMPENSATOR PLUG VALVE SHORT PATTERN CLASS 300 (GEAR OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Design as per API 6D
- Fire Test as per API 6FA

Figure no.	Operation	Type of ends
3422	Gear operator	RF
3423	Gear operator	RTJ
3424	Gear operator	WE




Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions						Approx Weight			
										E						RF/RTJ		WE	
		A		B		C		D		RF		RTJ		WE					
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb
3	76	11.3	287	4.41	112	12	305	4.62	117	11.12	283	11.75	298	13	330	62	136	50	110
4	100	10.1	257	5.05	128	12	305	5.25	133	12	305	12.62	321	14	356	68	150	52	114
6	150	11.4	290	6.38	162	20	508	8.12	206	15.87	403	16.5	419	18	457	118	260	89	196
8	200	13.11	333	9.14	232	20	508	9.75	248	16.5	419	17.12	435	20.5	521	181	398	140	308
10	250	16.53	420	10.4	264	30	762	?	?	18	457	18.62	473	22	559	340	748	300	660

Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figure: 3425

COMPENSATOR PLUG VALVE REGULAR PATTERN



Design Features

- ① Open/Close Indicator - quarter turn stop collar also functions as an indicator of the plug's position.
- ② Stem Sealing System - the stem is protected two ways. The weather seal protects it from external attack. High temperature soft packing protects the stem against internal leakage.
- ③ Balancing Spring - the mechanical spring type Stainless steel 304 is under compression and holds the plug in an equalized pressure position, thus eliminating the possibility of plug taper lock.
- ④ Isolated Sealant Chamber - the sealant's function is to provide a backup to the positively biased surface between the plug and the body.
- ⑤ Plug - the mechanically balanced plug has a permanently bonded PERFLO coating for a very low coefficient of friction. Operating torque remains low over the 4,000 cycle test life of the valve.
- ⑥ Plug Adjustment - the steel plug is mechanically loaded into the body to put tension on the balance spring and is then adjusted for optimum balance and performance. The adjustment screw is covered to prevent tampering and possible misadjustment.

*End to End Dimension as per ASME B16.10 to meet Regular Pattern Length


COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 150 (WRENCH OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Ball	Cr. Steel Gr. 200, A295 Type 52100
9	Thrust Ball Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Stem Environmental Seal	Elastomer
22	Cover Studs Environmental Seals	Buna N
23	Stop Collar	Carbon Steel
24	Stop Pin	Carbon Steel
25	Retainer	Carbon Steel
26	Adjustment Cover	Carbon Steel
27	Adjustment Cover Gasket	Natural Fiber
28	Adjustment Cover Screw	Carbon Steel
29	Identification Plate*	Stainless Steel 304
30	Sealant*	Walseal #10
31	Balance Spring Ball	A295 Type 52100
32	Wrench	Carbon Steel

*Not Shown

(1) Valves from ½" to 1 ½" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WC6.





COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 150 (WRENCH OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Design as per API 6D
- Fire Test as per API 6FA

Figure no.	Operation	Type of ends
1512	Wrench	RF
1514	Wrench	WE



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions						Approx Weight				Wrench No.
										E						RF/RTJ		WE		
		A		B		C		D		RF		RTJ		WE						
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb	
2	50	5.9	150	3.78	96	1.37	35	4.125	105	-	-	-	-	-	-	19	42	-	-	IB-2
3	76	6.84	174	4.53	115	1.37	35	4.62	117	-	-	-	-	-	-	30	66	-	-	IB-2
4	100	7.37	187	5.05	128	1.37	35	5.25	133	-	-	-	-	-	-	35	77	31	68	IB-2
6	150	9.51	242	6.25	159	1.99	51	8.12	206	15.5	394	16	406	-	-	64	141	45	99	IB-3
8	200	11.75	298	9	229	1.99	51	9.75	248	18	457	18.5	470	-	-	89	196	70	154	IB-3

Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figure 1515


COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 150 (GEAR OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Ball	Cr. Steel Gr. 200, A295 Type 52100
9	Thrust Ball Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Cover Studs Environmental Seals	Buna N
22	Adjustment Cover	Carbon Steel
23	Adjustment Cover Gasket	Natural Fiber
24	Adjustment Cover Screw	Carbon Steel
25	Identification Plate*	Stainless Steel 304
26	Sealant*	Walseal #10
27	Balance Spring Ball	A295 Type 52100
28	Gear Box	Commercial Steel
29	Top Socket Screw	Carbon Steel A449 Gr. 5

*Not Shown

(1) Valves from ½" to 1 ½" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WC6.





COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 150 (GEAR OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Design as per API 6D
- Fire Test as per API 6FA



Figure no.	Operation	Type of ends
1522	Gear operator	RF
1524	Gear operator	WE



Dimensions and Weights


Nominal Size		General Dimensions								End to End Dimensions						Approx Weight			
										E						RF/RTJ		WE	
		A		B		C		D		RF		RTJ		WE					
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb
4	100	10.18	259	5.05	128	12	305	5.25	133	-	-	-	-	-	-	77	169	54	119
6	150	11.4	290	6.38	162	20	508	8.12	206	15.5	394	16	406	-	-	101	222	65	143
8	200	13.11	333	9	229	20	508	9.75	248	18	457	15.5	475	-	-	133	293	87	191
10	250	14.83	377	9.5	241	20	508	11.5	292	21	533	21.5	546	-	-	209	460	170	374
12	300	16.5	419	11.69	297	20	508	12	305	24	610	24.3	622	-	-	314	691	190	418

Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figure 1525

COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 300 (WRENCH OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Ball	Cr. Steel Gr. 200, A295 Type 52100
9	Thrust Ball Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Stem Environmental Seal	Elastomer
22	Cover Studs Environmental Seals	Buna N
23	Stop Collar	Carbon Steel
24	Stop Pin	Carbon Steel
25	Retainer	Carbon Steel
26	Adjustment Cover	Carbon Steel
27	Adjustment Cover Gasket	Natural Fiber
28	Adjustment Cover Screw	Carbon Steel
29	Identification Plate*	Stainless Steel 304
30	Sealant*	Walseal #10
31	Balance Spring Ball	A295 Type 52100
32	Wrench	Carbon Steel



*Not Shown



(1) Valves from ½" to 1 ½" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WC6.

COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 300 (WRENCH OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Design as per API 6D
- Fire Test as per API 6FA

Figure no.	Operation	Type of ends
3512	Wrench	RF
3513	Wrench	RTJ
3514	Wrench	WE



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions						Approx Weight				Wrench No.
										E						RF/RTJ		WE		
		A		B		C		D		RF		RTJ		WE						
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb	
2	50	4.5	114	3.78	96	1.37	35	4.37	111	-	-	-	-	-	-	26	57	21	46	IB-2
3	76	6.84	174	4.41	112	1.37	35	4.62	117	-	-	-	-	-	-	46	101	38	84	IB-2
4	100	7.37	187	5.05	128	1.37	35	5.25	133	-	-	-	-	-	-	54	119	45	99	IB-2
6	150	9.51	242	6.38	162	1.99	51	8.12	206	15.87	403	16.5	419	-	-	119	262	99	218	IB-3
8	200	11.72	298	9.19	233	1.99	51	9.75	248	19.75	502	20.37	518	-	-	195	429	162	356	IB-3

Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figure 3515


COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 300 (GEAR OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Ball	Cr. Steel Gr. 200, A295 Type 52100
9	Thrust Ball Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Cover Studs Environmental Seals	Buna N
22	Adjustment Cover	Carbon Steel
23	Adjustment Cover Gasket	Natural Fiber
24	Adjustment Cover Screw	Carbon Steel
25	Identification Plate*	Stainless Steel 304
26	Sealant*	Walseal #10
27	Balance Spring Ball	A295 Type 52100
28	Gear Box	Commercial Steel
29	Top Socket Screw	Carbon Steel A449 Gr. 5

*Not Shown

(1) Valves from 1/2" to 1 1/2" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WC6.





COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 300 (GEAR OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Design as per API 6D
- Fire Test as per API 6FA



Figure no.	Operation	Type of ends
3522	Gear operator	RF
3523	Gear operator	RTJ
3524	Gear operator	WE



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions						Approx Weight			
										E						RF/RTJ		WE	
		A		B		C		D		RF		RTJ		WE					
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb
2	50	8.43	214	3.78	96	12	305	4.37	111	-	-	-	-	-	-	33	73	27	59
3	76	9.84	250	5.09	129	12	305	5	127	-	-	-	-	-	-	69	152	59	130
4	100	10.01	254	5.06	129	12	305	5.75	146	-	-	-	-	-	-	100	220	75	165
6	150	11.6	295	7.63	194	20	508	9.63	245	-	-	-	-	-	-	200	440	150	330
8	200	14.62	371	9.82	249	30	762	10.75	273	15.87	403	16.5	419	-	-	321	706	255	561
10	250	17.03	433	12.31	313	30	762	15.62	397	19.75	502	20.37	518	-	-	545	1199	410	902
12	300	18.04	458	14.19	360	30	762	15	381	22.37	568	23	584	-	-	820	1804	615	1353

Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figure 3525


COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 600 (WRENCH OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Ball	Cr. Steel Gr. 200, A295 Type 52100
9	Thrust Ball Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Stem Environmental Seal	Elastomer
22	Cover Studs Environmental Seals	Buna N
23	Stop Collar	Carbon Steel
24	Stop Pin	Carbon Steel
25	Retainer	Carbon Steel
26	Adjustment Cover	Carbon Steel
27	Adjustment Cover Gasket	Natural Fiber
28	Adjustment Cover Screw	Carbon Steel
29	Identification Plate*	Stainless Steel 304
30	Sealant*	Walseal #10
31	Balance Spring Ball	A295 Type 52100
32	Wrench	Carbon Steel

*Not Shown

(1) Valves from 1/2" to 1 1/2" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WCB.





COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 600 (WRENCH OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Threaded Dimensions conform to ANSI/ASME B1.20.1
- Design as per API 6D
- Fire Test as per API 6FA

Figure no.	Operation	Type of ends
6511	Wrench	THREADED
6512	Wrench	RF
6513	Wrench	RTJ
6514	Wrench	WE



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions								Approx Weight						Wrench No.
										E								RF/RTJ		WE		THREADED		
		A		B		C		D		RF		RTJ		THREADED	WE									
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb	Kg	lb	
1	25	4.5	114	2.78	71	0.74	19	3.62	92	-	-	-	-	-	-	-	-	10	22	7	15	7	15	IB-0
1 1/2	40	5.06	129	3.37	86	1	25	4	102	-	-	-	-	-	-	-	-	17	37	12	26	12	26	IB-1
2	50	5.98	152	3.78	96	1.37	35	4.37	111	11.5	292	11.62	295	7.75	197	11.5	292	24	53	18	40	18	40	IB-2
3	76	6.84	174	5.09	129	1.37	35	5	127	14	356	14.12	359	10	254	14	356	40	88	29	64	29	64	IB-2
4	100	7.37	187	5.88	149	1.37	35	5.75	146	17	432	17.12	435	11.5	292	17	432	70	154	50	110	50	110	IB-2
6	150	9.65	245	7.63	194	1.99	51	9.62	244	22	559	22.12	562	-	-	22	559	172	378	-	-	118	260	IB-3

Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figure 6515


COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 600 (GEAR OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Ball	Cr. Steel Gr. 200, A295 Type 52100
9	Thrust Ball Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Cover Studs Environmental Seals	Buna N
22	Adjustment Cover	Carbon Steel
23	Adjustment Cover Gasket	Natural Fiber
24	Adjustment Cover Screw	Carbon Steel
25	Identification Plate*	Stainless Steel 304
26	Sealant*	Walseal #10
27	Balance Spring Ball	A295 Type 52100
28	Gear Box	Commercial Steel
29	Top Socket Screw	Carbon Steel A449 Gr. 5

*Not Shown

(1) Valves from ½" to 1 ½" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WC6.





COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 600 (GEAR OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Design as per API 6D
- Fire Test as per API 6FA



Figure no.	Operation	Type of ends
6522	Gear operator	RF
6523	Gear operator	RTJ
6524	Gear operator	WE



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions						Approx Weight			
										E									
		A		B		C		D		RF		RTJ		WE		RF/RTJ		WE	
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb				
2	50	8.43	214	3.78	96	12	305	4.37	111	11.5	292	11.62	295	11.5	292	33	73	27	59
3	76	9.84	250	5.09	129	12	305	5	127	14	356	14.12	359	14	356	69	152	59	130
4	100	10.01	254	5.06	129	12	305	5.75	146	17	432	17.12	435	17	432	100	220	75	165
6	150	11.6	295	7.63	194	20	508	9.63	245	22	559	22.12	562	22	559	200	440	150	330
8	200	14.62	371	9.82	249	30	762	10.75	273	26	660	26.12	664	26	660	321	706	255	561
10	250	17.03	433	12.31	313	30	762	15.62	397	31	787	31.12	791	31	787	545	1199	410	902
12	300	18.04	458	14.19	360	30	762	15	381	-	-	-	-	-	-	820	1804	615	1353

Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figures 6525


COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 900 (WRENCH OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Ball	Cr. Steel Gr. 200, A295 Type 52100
9	Thrust Ball Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Stem Environmental Seal	Elastomer
22	Cover Studs Environmental Seals	Buna N
23	Stop Collar	Carbon Steel
24	Stop Pin	Carbon Steel
25	Retainer	Carbon Steel
26	Adjustment Cover	Carbon Steel
27	Adjustment Cover Gasket	Natural Fiber
28	Adjustment Cover Screw	Carbon Steel
29	Identification Plate*	Stainless Steel 304
30	Sealant*	Walseal #10
31	Balance Spring Ball	A295 Type 52100
32	Wrench	Carbon Steel

*Not Shown

(1) Valves from ½" to 1 ½" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WC6.





COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 900 (WRENCH OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Threaded Dimensions to conform to ANSI/ASME B 1.20.1
- Design as per API 6D
- Fire Test as per API 6FA

Figure no.	Operation	Type of ends
9511	Wrench	THREADED
9512	Wrench	RF
9513	Wrench	RTJ
9514	Wrench	WE



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions								Approx Weight						Wrench No.
										E								RF/RTJ		WE		THREADED		
		A		B		C		D		RF		RTJ		THREADED		WE								
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb	Kg	lb	
2	50	6	152	3.91	99	1.37	35	4.75	121	14.5	368	14.62	371	7.75	197	-	-	41	90	31	68	31	68	IB-2
3	76	7.93	201	5.09	129	2	51	6.12	155	15	381	15.12	384	10	254	15	381	65	143	55	121	55	121	IB-3
4	100	8.65	220	6.19	157	2	51	8.5	216	18	457	18.12	460	11.5	292	18	457	104	229	90	198	90	198	IB-3

Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figure 9515


COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 900 (GEAR OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Ball	Cr. Steel Gr. 200, A295 Type 52100
9	Thrust Ball Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Cover Studs Environmental Seals	Buna N
22	Adjustment Cover	Carbon Steel
23	Adjustment Cover Gasket	Natural Fiber
24	Adjustment Cover Screw	Carbon Steel
25	Identification Plate*	Stainless Steel 304
26	Sealant*	Walseal #10
27	Balance Spring Ball	A295 Type 52100
28	Gear Box	Commercial Steel
29	Top Socket Screw	Carbon Steel A449 Gr. 5

*Not Shown

(1) Valves from 1/2" to 1 1/2" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WC6.





COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 900 (GEAR OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Design as per API 6D
- Fire Test as per API 6FA



Figure no.	Operation	Type of ends
9522	Gear operator	RF
9523	Gear operator	RTJ
9524	Gear operator	WE



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions						Approx Weight			
										E						RF/RTJ		WE	
		A		B		C		D		RF		RTJ		WE					
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb
3	76	11.69	297	5.09	129	20	508	6.13	156	15	381	15.12	384	15	381	92	202	70	154
4	100	12.44	316	6.19	157	20	508	8.5	216	18	457	18.12	460	18	457	132	290	100	220
6	150	15.15	385	9	229	20	508	10	254	24	610	24.12	613	24	610	150	330	190	418
8	200	16.37	416	9.75	248	30	762	13	330	29	737	29.12	740	29	737	464	1021	350	770
10	254	19.37	492	11.37	289	20	508	15.62	397	33	838	33.12	841	33	838	625	1375	470	1034

Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figure 9525


COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 1500 (WRENCH OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Ball	Cr. Steel Gr. 200, A295 Type 52100
9	Thrust Ball Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Stem Environmental Seal	Elastomer
22	Cover Studs Environmental Seals	Buna N
23	Stop Collar	Carbon Steel
24	Stop Pin	Carbon Steel
25	Retainer	Carbon Steel
26	Adjustment Cover	Carbon Steel
27	Adjustment Cover Gasket	Natural Fiber
28	Adjustment Cover Screw	Carbon Steel
29	Identification Plate*	Stainless Steel 304
30	Sealant*	Walseal #10
31	Balance Spring Ball	A295 Type 52100
32	Wrench	Carbon Steel

*Not Shown

(1) Valves from ½" to 1 ½" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WC6.





COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 1500 (WRENCH OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Threaded Dimensions conform to ANSI/ASME B1.20.1
- Design as per API 6D
- Fire Test as per API 6FA



Figure no.	Operation	Type of ends
5511	Wrench	THREADED
5512	Wrench	RF
5513	Wrench	RTJ
5514	Wrench	WE



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions								Approx Weight						Wrench No.
										E								RF/RTJ		WE		THREADED		
		A		B		C		D		RF		RTJ		THREADED	WE	Kg	Lb							
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	Lb	Kg	Lb	Kg	Lb	
1/2	15	4.24	108	2.42	61	0.74	19	3.43	87	-	-	-	-	4.5	114	-	-	-	-	5	11	-	-	IB-0
3/4	20	4.24	108	2.42	61	0.74	19	3.43	87	-	-	-	-	4.5	114	-	-	-	-	5	11	-	-	IB-0
1	25	4.5	114	2.78	71	0.74	19	3.87	98	-	-	-	-	5	127	-	-	14	10	10	22	-	-	IB-0
2	50	5.06	129	3.5	89	1	25	4.25	108	14.5	368	14.62	371	6.69	170	14.5	368	25	17	17	37	-	-	IB-1
3	76	5.98	152	3.91	99	1.37	35	4.75	121	18.5	470	18.62	473	7.75	197	18.5	470	41	31	31	68	31	68	IB-2
4	100	7.93	201	5.09	129	1.99	51	6.37	162	21.5	546	21.62	549	10	254	21.5	546	89	67	67	147	67	147	IB-3
6	150	8.56	217	6.19	157	1.99	51	8.5	216	27.75	705	30	711	11.5	292	27.75	705	133	100	100	220	100	220	IB-3

Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figure 5515


COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 1500 (GEAR OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Ball	Cr. Steel Gr. 200, A295 Type 52100
9	Thrust Ball Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Cover Studs Environmental Seals	Buna N
22	Adjustment Cover	Carbon Steel
23	Adjustment Cover Gasket	Natural Fiber
24	Adjustment Cover Screw	Carbon Steel
25	Identification Plate*	Stainless Steel 304
26	Sealant*	Walseal #10
27	Balance Spring Ball	A295 Type 52100
28	Gear Box	Commercial Steel
29	Top Socket Screw	Carbon Steel A449 Gr. 5
30	Packing Injector	Carbon Steel

*Not Shown

(1) Valves from ½" to 1 ½" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WC6.





COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 1500 (GEAR OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Design as per API 6D
- Fire Test as per API 6FA

Figure no.	Operation	Type of ends
5522	Gear operator	RF
5523	Gear operator	RTJ
5524	Gear operator	WE



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions						Approx Weight			
										E						RF/RTJ		WE	
		A		B		C		D		RF		RTJ		WE					
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb
2	50	10.41	264	3.91	99	12	305	4.75	121	14.5	368	14.62	371	-	-	69	152	52	114
3	76	13.96	355	8.71	221	20	508	6.37	162	18.5	470	18.62	473	18.5	470	110	242	80	176
4	100	12.44	316	6.19	157	20	508	8.5	216	21.5	546	21.62	549	21.5	546	160	352	127	279
6	150	15.29	388	8.25	210	30	762	10.75	273	27.75	705	28	711	27.75	705	384	845	290	638
8	200	21.62	549	11.5	292	20	508	13	330	32.75	832	33.12	841	32.75	832	755	1661	565	1243
10	250	20.53	521	15.56	395	30	762	13	330	39	991	39.37	1000	39	991	1682	3700	1465	3223


Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figure 5525

COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 2500 (WRENCH OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Ball	Cr. Steel Gr. 200, A295 Type 52100
9	Thrust Ball Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Stem Environmental Seal	Elastomer
22	Cover Studs Environmental Seals	Buna N
23	Stop Collar	Carbon Steel
24	Stop Pin	Carbon Steel
25	Retainer	Carbon Steel
26	Adjustment Cover	Carbon Steel
27	Adjustment Cover Gasket	Natural Fiber
28	Adjustment Cover Screw	Carbon Steel
29	Identification Plate*	Stainless Steel 304
30	Sealant*	Walseal #10
31	Balance Spring Ball	A295 Type 52100
32	Wrench	Carbon Steel
33	Packing Injector	Carbon Steel

*Not Shown





COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 2500 (WRENCH OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Threaded Dimensions conform to ANSI/ASME B 1.20.1
- Design as per API 6D
- Fire Test as per API 6FA

Figure no.	Operation	Type of ends
2511	Wrench	THREADED
2512	Wrench	RF
2513	Wrench	RTJ
2514	Wrench	WE



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions								Approx Weight						Wrench No.
										E								RF/RTJ		WE		THREADED		
		A		B		C		D		RF		RTJ		THREADED	WE									
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb	Kg	lb	
1/2	15	5.7	145	3.9	99	0.85	22	4.6	117	-	-	-	-	5.04	128	-	-	-	-	10	22	-	-	IB-0
3/4	20	5.7	145	3.9	99	0.85	22	4.6	117	-	-	-	-	5.04	128	-	-	-	-	10	22	-	-	IB-0
1	25	5.7	145	3.9	99	0.85	22	4.6	117	-	-	-	-	5.04	128	-	-	23	51	10	22	-	-	IB-0
1 1/2	40	6.6	168	4.8	122	1.09	28	7.15	182	-	-	-	-	-	-	-	-	40	88	-	-	30	66	IB-1
2	50	6.6	168	4.8	122	1.09	28	7.15	182	17.75	451	17.88	454	-	-	-	-	70	154	-	-	53	116	IB-2
3	76	8	203	5.7	145	1.41	36	8.6	218	22.75	578	23	584	-	-	-	-	150	330	-	-	113	248	IB-3
4	100	9.1	231	6.7	170	2.31	59	9.98	253	26.5	673	26.88	683	-	-	-	-	230	506	-	-	173	380	IB-3


Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figure 2515

COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 2500 (GEAR OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Ball	Cr. Steel Gr. 200, A295 Type 52100
9	Thrust Ball Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Cover Studs Environmental Seals	Buna N
22	Adjustment Cover	Carbon Steel
23	Adjustment Cover Gasket	Natural Fiber
24	Adjustment Cover Screw	Carbon Steel
25	Identification Plate*	Stainless Steel 304
26	Sealant*	Walseal #10
27	Balance Spring Ball	A295 Type 52100
28	Gear Box	Commercial Steel
29	Top Socket Screw	Carbon Steel A449 Gr. 5
30	Packing Injector	Carbon Steel

*Not Shown





COMPENSATOR PLUG VALVE REGULAR PATTERN CLASS 2500 (GEAR OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Design as per API 6D
- Fire Test as per API 6FA



Figure no.	Operation	Type of ends
2522	Gear operator	RF
2523	Gear operator	RTJ
2524	Gear operator	WE




Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions						Approx Weight			
										E						RF/RTJ		WE	
		A		B		C		D		RF		RTJ		WE					
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb
6	152	17	432	9.6	244	20	508	13.5	343	36	914	36.5	927	-	-	770	1694	578	1271
8	203	19.5	495	11.8	300	30	762	17.8	452	40.25	1022	40.88	1038	-	-	1013	2229	760	1671

Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figure 2525

COMPENSATOR PLUG VALVE VENTURI PATTERN



Design Features

- ① Stem Sealing System - the stem is protected two ways. The weather seal protects it from external attack. High temperature soft packing protects the stem against internal leakage.
- ② Balancing Spring - the mechanical spring type grade 304 Stainless Steel is under compression and holds the plug in an equalized pressure position, thus eliminating the possibility of plug taper lock.
- ③ Isolated Sealant Chamber - the sealant's function is to provide a backup to the positively biased surface between the plug and the body.
- ④ Plug - the mechanically balanced plug has a permanently bonded PERFLO coating for a very low coefficient of friction. Operating torque remains low over the 4,000 cycle test life of the valve.
- ⑤ Plug Adjustment - the steel plug is mechanically loaded into the body to put tension on the balance spring and is then adjusted for optimum balance and performance. The adjustment screw is covered to prevent tampering and possible misadjustment.

* End to End Dimension as per ASME B16.10 to meet Venturi Pattern Length


COMPENSATOR PLUG VALVE VENTURI PATTERN CLASS 150 (GEAR OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Spherical Disc	Alloy Steel AISI 4140
9	Thrust Spherical Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve*	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Cover Studs Environmental Seals	Buna N
22	Adjustment Cover	Carbon Steel
23	Adjustment Cover Gasket	Natural Fiber
24	Adjustment Cover Screw	Carbon Steel
25	Identification Plate*	Stainless Steel 304
26	Sealant*	Walseal #10
27	Balance Check valve	Commercial Steel
28	Gear Box	Commercial Steel
29	Top Socket Screw	Carbon Steel A449 Gr. 5
30	Packing Injector	Carbon Steel

*Not Shown

(1) Valves from 1/2" to 1 1/2" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WCB.





COMPENSATOR PLUG VALVE VENTURI PATTERN CLASS 150 (GEAR OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Design as per API 6D
- Fire Test as per API 6FA

Figure no.	Operation	Type of ends
1622	Gear operator	RF
1624	Gear operator	WE



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions						Approx Weight			
										E						RF/RTJ		WE	
		A		B		C		D		RF		RTJ		WE					
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb
14	350	20	508	14	356	30	762	18	457	27	686	27.5	699	27	686	460	1012	345	759
16	400	25	635	13	330	20	508	20	508	30	762	30.7	775	30	762	725	1595	545	1199

Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figure 1625


COMPENSATOR PLUG VALVE VENTURI PATTERN CLASS 300 (WRENCH OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Spherical Disc	Alloy Steel AISI 4140
9	Thrust Spherical Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Stem Environmental Seal	Elastomer
22	Cover Studs Environmental Seals	Buna N
23	Stop Collar	Carbon Steel
24	Stop Pin	Carbon Steel
25	Retainer	Carbon Steel
26	Adjustment Cover	Carbon Steel
27	Adjustment Cover Gasket	Natural Fiber
28	Adjustment Cover Screw	Carbon Steel
29	Identification Plate*	Stainless Steel 304
30	Sealant*	Walseal #10
31	Balance Check Valve	Commercial Steel
32	Wrench	Carbon Steel
33	Packing Injector	Carbon Steel

*Not Shown

(1) Valves from ½" to 1 ½" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WC6.





COMPENSATOR PLUG VALVE VENTURI PATTERN CLASS 300 (WRENCH OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Design as per API 6D
- Fire Test as per API 6FA

Figure no.	Operation	Type of ends
3612	Wrench	RF
3613	Wrench	RTJ
3614	Wrench	WE



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions						Approx Weight				Wrench No.
										E						RF/RTJ		WE		
		A		B		C		D		RF		RTJ		WE						
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb	
6	150	9.45	240	6.33	161	1.99	51	7.62	194	15.87	403	16.5	419	18	457	75	165	56	123	IB-3
8	200	10.5	267	7.81	198	1.99	51	8.75	222	16.5	419	17.12	435	20.5	521	120	264	96	211	IB-3

Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figure 3615


COMPENSATOR PLUG VALVE VENTURI PATTERN CLASS 300 (GEAR OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Spherical Disc	Alloy Steel AISI 4140
9	Thrust Spherical Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Cover Studs Environmental Seals	Buna N
22	Adjustment Cover	Carbon Steel
23	Adjustment Cover Gasket	Natural Fiber
24	Adjustment Cover Screw	Carbon Steel
25	Identification Plate*	Stainless Steel 304
26	Sealant*	Walseal #10
27	Balance Check Valve	Commercial Steel
28	Gear Box	Commercial Steel
29	Top Socket Screw	Carbon Steel A449 Gr. 5

*Not Shown

(1) Valves from 1/2" to 1 1/2" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WC6.





COMPENSATOR PLUG VALVE VENTURI PATTERN CLASS 300 (GEAR OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Design as per API 6D
- Fire Test as per API 6FA

Figure no.	Operation	Type of ends
3622	Gear operator	RF
3624	Gear operator	RTJ
3624	Gear operator	WE



Dimensions and Weights


Nominal Size		General Dimensions								End to End Dimensions						Approx Weight			
										E						RF/RTJ		WE	
		A		B		C		D		RF		RTJ		WE					
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb
6	150	11.37	289	6.33	161	20	508	7.62	194	15.87	403	16.5	419	18	457	102	224	85	187
8	200	11.94	303	7.81	198	20	508	8.75	222	16.5	419	17.12	435	20.5	521	150	330	115	253
10	250	16.28	414	10.25	260	30	762	11.75	298	18	457	18.62	473	22	559	310	682	256	563
12	300	18.07	459	13.25	337	30	762	12.87	327	19.75	502	20.37	518	25	635	402	884	335	737
14	350	19.5	495	13.38	340	30	762	23	584	30	762	30.62	778	30	762	639	1406	530	1166
16	400	23.25	591	14.31	363	20	508	25.5	648	33	838	33.62	854	33	838	825	1815	670	1474
20	500	24.75	629	18.12	460	30	762	30.5	775	39	991	39.75	1010	39	991	1516	3335	1340	2948
24	600	30.3	770	21.12	536	30	762	36	914	45	1143	45.87	1165	45	1143	2465	5423	2200	4840

Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figure 3625

COMPENSATOR PLUG VALVE VENTURI PATTERN CLASS 600 (WRENCH OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Spherical Disc	Alloy Steel AISI 4140
9	Thrust Spherical Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Stem Environmental Seal	Elastomer
22	Cover Studs Environmental Seals	Buna N
23	Stop Collar	Carbon Steel
24	Stop Pin	Carbon Steel
25	Retainer	Carbon Steel
26	Adjustment Cover	Carbon Steel
27	Adjustment Cover Gasket	Natural Fiber
28	Adjustment Cover Screw	Carbon Steel
29	Identification Plate*	Stainless Steel 304
30	Sealant*	Walseal #10
31	Balance Check Valve	Commercial Steel
32	Wrench	Carbon Steel
33	Packing Injector	Carbon Steel



*Not Shown



(1) Valves from ½" to 1 ½" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WCB.

COMPENSATOR PLUG VALVE VENTURI PATTERN CLASS 600 (WRENCH OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Design as per API 6D
- Fire Test as per API 6FA

Figure no.	Operation	Type of ends
6612	Wrench	RF
6613	Wrench	RTJ
6614	Wrench	WE



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions						Approx Weight				Wrench No.
										E						RF/RTJ		WE		
		A		B		C		D		RF		RTJ		WE						
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb	
6	150	11.9	302	7.19	183	1.99	51	9.12	232	22	559	22.12	562	22	559	157	345	120	264	IB-3

Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figure 6615


COMPENSATOR PLUG VALVE VENTURI PATTERN CLASS 600 (GEAR OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Spherical Disc	Cr. Steel Gr. 200, A295 Type 52100
9	Thrust Spherical Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Cover Studs Environmental Seals	Buna N
22	Adjustment Cover	Carbon Steel
23	Adjustment Cover Gasket	Natural Fiber
24	Adjustment Cover Screw	Carbon Steel
25	Identification Plate*	Stainless Steel 304
26	Sealant*	Walseal #10
27	Balance Check Valve	A295 Type 52100
28	Gear Box	Commercial Steel
29	Top Socket Screw	Carbon Steel A449 Gr. 5

*Not Shown

(1) Valves from ½" to 1 ½" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WC6.





COMPENSATOR PLUG VALVE VENTURI PATTERN CLASS 600 (GEAR OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Design as per API 6D
- Fire Test as per API 6FA

Figure no.	Operation	Type of ends
6622	Gear operator	RF
6624	Gear operator	RTJ
6624	Gear operator	WE



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions						Approx Weight			
										E						RF/RTJ		WE	
		A		B		C		D		RF		RTJ		WE					
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb
6	150	11.9	302	7.19	183	20	508	9.12	232	22	559	22.12	562	22	559	185	407	150	330
8	200	13.53	344	8.56	217	20	508	10.5	267	26	660	26.12	664	26	660	277	609	208	458
10	250	14.5	368	12.31	313	30	762	12	305	31	787	31.12	791	31	787	455	1001	340	748
12	300	18.84	479	14	356	30	762	13.37	340	33	838	33.12	841	33	838	615	1353	460	1012
14	350	23.37	594	23.37	594	20	508	18.25	464	35	889	35.12	892	35	889	835	1837	630	1386
16	400	24.62	625	24.62	625	30	762	23	584	39	991	39.12	994	39	991	1460	3212	950	2090
18	450	24.1	612	24.1	612	30	762	31.87	809	43	1092	43.12	1095	43	1092	2045	4499	1715	3773
20	500	25.12	638	25.12	638	30	762	33.5	851	47	1194	47.25	1200	47	1194	2475	5445	2090	4598
24	600	36.37	924	36.37	924	30	762	42	1067	55	1397	55.37	1407	55	1397	4515	9933	4020	8844

Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figure 6625


COMPENSATOR PLUG VALVE VENTURI PATTERN CLASS 900 (GEAR OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	ASTM A 216 Gr. WCB / A395 Gr. 60-40-18
3	Cover	A515 Gr. 70
4	Stem	Stainless Steel A276 Type 410
5	Gland	A515 Gr. 70
6	Diaphragm	Stainless Steel A167 Type 304
7	Adjustment Screw	Alloy Steel A322 Gr. 4140
8	Thrust Spherical Disc	Cr. Steel Gr. 200, A295 Type 52100
9	Thrust Spherical Seat	Alloy Steel AISI 4140
10	Thrust Button	Carbon Steel
11	Cover Studs	Alloy Steel A193 Gr. B7
12	Cover Stud Nuts	Carbon Steel A194 Gr. 2H
13	Gland Screw	Carbon Steel A449 Gr. 5
14	Stem Packing	Graphite
15	Balance Spring	Stainless Steel
16	Stem to Plug Coupling	Alloy Steel A322 Gr. 4140
17	Plug Check Valve	Commercial Steel
18	Sealant Check Valve	Commercial Steel
19	Sealant Injection Fitting	Commercial Steel
20	Cover Gasket	Soft Steel
21	Cover Studs Environmental Seals	Buna N
22	Adjustment Cover	Carbon Steel
23	Adjustment Cover Gasket	Natural Fiber
24	Adjustment Cover Screw	Carbon Steel
25	Identification Plate*	Stainless Steel 304
26	Sealant*	Walseal #10
27	Balance Check Valve	A295 Type 52100
28	Gear Box	Commercial Steel
29	Top Socket Screw	Carbon Steel A449 Gr. 5
30	Packing Injector	Carbon Steel

*Not Shown

(1) Valves from 1/2" to 1 1/2" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WCB.





COMPENSATOR PLUG VALVE VENTURI PATTERN CLASS 900 (GEAR OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Design as per API 6D
- Fire Test as per API 6FA

Figure no.	Operation	Type of ends
9622	Gear operator	RF
9624	Gear operator	RTJ
9624	Gear operator	WE




Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions						Approx Weight			
										E						RF/RTJ		WE	
		A		B		C		D		RF		RTJ		WE					
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb
10	250	19.25	489	12.81	325	20	508	12.25	311	33	838	33.12	841	33	838	540	1188	450	990
12	300	22.03	560	14.87	378	30	762	14.125	359	38	965	38.12	968	38	965	920	2024	600	1320
16	400	24.8	630	17.75	451	30	762	18.25	464	44.5	1130	44.8	1140	44.5	1130	2000	4400	1740	3828

Note: The same range of valves is available with Flanged by Butt-weld end (RF x WE) with the figure 9625

TOP ENTRY PLUG VALVE SHORT PATTERN

WALWORTH Top Entry Cast Steel Plug valves provide safe, reliable, long life service at an economical price. The taper of the plug and seat maintains an intimate working contact between the two parts at all times, and with the proper lubricant, the valve seals drop tight from zero to full rated differential pressure.



Design Features

- ① Sealant Fitting – fast sealant injection that can be removed under pressure. The system includes ball check valves that prevent back pressure and maintain pressure in the sealant cavity.
 - ② Balancing Spring - the mechanical spring type grade 304 Stainless Steel washer is under compression and holds the plug in an equalized pressure position, thus eliminating the possibility of plug taper lock.
 - ③ Sealant Grooves - this system permits sealant injection while the valve is under full line pressure. WALWORTH recommends that the valves be lubricated, with the plug in the fully opened or fully closed position for optimum valve performance.
 - ④ Open/Close Indicator - quarter turn stop collar also functions as an indicator of the plug's position.
 - ⑤ Diaphragm Gasket - ensures a complete sealing of the valve against any leakage.
 - ⑥ Plug - WALWORTH plugs are designed with a specific coating material that reduces the coefficient of friction, making the valve operate with low torque.
- * End to End Dimension as per ASME B16.10 to meet short Pattern Length



SHORT PATTERN

Provides face to face dimensions that match gate valves.



REGULAR PATTERN

Offers the largest port opening in a trapezoidal configuration – close to a full pipe size.



VENTURI PATTERN

Has a smaller port than the other two patterns. Is lower in cost and flow contours maximize hydraulic efficiency.


TOP ENTRY PLUG VALVE SHORT PATTERN CLASS 150 (WRENCH OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	STM A 216 Gr. WCB/ A395 Gr.60-40-18
3	Retainer	Carbon Steel A216 Gr. WCB
4	Gland	Carbon Steel A216 Gr. WCB
5	Retainer Bolting	B7 Alloy Steel Studs
6	Gland Bolting	B7 Alloy Steel Studs
7	Diaphragm	Stainless Steel Type 410
8	Diaphragm Gasket	Non-asbestos composite
9	Packing	Alloy Steel O'ring Retainer Sleeve with Buna-N O'ring
10	Packing Retainer	Steel
11	Plug Check Valve	Steel
12	Sealant Fitting	Steel
13	Stop Collar	Steel
14	Collar Retainer	Steel
15	Wrench	Carbon Steel
16	Spring	Stainless Steel
17	Spring Washer	Steel
18	Seal	Nitrile (Buna-N)
19	Stop Post	Steel
20	Identification Plate*	Stainless Steel 304

*Not Shown

(1) Valves from ½" to 1 ½" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WC6.





TOP ENTRY PLUG VALVE SHORT PATTERN CLASS 150 (WRENCH OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Threaded Dimensions conform to ANSI/ASME B1.20.1
- Design as per API 6D



Figure no.	Operation	Type of ends
1749F	Wrench	RF
1750	Wrench	THREADED



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions				Approx Weight				Wrench No.
										E				RF/RTJ		THREADED		
		A		B		C		D		RF		THREADED						
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb	
1	25	6.87	174	2.12	54	1.22	31	3.12	79	-	-	-	-	6	13	4	9	IH-2
1 1/2	38	7.62	194	2.5	64	1.41	36	3.75	95	-	-	-	-	11	24	8	18	IH-3
2	50	9	229	3	76	1.6	41	4.25	108	7	178	7.75	197	16	35	12	26	IH-4
2 1/2	63	9.87	251	3.75	95	1.6	41	4.25	108	7.5	191	10	254	22	48	16	35	IH-4
3	80	10.87	276	4.37	111	1.94	49	5.25	133	8	203	10	254	32	70	25	55	IH-6
4	100	10.87	276	4.87	124	1.94	49	7	178	9	229	11.5	292	44	97	34	75	IA-1
6	150	14.62	371	5.62	143	2.31	59	8.5	216	10.5	267	-	-	63	139	-	-	IA-2
8	200	16.75	425	7.12	181	2.62	67	10	254	11.5	292	-	-	104	229	-	-	IA-3


TOP ENTRY PLUG VALVE SHORT PATTERN CLASS 300 (WRENCH OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	STM A 216 Gr. WCB/ A395 Gr.60-40-18
3	Retainer	Carbon Steel A216 Gr. WCB
4	Gland	Carbon Steel A216 Gr. WCB
5	Retainer Bolting	B7 Alloy Steel Studs
6	Gland Bolting	B7 Alloy Steel Studs
7	Diaphragm	Stainless Steel Type 410
8	Diaphragm Gasket	Non-asbestos composite
9	Packing	Alloy Steel O'ring Retainer Sleeve with Buna-N O'ring
10	Packing Retainer	Steel
11	Plug Check Valve	Steel
12	Sealant Fitting	Steel
13	Stop Collar	Steel
14	Collar Retainer	Steel
15	Wrench	Carbon Steel
16	Spring	Stainless Steel
17	Spring Washer	Steel
18	Seal	Nitrile (Buna-N)
19	Stop Post	Steel
20	Identification Plate*	Stainless Steel 304

*Not Shown



(1) Valves from ½" to 1 ½" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WC6.



TOP ENTRY PLUG VALVE SHORT PATTERN CLASS 300 (WRENCH OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Threaded Dimensions conform to ANSI/ASME B1.20.1
- Design as per API 6D




Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions				Approx Weight				Wrench No.
										E				RF/RTJ		THREADED		
		A		B		C		D		RF		THREADED						
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb	
1/2	13	6.25	159	1.75	44	1.1	28	3.12	79	-	-	-	-	-	-	4	9	IH-1
3/4	19	6.25	159	1.75	44	1.1	28	3.12	79	-	-	-	-	-	-	4	9	IH-1
1	25	6.87	174	2	51	1.22	31	3.12	79	6.25	159	4.5	114	10	22	6	13	IH-2
1 1/2	38	7.62	194	2.5	64	1.41	36	3.75	95	7.5	190	6.69	170	14	31	8	18	IH-3
2	50	9	229	3	76	1.6	41	4.25	108	8.5	216	7.75	197	19	42	12	26	IH-4
2 1/2	63	9.62	244	3.75	95	1.6	41	4.25	108	9.5	241	10	254	26	57	17	37	IH-4
3	80	10.87	276	4.37	111	1.94	49	5.25	133	11.12	283	10	-	48	106	15	33	IH-6
4	100	11.12	282	4.87	124	1.94	49	7	178	12	305	-	-	57	125	-	-	IA-1

TOP ENTRY PLUG VALVE REGULAR PATTERN

WALWORTH Top Entry Cast Steel Plug valves provide safe, reliable, and long life service at an economical price. The taper of the plug and seat maintains an intimate working contact between the two parts at all times, and with the proper lubricant, the valve seals drop tight from zero to full rated differential pressure.



Design Features

- ① Sealant Fitting - fast sealant injection that can be removed under pressure. The system includes ball check valves that prevent back pressure and maintain pressure in the sealant cavity.
- ② Balancing Spring - the mechanical spring type grade 304 Stainless Steel washer is under compression and holds the plug in an equalized pressure position, thus eliminating the possibility of plug taper lock.
- ③ Sealant Grooves - this system permits sealant injection while the valve is under full line pressure. WALWORTH recommends that the valves be lubricated with the plug in the fully opened or fully closed position for optimum valve performance.
- ④ Open/Close Indicator - quarter turn stop collar also functions as an indicator of the plug's position.
- ⑤ Diaphragm Gasket - ensures a complete sealing of the valve against any leakage.
- ⑥ Plug - WALWORTH plugs are designed with a specific coating material that reduces the coefficient of friction, making the valve operate with low torque.

* End to End Dimension as per ASME B16.10 to meet Regular Pattern Length


TOP ENTRY PLUG VALVE REGULAR PATTERN CLASS 600 (WRENCH OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	STM A 216 Gr. WCB/ A395 Gr.60-40-18
3	Retainer	Carbon Steel A216 Gr. WCB
4	Gland	Carbon Steel A216 Gr. WCB
5	Retainer Bolting	B7 Alloy Steel Studs
6	Gland Bolting	B7 Alloy Steel Studs
7	Diaphragm	Stainless Steel Type 410
8	Diaphragm Gasket	Non-asbestos composite
9	Packing	Alloy Steel O'ring Retainer Sleeve with Buna-N O'ring
10	Packing Retainer	Steel
11	Plug Check Valve	Steel
12	Sealant Fitting	Steel
13	Stop Collar	Steel
14	Collar Retainer	Steel
15	Wrench	Carbon Steel
16	Spring	Stainless Steel
17	Spring Washer	Steel
18	Seal	Nitrile (Buna-N)
19	Stop Post	Steel
20	Identification Plate*	Stainless Steel 304

*Not Shown

(1) Valves from ½" to 1 ½" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WC6.




TOP ENTRY PLUG VALVE REGULAR PATTERN CLASS 600 **(WRENCH OPERATED)**

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Threaded Dimensions conform to ANSI/ASME B1.20.1
- Design as per API 6D

Figure no.	Operation	Type of ends
1748	Wrench	THREADED




Dimensions and Weights

Nominal Size		General Dimensions								END TO END DIMENSIONS		Approx Weight		Wrench No.
										E		THREADED		
		A		B		C		D		in	mm			
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	
1/2	13	6.25	159	1.75	44	1.1	28	3.25	83	4.25	108	4	9	IH-1
3/4	19	6.25	159	1.75	44	1.1	28	3.25	83	4.25	108	4	9	IH-1
1	25	6.87	174	2.12	54	1.22	31	3.25	83	4.5	114	6	13	IH-2
1 1/2	38	7.62	194	2.5	64	1.41	36	4	102	6.7	170	9	20	IH-3
2	50	9	229	3.25	83	1.6	41	5.43	138	7.75	197	14	31	IH-4

TOP ENTRY PLUG VALVE VENTURI PATTERN

WALWORTH Top Entry Cast Steel Plug valves provide safe, reliable long life service at an economical price. The taper of the plug and seat maintains an intimate working contact between the two parts at all times, and with the proper lubricant, the valve seals drop tight from zero to full rated differential pressure.



Design Features

- ① Sealant Fitting – fast sealant injection that can be removed under pressure. The system includes ball check valves that prevent back pressure and maintain pressure in the sealant cavity.
- ② Balancing Spring - the mechanical spring type grade 304 Stainless Steel washer is under compression and holds the plug in an equalized pressure position, thus eliminating the possibility of plug taper lock.
- ③ Sealant Grooves - this system permits sealant injection while the valve is under full line pressure. WALWORTH recommends that the valves be lubricated with the plug in the fully opened or fully closed position for optimum valve performance.
- ④ Open/Close Indicator - quarter turn stop collar also functions as an indicator of the plug's position.
- ⑤ Diaphragm Gasket - Ensures a complete sealing of the valve against any leakage.
- ⑥ Plug - WALWORTH plugs are designed with an specific coating material that reduces the coefficient of friction, making the valve operate with low torque.

* End to End Dimension as per ASME B16.10 to meet Venturi Pattern Length


TOP ENTRY PLUG VALVE VENTURI PATTERN CLASS 150 (GEAR OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	STM A 216 Gr. WCB/ A395 Gr.60-40-18
3	Retainer	Carbon Steel A216 Gr. WCB
4	Gland	Carbon Steel A216 Gr. WCB
5	Retainer Studs	B7 Alloy Steel Studs
6	Gland Studs	B7 Alloy Steel Studs
7	Diaphragm	Stainless Steel Type 410
8	Diaphragm Gasket	Carbon Steel A635 Gr. 1010
9	Packing	Alloy Steel O'ring Retainer Sleeve with Buna-N O'ring
10	Retainer Nuts	Carbon Steel A194 Gr. 2H
11	Gland Nuts	Carbon Steel A194 Gr. 2H
12	Plug Check Valve	Steel
13	Sealant Fitting	Steel
14	Sealant Check Valve	Commercial Steel
15	Collar Retainer	Steel
16	Gear Box Bolting	Alloy Steel
17	Spring	Stainless Steel
18	Spring Washer	Steel
19	Seal	Nitrile (Buna-N)
20	Gear Box Support	Carbon Steel
21	Identification Plate*	Stainless Steel 304
22	Gear Box	Commercial Steel

*Not Shown

(1) Valves from ½" to 1 ½" classes from 150 to 1500 with A322 Gr. 4140 or A216 Gr. WC6.




TOP ENTRY PLUG VALVE VENTURI PATTERN CLASS 150 (GEAR OPERATED)

Design Features

- Flanged Dimensions conform to ANSI/ASME B16.5, B16.34
- Design as per API 6D



Figure no.	Operation	Type of ends
1752F	Gear operator	RF



Dimensions and Weights


Nominal Size		General Dimensions						END TO END DIMENSIONS		Approx Weight	
								E			
		A		B		C		RF			
in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb
14	350	24.5	622	12.62	321	16.12	409	27	686	574	1263
16	400	24.5	622	12.62	321	16.12	409	30	762	624	1373
18	450	26.37	670	13.87	352	18	457	34	864	851	1872
20	500	28.5	724	15.5	394	19.52	496	36	914	1030	2266
24	600	30.5	775	17.25	438	21.37	543	42	1067	1690	3718
30	750	41.06	1043	20.5	521	37.25	946	-	-	3250	7150
36	900	41.75	1060	23.25	591	38.25	972	-	-	4725	10395

GAS SERVICE PLUG VALVE FIG. 1966

The WALWORTH Gas Service Plug valves were designed specially to give natural gas utility companies high quality carbon steel lubricated plug valves at a price comparable to cast iron gate valves with flanged ends.

The cast carbon steel body and ends have proved to be far superior to conventional cast iron gate valves in cases where gas lines have been subjected to ground shifting.

These WALWORTH plug valves incorporate a high strength cast iron plug. This plug is coated for long trouble-free life and low operating torque. The valves are single gland construction employing two cap screws and packing arrangements.



Design Features

- ① Sealant Fitting – fast sealant injection that can be removed under pressure. The system includes ball check valves that prevent back pressure and maintain pressure in the sealant cavity.
- ② Balancing Spring - the mechanical spring type grade 304 Stainless Steel washer is under compression and holds the plug in an equalized pressure position, thus eliminating the possibility of plug taper lock.
- ③ Sealant Grooves - this system permits sealant injection while the valve is under full line pressure. Walworth recommends that the valves be lubricated with the plug in the fully opened or fully closed position for optimum valve performance.
- ④ Open/Close Indicator - quarter turn stop collar also functions as an indicator of the plug's position.
- ⑤ Diaphragm Gasket - Ensures a complete sealing of the valve against any leakage.
- ⑥ Plug - Walworth Plugs are designed with a specific coating material that reduces the coefficient of friction, making the valve operate with low torque.



CLASS 200



CLASS 150


GAS SERVICE PLUG VALVE CLASS 200 CWP FIG. 1966 (WRENCH OPERATED)

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	Gray Iron ASTM A126 Class B
3	Plug Check Valve	Carbon Steel
4	Center Packing	Nitrile
5	Pressure Ring	RPTFE
6	Packing	Buna'-N O'Ring
7	Gland	Gray Iron ASTM A126 Class B
8	Gland Bolt	ASTM A 307 Gr. B
9	Weather Seal	Nitrile
10	Stop Collar	Stainless Steel
11	Circlip	Stainless Steel
12	Sealant Fitting	Carbon Steel
13	Wrench	Gray Iron ASTM A126 Class B
14	Spring	Stainless Steel
15	Set Screw	Alloy Steel

*Not Shown

¹ Valves from 1/2 to 1 1/2 classes from 150 to 1500 with A322 Gr. 4140




GAS SERVICE PLUG VALVE CLASS 200 CWP FIG. 1966 **(WRENCH OPERATED)**

Design Features

- Socket Weld Dimensions conform to ANSI/ASME B16.11
- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Design as per API 6D

Figure no.	Operation	Type of ends
1966SW	Wrench	SW
1966WE	Wrench	WE



Dimensions and Weights


Nominal Diameter		General dimensions								End to End Dimensions				APPROX. WIEGHT				WRENCH
										E				SW		WE		
		A		B		C		D		SW		WE						
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb	
3/4	19	3.8	97	1.62	41	3	76	0.81	21	4.5	114	-	-	3	7	-	-	D-4
1 1/4	31	4.5	114	1.94	49	3.12	79	0.91	23	5	127	-	-	8	18	-	-	D-4
2	50	4.81	122	2.56	65	3.62	92	1.06	27	-	-	7	178	-	-	7	15	G-1
3	80	6.31	160	3.12	79	4.75	121	1.37	35	-	-	8	203	-	-	13	29	M-1
4	100	7.37	187	3.87	98	5.75	146	1.5	38	-	-	9	229	-	-	22	48	P-1

GAS SERVICE PLUG VALVE FIG. 1967

The WALWORTH Gas Service Plug valves were designed specially to give natural gas utility companies high quality carbon steel lubricated plug valves at a price comparable to cast iron gate valves with flanged ends.

The cast carbon steel body and ends have proved to be far superior to conventional cast iron gate valves in cases where gas lines have been subjected to ground shifting.

These WALWORTH plug valves incorporate a high strength cast iron plug. This plug is coated for long trouble-free life and low operating torque. The valves are single gland construction employing two cap screws and packing arrangements.




Design Features

- ① Sealant Fitting – fast sealant injection that can be removed under pressure. The system includes ball check valves that prevent back pressure and maintain pressure in the sealant cavity.
- ② Balancing Spring - the mechanical spring type grade 304 Stainless Steel washer is under compression and holds the plug in an equalized pressure position, thus eliminating the possibility of plug taper lock.
- ③ Sealant Grooves - this system permits sealant injection while the valve is under full line pressure. WALWORTH recommends that the valves be lubricated with the plug in the fully opened or fully closed position for optimum valve performance.
- ④ Open/Close Indicator - quarter turn stop collar also functions as an indicator of the plug's position.
- ⑤ Diaphragm Gasket - ensures a complete sealing of the valve against any leakage.
- ⑥ Plug - Walworth plugs are designed with a specific coating material that reduces the coefficient of friction, making the valve operate with low torque.

GAS SERVICE PLUG VALVE CLASS 150 Fig. 1967 **(WRENCH OPERATED)**

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	Gray Iron ASTM A126 Class B
3	Plug Check Valve	Carbon Steel
4	Gasket	Nitrile
5	Plug Check	Carbon Steel
6	Packing	Buna'-N O'Ring
7	Gland	Gray Iron ASTM A126 Class B
8	Gland Stud	ASTM A 307 Gr. B
9	Weather Seal	Nitrile
10	Stop Collar	Stainless Steel
11	Circlip	Stainless Steel
12	Sealant Fitting	Carbon Steel
13	Wrench	Gray Iron ASTM A126 Class B
14	Spring	Stainless Steel
15	Cover Stud	ASTM A193 Gr. B7
16	Cover Stud Nut	ASTM A194 Gr. 2H
17	Gland Stud Nut	ASTM A194 Gr. 2H
18	Handwheel Pin	ASTM A568
19	Set Screw	Alloy Steel
20	Cover	Gray Iron ASTM A126 Class B
21	Identification Plate *	Stainless Steel



*Not Shown


¹ Valves from 1/2 to 1 1/2 classes from 150 to 1500 with A322 Gr. 4140

GAS SERVICE PLUG VALVE CLASS 150 Fig. 1967 (WRENCH OPERATED)

Design Features

- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Design as per API 6D

Figure no.	Operation	Type of ends
1967WE	Wrench	WE



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions		Approx. Weight		Wrench
										E		WE		
		A		B		C		D		WE				
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm			
6	19	11.75	298	6.12	155	1.5	38	8.37	213	13	330	65	143	P-3
8	31	12.81	325	7.5	191	1.75	44	9.62	244	15.5	394	94	207	R-3


GAS SERVICE PLUG VALVE CLASS 150 Fig. 1968 **(GEAR OPERATED)**

Regular Bill of Materials

No.	Description	Standard Material
1	Body	Carbon Steel A216 Gr. WCB
2	Plug ⁽¹⁾	Gray Iron ASTM A126 Class B
3	Plug Check Valve	Carbon Steel
4	Center Packing	Nitrile
5	Pressure Ring	RPTFE
6	Packing	Buna'-N O'Ring
7	Gland	Gray Iron ASTM A126 Class B
8	Gland Bolt	ASTM A 307 Gr. B
9	Weather Seal	Nitrile
10	Stop Collar	Stainless Steel
11	Circlip	Stainless Steel
12	Sealant Fitting	Carbon Steel
13	Gear Operator	Commercial Steel
14	Spring	Stainless Steel
15	Stem Extension	ASTM A322 Gr 4140
16	Base	ASTM A36
17	Cover Bolt	ASTM 193 GR. B7
18	Cover Bolt Nut	ASTM A194 GR. 2H
19	Gland Nut	ASTM A194 GR. 2H
20	Allen Screw	ASTM A 571
21	Check	Carbon Steel
22	Identification Plate*	Stainless Steel

*Not Shown

¹ Valves from 1/2 to 1 1/2 classes from 150 to 1500 with A322 Gr. 4140




GAS SERVICE PLUG VALVE CLASS 150 Fig. 1968 (WRENCH OPERATED)

Design Features

- Butt-weld Dimensions conform to ANSI/ASME B16.25
- Design as per API 6D

Figure no.	Operation	Type of ends
1968WE	Wrench	WE



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions		Approx. Weight	
										E		WE	
		A		B		C		D					
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb
6	19	19.75	502	6.12	155	17.5	445	8.37	213	13	330	87	191
8	31	19.03	483	7.5	191	17.5	445	9.62	244	15.5	394	116	255

TECHNICAL INFORMATION

PLUG VALVES WRENCHES

COMPENSATOR STEEL PLUG VALVES WRENCHES

WRENCH NUMBER	SIZE OPENING	HANDLE LENGTH	FOR USE WITH VALVES SIZE, CLASS OR FIGURE NUMBER
IB – 0	15/16" X 1 1/2"	18"	1" 600 Class 1/2", 3/4", 1" 1500 Class
IB – 1	1 1/8" X 13/16	27"	1500 Class, 1" 2500
IB – 2	1 1/2" x 1 1/8"	36"	2", 3" & 4" Class 150, 300 & 600; 2" Class 900 & 1500
IB – 3	2 1/8" x 1 7/16"	48"	6" & 8" Class 150 & 300, 6" Class 600; 3" & 4" Class 900 & 1500

TOP ENTRY STEEL PLUG VALVES WRENCHES

WRENCH NUMBER	SIZE OPENING	HANDLE LENGTH	FOR USE WITH VALVES SIZE, CLASS OR FIGURE NUMBER
IH – 1	1 7/64" X 13/16	5 1/2"	1/2" AND 3/4" 1748, 1749WE, 1760, 1760WE
IH – 2	1 1/4" X 57/64"	6"	1" 1748, 1749F, 1749WE, 1760, 1760F, 1760WE
IH – 3	1 1/2" X 1 1/64"	9"	1 1/2" 1748, 1749F, 1749WE, 1760, 1760F, 1760WE
IH – 4	1 21/32" X 1 9/64"	12"	2" 1748, 2" & 2 1/2" 1749F, 1750, 1760, 1760F, 1760WE
IH – 6	1 3/8" X 2 1/32"	18"	3" 1749F, 1749WE, 1750, 1760, 1760F, 1760WE
IA – 1	1 3/8" X 2 1/16"	25 1/8"	4" 1749F, 1749WE, 1750, 1760F, 1760WE
IA – 2	1 7/8" X 1 7/8"	24 1/8"	6" 1749F, 1760, 1760F
IA – 3	2 1/8" X 2 1/8"	40 1/8"	8" 1749F, 1760, 1760F
G – 1	1 1/16" X 1 1/16"	9"	2" 1966WE & 1966SW (Wrench size if 2" square nut is removed)
M – 1	1 3/8" x 1 3/8"	15"	3" 1966WE & 1966SW (Wrench size if 2" square nut is removed)
P – 1	1 1/2" 1 1/2"	18"	4 - 1966WE
P – 3	1 1/2" x 1 1/2"	36"	6" 1967WE
R – 3	1 3/4" X 1 3/4"	36"	8" 1967WE



TECHNICAL INFORMATION

2" SQUARE OPERATING NUTS

TOP ENTRY STEEL PLUG VALVES

OPERATING No.	RECTANGLE OPENING SIZE	VALVE	FOR USE WITH VALVE NUMBER
ON1	1 7/64" X 13/16"	1/2" & 3/4"	1748, 1760
ON2	1 1/4" X 57/64"	1"	1748, 1749F, 1760, 1760F
ON3	1 1/2" X 1 1/64"	1 1/2"	1748, 1749F, 1760, 1760F
ON4	1 21/32" X 1 9/64"	2"	1748, 1749F, 1750, 1760, 1760F
		2 1/2"	1749F, 1750, 1760, 1760F
ON10	2 1/8" X 1 7/16"	3" 4"	1749F, 1750, 1760, 1760F

COMPENSATOR STEEL PLUG VALVES

OPERATING	RECTANGLE	VALVE	FOR USE WITH VALVE NUMBER
ON7	1 1/16" X 1/2"	1"	6511 TO 6516
		1/2", 3/4"	5511 TO 5516
ON8	1 1/8" X 1 3/16"	1 1/2"	6511 TO 6516
		1 1/2"	5511 TO 5516
ON9	1 1/2" X 1 1/8"	2", 3", 4"	1412 TO 6516
		2"	9511 TO 9516
ON10	2 1/8" X 1 7/16"	6", 8"	1412 TO 3616
		6"	6512 TO 6616
		3", 4"	9511 TO 5516
ON11			ALL COMPENSATOR VALVES WITH GEAR OPERATOR

CORRESPONDING OPERATING NUT AND RECTANGLE OPENING SIZE

OPERATING No.	VALVE SIZE
ON1	1 7/64" X 13/16"
ON2	1 1/4" X 57/64"
ON3	1 1/2" X 1 1/64"
ON4	1 21/32" X 1 9/64"
ON7	1 1/16" X 1/2"
ON8	1 1/8" X 1 3/16"
ON9	1 1/2" X 1 1/8"
ON10	2 1/8" X 1 7/16"

TECHNICAL INFORMATION

WALSEAL PLUG VALVES SEALANT

FUNCTION AND PROPERTIES OF WALSEAL SEALANTS

To assure thoroughly satisfactory service, WALWORTH Walseal Sealants should always be used with WALWORTH Plug Valves.

Function: The sealant minimizes friction during operation of the valve and protects seating surfaces from corrosion. Because the ports of valves are completely encircled with sealant grooves, leakage is prevented by the Walseal sealant.

Properties: Walseal sealants have the necessary properties to serve a variety of purposes.

1. Have lubricating value to allow the valve to turn easily.
2. Have sufficient body to resist dilution by line fluids and still assure tight sealing.
3. Are chemically inert in the fluids for which they are specified, and have the ability to adhere to the metal of the finished seating surfaces to protect from corrosion.
4. Remain in a plastic state over a wide range of temperature conditions, to act as a hydraulic medium and provide for lubrication and corrosion protection.
5. Contain a minimum of ingredients that might solidify from temperature or chemical reactions and clog the groove system.

2. Color - Where discoloration of the line contents must be guarded against, select a white sealant if available. In special cases consult a WALWORTH representative.
3. Contamination - Sealant for use with foodstuffs or pharmaceuticals must be non-toxic, taste -and color- free and chemically inert.
4. Temperature - As a general rule, choose the sealant with the lowest maximum temperature rating. Such a sealant will usually have greater lubricating value at normal temperatures than one with a higher limit. This is important as it affects the ease of operation of the valve.
5. Compromise - If a sealant is required for a mixed service condition, a good practical rule is to select the sealant recommended for the predominating part of the pipeline contents.
6. Nitrating Acids - It is dangerous to use certain sealants on nitrating acids. Please contact your WALWORTH representative for this application.

Proper sealant maintenance:

The amount of maintenance required depends upon the frequency of operation of the valve.

Regular maintenance preserve the seating surfaces and prevents leakage. Definite periodic service gives the best results. Any valve not regularly operated should be serviced at least every six months.

SELECTION AND MAINTENANCE OF WALSEAL SEALANT

How to select a sealant:

1. Line Contents - Select a sealant recommended for the particular service requirements.

Ordering Information:

1. State whether jumbo, stick or bulk sealant is desired.
2. For bulk sealant, give Walseal number and container size.

STICK	STICK SIZE	AVAILABLE IN WALSEAL NO.
B (24/box)	318' X 1 1/2' (Box approx. 1.2 lb.)	10, 20, 40 and 60
C (24/box)	7/16' X 2 1/8' (Box approx. 1.2 lb.)	10, 20, 40 and 60
D (24/box)	1/2' X 2 1/4' (Box approx. 1.2 lb.)	10, 20, 40 and 60
G (24/box)	518' X 3 1/2' (Box approx. 1.2 lb.)	10, 20, 40 and 60
CARTRIDGE - (Box of 4 - 1 lb. each)		All TYPES
BULK		
J-Jumbo Jr. (6)	1 3/8' X 8 1/2' (Box approx. 3.2 lb.)	10, 20, 40 and 60
K-Jumbo (12)	1 1/2' X 10 1/2' (Box approx. 9.2 lb.)	10, 20,40 and 60
Gun Pack (Box-6 GP)		All TYPES
10 pound (5 quart can)		
40 pound (5 gallon can)		
400 pound (55 gallon drum)		

TECHNICAL INFORMATION

WALSEAL PLUG VALVES SEALANT

WALSEAL #10

Temperature range from -20F to 500F Stick / -40F to 500F Bulk

Color: dark gray

Service: General purpose sealant intended for use in natural gas and liquid petroleum services, including crude distillates combustible fuels such as gasoline, jet fuel and heating oils. Used as assembly sealant in all WALWORTH plug valves unless otherwise specified.

Not intended for use in: solvents (aromatic); strong acids; alkalies or steam.

WALSEAL #20

Temperature range from 0F to 650F Bulk / 30F to 690F Stick

Color: red

Service: High temperature general purpose sealant for use in acids, alkalis, alcohols, amines, asphalt, aqueous solutions, fats, glycerine, glycols, soap, steam, or water service having continuous exposure to temperatures above 400F.

Not intended for use in: aromatic solvents; light liquid hydrocarbons; or nitrating acids.

WALSEAL #40

Temperature range from 1 0F to 350F Stick / -10F to 350F Bulk

Color: light brown

Service: Specifically formulated for resistance to all octane gasolines, aviation and jet fuels, kerosene, fuel blending ingredients and water. Approved for government use per MIL-G-6032.

Not intended for use in: strong acids and alkalies.

WALSEAL #50

Temperature range from -50F to 300F

Color: beige

Service: Low temperature general purpose sealant for use in services similar to Walseal #10. Recommended for continuous exposure to temperatures below 0°F.

Not intended for use in: solvents (aromatic and chlorinated); strong acids and alkalies.

WALSEAL #60

Temperature range from 1 0F to 350F Stick / 0F to 300F Bulk
Service: Suitable for water, acids, alkalies, alcohols, and amines. May be used in food or pharmaceutical applications if approved by user. Certified by the National Sanitary Foundation.

Not intended for use in: hydrocarbon solvents.

Continued use of any sealant at either the low or high temperature limit is not recommended.

For more information concerning these sealants or recommendations for a particular service, contact your WALWORTH representative.

WALWORTH VALVE FLUSH

For hard-to-operate valves

-20°F to 400°F

(-28°C) (204°C) BLACK

VALVE FLUSH is not a sealant; however, it is compatible with any lubricant or sealant. It contains molybdenum disulfide for added lubricity. VALVE FLUSH may be applied with conventional lubricating equipment.

VALVE FLUSH will work through any fitting that is not completely plugged. In other words, if VALVE FLUSH cannot be injected past the fitting, it will not free the valve. If the fitting is plugged, then it is recommended that the fitting be removed and replaced with the appropriate WALWORTH fitting.

WALWORTH "VALVE FLUSH" JUMBO, JR. BAG 6/BX

WALWORTH "VALVE FLUSH" JUMBO, BAG 6/BX

WALWORTH "VALVE FLUSH" 1 CARTRIDGE 12/CTN

WALWORTH "VALVE FLUSH" 10LB. (5QT.) CAN.

WALWORTH "VALVE FLUSH" 20 LB. (3GAL.) PAIL

WALWORTH "VALVE FLUSH" 40 LB. (6GAL.) PAIL

TECHNICAL INFORMATION

ACTUATORS

Valves can be furnished with either electric, pneumatic or hydraulic actuators. The actuators can be furnished as either waterproof and/or explosion proof. The Customer must specify such things as open-close speed, maximum differential pressure, service temperature, type of voltage-phase-frequency, air or gas pressure for pneumatic actuators, and flow characteristics for hydraulic actuators to be assured of correct performance.



LUBRICANT ACCESORIES

1002 WALSEAL HYDRAULIC DELTA STICK SEALANT GUN, FOR USE WITH "K" SIZED SEALANT.

1699 HIGH PRESSURE LUBRICANT GUN

1699 G HIGH PRESSURE LUBRICANT GUN WITH GAUGE

Where a number of valves are installed under the same or related service conditions, it is advantageous to lubricate them with a **WALWORTH High Pressure Lubricant Gun**.

The Walworth High Pressure Lubricant Gun is the only portable gun that can handle full-bodied valve lubricants in stick form.

The gun is self-priming and may be used in any position. The pump handle is detachable and has a hole drilled near one end.

By detaching the handle and placing the hole over the protruding button on the charging cap, the cap can readily be removed and replaced.

The handle is also used as a pusher for returning the piston to the bottom of the cylinder for the purpose of charging the gun.

To charge the gun, the by-pass is opened and the piston pushed down as far as it will go. The by-pass valve is then closed and two

sticks of WALWORTH Jumbo Size Lubricant are inserted. Then the charging cap is replaced, using the pump handle and protruding button on the cap to tighten it, and the gun is ready for use. The lever handle is then pumped until sealant appears at the end of the hose.

During operation of the gun, if the pressure that is created locks the coupling to the button-head filling, the pressure can be relieved and the coupling disconnected by opening the bypass valve. Relief fittings are provided on the hose and within the gun to prevent damage to the valve, should the lubricating system be clogged, or to the gun itself if operated when empty.

HIGH PRESSURE GAUGE

For use with sealant hand guns and pumps. An essential accessory to indicate when sufficient sealant pressure has been developed.

Gauge needle pulsation goes up by steps until the valve is completely filled with Sealant. When Sealant pressure reaches a certain point, the gauge needle begins to drop, showing that the valve is full. Gauge also indicates valve adjustment and other service is required.



TECHNICAL INFORMATION

WALWORTH LUBRICANT FITTINGS

Most types of WALWORTH Lubricated Plug Valves are regularly provided with the WALWORTH Lubricant Fitting below illustrated. It is a Giant Button-Head Fitting to which the lubricant gun may be easily coupled for a leakproof connection. These fittings may also be used as regular lubricant screws with standard size lubricant sticks.

One size of Button-Head Fitting is used for all Compensator Plug Valves. The Button-Head figure number for other WALWORTH Plug Valves is the same as the "Sealant Stick Size" listed on the catalog page for each valve type and size.



WALWORTH BUTTON-HEAD LUBRICANT FITTINGS	LUBRICANT FITTING SIZE	WALWORTH LUBRICANT FITTING NUMBER
For Standard Compensators	1/4"	BH1
For NACE MR0-01-75 Compensators	1/4"	BH1-N
For valves with Sealant Stick Size: B	1/4"	BH2
C	3/8	BH3
D	1/2	BH4
G	3/4	BH5

DOUBLE BALL CHECK VALVE ASSEMBLIES	
No.	Valve Size
B	1/2 to 2"
C	2 1/2 to 3"
D	4 & 5"
G	6" & up

TECHNICAL INFORMATION

BUTT WELD DIMENSIONS

NOMINAL PIPE SIZE (INCHES)	3	4	5	6	8	10	12	14	16	18	20	24
AA DIAMETER (INCHES)	3 ¹⁹ / ₃₂	4 ⁵ / ₈	5 ¹¹ / ₁₆	6 ²⁵ / ₃₂	8 ²⁵ / ₃₂	10 ¹⁵ / ₁₆	12 ³¹ / ₃₂	14 ¹⁹ / ₃₂	16 ¹⁹ / ₃₂	18 ¹⁹ / ₃₂	20 ¹⁹ / ₃₂	24 ¹⁹ / ₃₂

ANSI STANDARD B16.25

A - Nominal outside diameter of pipe in inches.

AA- Nominal outside diameter for cast steel valves in inches (see table).

8 - Nominal inside diameter of pipe in inches. **

t - Nominal wall thickness of pipe in inches.

C - A-0.031-1.75t-0.010 in inches.

For complete dimensions, details, other configurations, and tolerances, ANSI B16.25

OUTSIDE CONTOUR

When the thickness of the welding end of the valve is greater than that of the mating pipe, and when the additional thickness increases the outside diameter, a taper weld having a slope not exceeding 1:3 may be employed or the greater outside diameter may be extended back in a manner within the maximum slope lines indicated in Figs. 1A and 1B. The transition shall be of a shape avoiding sharp reentrant angles and abrupt changes in slope. The profile of the outside contour shall be at the manufacturer's option provided above conditions are met.

INSIDE CONTOUR

For a joint without a continuous backing ring, the inside contour of the valve end shall be bored to a diameter B to a depth of 1/2" min. The inside diameter of a valve end beyond this machined surface may be either larger or smaller than the inside diameter of the pipe. The transition shall be of a shape avoiding sharp re-entrant angles and abrupt changes in slope. See Figs. 1A and 1B. (Transition shape also applies to Figs. 2 and 3).

For a joint with a continuous rectangular backing ring, the contour of the valve end shall be a straight bore of diameter C, 1/2 in. deep. This depth is based on a backing ring 3/4 in. wide; but if a wider ring is used, the depth shall be increased to provide the 1/8 in. minimum end clearance indicated. See Fig. 2.

For a joint with a continuous tapered backing ring, the inside contour of the valve end shall be taper bored from diameter C at the lip tapering at 10 deg to a taper length of 7/32 in minimum. Beyond this taper length the bore may be extended to the inside port diameter. See Fig. 3

*See Figs. 1A and 1 for Outside Contours.

** Tolerances for B : NPS 10 and Smaller: +0.03"; NPS 12 to 18: ± 0.06"; NPS 20 to 24: +0.12, - 0.06"

BORES: WALWORTH's standard practice for Class 150 and 300 cast steel valves is that butt welding ends be machined in accordance with Figs. 1A and 1B, bored to match the inside diameters of Schedule 40 pipe in sizes 12-inch and smaller, and of 0.375 inch Standard Wall Pipe in larger sizes, unless otherwise specified. Orders for all sizes of Class 600 and higher must specify the diameter of valves bore, type of backing ring, etc.




Fig. 1A.- Welding End for No Backing Ring or for Split Backing Ring. Pipe Wall Thickness "t" 7/8" and less.




Fig. 1B.- Welding End for No backing Ring or for Split Backing Ring. Pipe Wall Thickness "t" Greater Than 7/8"




Fig. 2.- Welding End for Continuous Rectangular Backing Ring (inside contour).*





Fig. 3.- Welding End for Continuous Rectangular Backing Ring (inside contour).*

TECHNICAL INFORMATION

FLANGE DIMENSIONS AND TEMPLATES

STEEL FLANGE DIMENSIONS AND DRILLING TEMPLATES ANSI B 16.5



CLASS 150 AND 300



LENGTH OF STUD BOLT



LENGTH OF MACHINE BOLT

CLASS 150

NOMINAL PIPE SIZE	FLANGE DIAMETER A	FLANGE THICKNESS		DIAMETER OF RAISED FACE C	DIAMETER OF VOLT CIRCLE D	DIAMETER OF BOLT HOLES E	NUMBER OF BOLTS	DIAMETER OF BOLTS	LENGTH OF STUD BOLTS F	LENGTH OF MACHINE G
		COMPANION FLANGE B	VALVE FLANGE B							
1	4 1/2	9/16	7/16	2	3 1/8	5/8	4	1/2	2 1/2	2 1/4
1 1/2	5	11/16	9/6	2 7/8	3 7/8	5/8	4	1/2	2 3/4	2 1/2
2	6	3/4	5/8	3 5/8	4 3/4	3/4	4	5/8	3 1/4	2 3/4
2 1/2	7	7/8	11/16	4 1/8	5 1/2	3/4	4	5/8	3 1/4	3
3	7 1/2	15/16	3/4	5	6	3/4	4	5/8	3 1/2	3
4	9	15/16		6 3/16	7 1/2	3/4	8	5/8	3 1/2	3
6	11	1		8 1/2	9 1/2	7/8	8	3/4	4	3 1/4
8	13 1/2	1 1/8		10 5/8	11 3/4	7/8	8	3/4	4 1/4	3 1/2
10	16	1 3/16		12 3/4	14 1/4	1	12	7/8	4 1/2	4
12	19	1 1/4		15	17	1	12	7/8	4 3/4	4
14	21	1 3/8		16 1/4	18 3/4	1 1/8	12	1	5 1/4	4 1/2
16	23 1/2	1 7/16		18 1/2	21 1/4	1 1/8	16	1	5 1/4	4 1/2
18	25	1 9/16		21	22 3/4	1 1/4	16	1 1/8	5 3/4	5
20	27 1/2	1 11/16		23	25	1 1/4	20	1 1/8	6 1/4	5 1/2
24	32	1 7/8		27 1/4	29 1/2	1 3/8	20	1 1/4	6 3/4	6

CLASS 300

NOMINAL PIPE SIZE	FLANGE DIAMETER A	FLANGE THICKNESS B	DIAMETER OF RAISED FACE C	DIAMETER OF VOLT CIRCLE D	DIAMETER OF BOLT HOLES E	NUMBER OF BOLTS	DIAMETER OF BOLTS	LENGTH OF STUD BOLTS F	LENGTH OF MACHINE G
1/2	3 3/4	9/16	1 3/8	2 5/8	5/8	4	1/2	2 1/2	2 1/4
3/4	4 5/8	5/8	1 11/16	3 1/4	3/4	4	5/8	3	2 1/2
1	4 7/8	11/16	2	3 1/2	3/4	4	5/8	3	2 1/2
1 1/4	5 1/4	3/4	2 1/2	3 7/8	3/4	4	5/8	3 3/4	2 3/4
1 1/2	6 1/8	13/16	2 7/8	4 1/2	7/8	4	3/4	3 1/2	3
2	6 1/2	7/8	3 5/8	5	3/4	8	5/8	3 1/2	3
2 1/2	7 1/2	1	4 1/8	5 7/8	7/8	8	3/4	4	3 1/4
3	8 1/4	1 1/8	5	6 5/8	7/8	8	3/4	4 1/2	3 1/2
4	10	1 1/4	6 3/16	7 7/8	7/8	8	3/4	4 1/2	3 3/4
5	11	1 3/8	7 5/16	9 1/4	7/8	8	3/4	4 3/4	4 1/4
6	12 1/2	1 7/16	8 1/2	10 5/8	7/8	12	3/4	4 3/4	4 1/4
8	15	1 5/8	10 5/8	13	1	12	7/8	5 1/2	4 3/4
10	17 1/2	1 7/8	12 3/4	15 1/4	1 1/8	16	1	6	5 1/2
12	20 1/2	2	15	17 3/4	1 1/4	16	1 1/8	6 3/4	5 3/4
14	23	2 1/8	16 1/4	20 1/4	1 1/4	20	1 1/8	7	6 1/4
16	25 1/2	2 1/4	18 1/12	22 1/2	1 3/8	20	1 1/4	7 1/2	6 1/2
18	28	2 3/8	21	24 3/4	1 3/8	24	1 1/4	7 3/4	6 3/4
20	30 1/2	2 1/2	23	27	1 3/8	24	1 1/4	8	7 1/4
24	36	2 3/4	27 1/4	32	1 5/8	24	1 1/2	9	8

The regular 1/16-inch raised face of Class 150 and 300 flanges is included in the minimum flange thickness given above, but other raised faces must be added thereto. Class 150 loose flanges are thicker than integral flanges for sizes 3" inch and smaller. Note Column B.

Lengths of stud bolts do not include the height of the points.

Bolt lengths not shown in the tables can be determined by reference to Appendix F of ANSI B16.5-1981.




When flanges are integral with valves, the bolt holes which are in multiples of four are drilled to straddle the center line unless otherwise ordered.

TECHNICAL INFORMATION

FLANGE DIMENSIONS AND TEMPLATES

CLASS 600

NOMINAL PIPE SIZE	FLANGE DIAMETER A	FLANGE THICKNESS B	DIAMETER OF RAISED FACE C	DIAMETER OF VOLT CIRCLE D	DIAMETER OF BOLT HOLES E	NUMBER OF STUD BOLTS	DIAMETER OF STUD BOLTS	LENGTH OF STUD BOLTS WITH 2 NUTS	
								F	G
1	4 7/8	1 1/16	2	3 1/2	3/4	4	5/8	3 1/2	3 1/4
1 1/2	6 1/8	7/8	2 7/8	4 1/2	7/8	4	3/4	4 1/4	4
2	6 1/2	1	3 5/8	5	3/4	8	5/8	4 1/4	4
3	8 1/4	1 1/4	5	6 5/8	7/8	8	3/4	5	4 3/4
4	10 3/4	1 1/2	6 3/16	8 1/2	1	8	7/8	5 3/4	5 1/2
6	14	1 7/8	8 1/2	11 1/2	1 1/8	12	1	6 3/4	6 1/2
8	16 1/2	2 3/16	10 5/8	13 3/4	1 1/4	12	1 1/8	7 1/2	7 1/4
10	20	2 1/2	12 3/4	17	1 3/8	16	1 1/4	8 1/2	8 1/4
12	22	2 5/8	15	19 1/4	1 3/8	20	1 1/4	8 3/4	8 1/2
14	23 3/4	2 3/4	16 1/4	20 3/4	1 1/2	20	1 3/8	9 1/4	9
16	27	3	18 1/2	23 3/4	1 5/8	20	1 1/2	10	9 3/4
18	29 1/4	3 1/4	21	25 3/4	1 3/4	20	1 5/8	10 3/4	10 1/2
20	32	3 1/2	23	28 1/2	1 3/4	24	1 5/8	11 1/4	11
24	37	4	27 1/4	33	2	24	1 7/8	13	12 3/4



STUD BOLT LENGTH "G" ALSO APPLIES FOR TONGUE TO GROOVE FLANGED JOINT

CLASS 900

NOMINAL PIPE SIZE	FLANGE DIAMETER A	FLANGE THICKNESS B	DIAMETER OF RAISED FACE C	DIAMETER OF VOLT CIRCLE D	DIAMETER OF BOLT HOLES E	NUMBER OF STUD BOLTS	DIAMETER OF STUD BOLTS	LENGTH OF STUD BOLTS WITH 2 NUTS	
								F	G
3*	9 1/2	1/12	5	7 1/2	1	8	7/8	5 1/2	5 1/4
4	11 1/2	1 3/4	6 3/16	9 1/4	1 1/4	8	1 1/8	6 1/2	6 1/4
6	15	2 3/16	8 1/2	12 1/2	1 1/4	12	1 1/8	6 1/2	6 1/4
8	18 1/2	2 1/2	10 5/8	15 1/2	1 1/2	12	1 3/8	8 1/2	8 1/4
10	21 1/2	2 3/4	12 3/4	18 1/2	1 1/2	16	1 3/8	8 1/2	8 1/4
12	24	3 1/8	15	21	1 1/2	20	1 3/8	9 3/4	9 1/2
16	27 3/4	3 1/2	18 1/2	24 1/4	1 3/4	20	1 5/8	11	10 3/4

* Use Class 1500 dimensions in sizes smaller than 3-inch.

CLASS 1500

NOMINAL PIPE SIZE	FLANGE DIAMETER A	FLANGE THICKNESS B	DIAMETER OF RAISED FACE C	DIAMETER OF VOLT CIRCLE D	DIAMETER OF BOLT HOLES E	NUMBER OF STUD BOLTS	DIAMETER OF STUD BOLTS	LENGTH OF STUD BOLTS WITH 2 NUTS	
								F	G
1	5 7/8	1 1/8	2	4	1	4	7/8	5	4 3/4
2	8 1/2	1 1/2	3 5/8	6 1/2	1	8	7/8	5 3/4	5 1/2
3	10 1/2	1 7/8	5	8	1 1/4	8	1 1/8	7	6 3/4
4	12 1/4	2 1/8	6 3/16	9 1/2	1 3/8	8	1 1/4	7 3/4	7 1/2
6	15 1/2	3 1/4	8 1/2	12 1/2	1 1/2	12	1 3/8	10	9 3/4
8	19	3 5/8	10 5/8	15 1/2	1 3/4	12	1 5/8	11 1/4	11

The regular 1/4-inch raised face of class 600, 900 and 1500 flanges is not included in the minimum flange thickness given above.

The addition of any facing is beyond the outside edge of the flange.

Lengths of steel stud bolts do not include the height of the points.





Bolt lengths not shown in the tables can be determined by reference to Appendix F of ANSI B 16.5- 1961.

When flanges are integral with valves, the bolt holes, which are in multiples of four, are drilled to straddle the center line unless otherwise ordered.

TECHNICAL INFORMATION

FLANGE DIMENSIONS AND TEMPLATES

CAST IRON FLANGE DIMENSIONS AND DRILLING TEMPLATES ANSI B 16.5



CLASS 125

NOMINAL PIPE SIZE	FLANGES		DRILLING		BOLTING		LENGTH OF MACHINE BOLTS F
	FLANGE DIAMETER A	FLANGE THICKNESS MIN B	DIAMETER OF VOLT CIRCLE D	DIAMETER OF BOLT HOLES E	NUMBER OF BOLTS	DIAMETER OF BOLTS	
1	4 1/4	7/16	3 1/8	5/8	4	1/2	1 3/4
1 1/4	4 5/8	1/2	3 1/2	5/8	4	1/2	2
1 1/2	5	9/16	3 7/8	5/8	4	1/2	2
2	6	5/8	4 3/4	3/4	4	5/8	2 1/4
2 1/2	7	3/4	5 1/2	3/4	4	5/8	2 1/2
3	7 1/2	15/16	6	3/4	4	5/8	2 1/2
4	9	15/16	7 1/2	3/4	8	5/8	3
5	10	15/16	8 1/2	7/8	8	3/4	3
6	11	1	9 1/2	7/8	8	3/4	3 1/4
8	13 1/2	1 1/8	11 3/4	7/8	8	3/4	3 1/2
10	16	1 3/16	14 3/4	1	12	7/8	3 3/4
12	19	1 1/4	17	1	12	7/8	3 3/4

Bolt lengths are for flanges of thickness shown herein. Bolt lengths should be checked for the thicker flanges shown in some individual valve description pages. When flanges are integral with valves or fittings, the bolt holes, which are in multiples of four, are drilled to straddle the center lines unless otherwise ordered. Class 125 cast iron flanges have plain faces.

CLASS 250

NOMINAL PIPE SIZE	FLANGE THICKNESS			DRILLING		BOLTING		LENGTH OF MACHINE BOLTS F
	FLANGE DIAMETER A	FLANGE THICKNESS MIN B	DIAMETER OF RAISED FACE C	DIAMETER OF VOLT CIRCLE D	DIAMETER OF BOLT HOLES E	NUMBER OF BOLTS	DIAMETER OF BOLTS	
1	4 7/8	1 1/16	2 11/15	3 1/2	3/4	4	5/8	2 1/2
2	6 1/2	7/8	4 3/16	5	3/4	8	5/8	2 3/4
3	8 1/4	1 1/8	5 11/16	6 5/8	7/8	8	3/4	3 1/2
4	10	1 1/4	6 15/16	7 7/8	7/8	8	3	3 3/4

The 1/16-inch raised face on the Class 250 cast iron flanges is included in the dimension B for thickness of flange. Bolt lengths are for flanges of thickness shown herein. Bolt lengths should be checked for the thicker flanges shown in some individual valve description pages.

PRESSURE-TEMPERATURE RATINGS

CAST STEEL ASTM A 216 GR WCB

°F Temperature °C		MAXIMUM ALLOWABLE NON-SHOCK WORKING PRESSURE IN PSIG BY CLASS					
		150	300	600	900	1,500	2500
-20 a 100	-29 to 38	285	740	1,480	2,220	3,705	6,170
200	93	260	680	1,360	2,035	3,395	5,655
300	149	230	655	1,310	1,965	3,270	5,450
400	204	200	635	1,265	1,900	3,170	5,280
500	260	170	605	1,205	1,810	3,015	5,025
600	316	140	570	1,135	1,705	2,840	4,730
650	343	125	550	1,100	1,650	2,745	4,575
700	371	110	530	1,060	1,590	2,665	4,425
750	399	95	505	1,015	1,520	2,535	4,230
800	427	80	410	825	1,235	2,055	3,430
850	454	65	320	640	955	1,595	2,655
900	482	50	230	460	690	1,150	1,915
950	510	35	135	275	410	685	1,145
1,000	538	20	85	170	255	430	715

Note: Upon prolonged exposure to temperatures above 800°F, the carbide phase of steel may be converted to graphite. Permissible, but not recommended for prolonged use above 800°F.

CAST STEEL ASTM A 217 GR WC9

°F Temperature °C		MAXIMUM ALLOWABLE NON-SHOCK WORKING PRESSURE IN PSIG BY CLASS					
		150	300	600	900	1,500	2500
-20 a 100	-29 a 38	290	750	1,500	2,250	3,750	6,250
200	93	260	750	1,500	2,250	3,750	6,250
300	149	230	730	1,455	2,185	3,640	6,070
400	204	200	705	1,410	2,115	3,530	5,880
500	260	170	665	1,330	1,995	3,325	5,540
600	316	140	605	1,210	1,815	3,025	5,040
650	343	125	590	1,175	1,765	2,940	4,905
700	371	110	570	1,135	1,705	2,840	4,730
750	399	95	530	1,065	1,595	2,660	4,430
800	427	80	510	1,015	1,525	2,540	4,230
850	454	65	485	975	1,460	2,435	4,060
900	482	50	450	900	1,350	2,245	3,745
950	510	35	385	755	1,160	1,930	3,220
1,000	538	20	265	535	800	1,335	2,230
1,050	566	20(a)	175	350	525	875	1,455
1,100	593	20(a)	110	220	330	550	915
1,150	621	20(a)	70	135	205	345	570
1,200	649	15(a)	40	80	125	205	345

Notes:

- Use normalized and tempered material only.
- Not to be used over 1,100°F.
- The deliberate addition of any element not listed in ASTM A 217, Table 1 is prohibited, except that Ca and Mg may be added for deoxidation.

(a) Flanged-end valve ratings terminate at 1,000°F.

PRESSURE-TEMPERATURE RATINGS

CAST STEEL ASTM A 351 GR CF8

°F Temperature °C		MAXIMUM ALLOWABLE NON-SHOCK WORKING PRESSURE IN PSIG BY CLASS					
		150	300	600	900	1,500	2,500
-20 a 100	-29 a 38	275	720	1,440	2,160	3,600	6,000
200	93	230	600	1,200	1,800	3,000	5,000
300	149	205	540	1,075	1,615	2,690	4,480
400	204	190	495	995	1,490	2,485	4,140
500	260	170	465	930	1,395	2,330	3,880
600	316	140	440	885	1,325	2,210	3,680
650	343	125	430	865	1,295	2,160	3,600
700	371	110	420	845	1,265	2,110	3,520
750	399	95	415	825	1,240	2,065	3,440
800	427	80	405	810	1,215	2,030	3,380
850	454	65	395	790	1,190	1,980	3,300
900	482	50	390	780	1,165	1,945	3,240
950	510	35	380	765	1,145	1,910	3,180
1,000	538	20	355	710	1,065	1,770	2,950
1,050	566	20(a)	325	650	975	1,630	2,715
1,100	593	20(a)	255	515	770	1,285	2,145
1,150	621	20(a)	205	410	615	1,030	1,715
1,200	649	20(a)	165	330	495	825	1,370
1,250	677	20(a)	135	265	400	970	1,115
1,300	704	20(a)	115	225	340	565	945
1,350	732	20(a)	95	185	280	465	770
1,400	760	20(a)	75	150	225	380	630
1,450	788	20(a)	60	115	175	290	485
1,500	816	15(a)	40	85	125	205	345

Notes:

- At temperatures over 1,000°F, use only when the carbon content is 0.04% or higher.

(a) For welding ends valves only. Flanged ends ratings terminate at 1000°F (538°C).

CAST STEEL ASTM A 351 GR CF8 M

°F Temperature °C		MAXIMUM ALLOWABLE NON-SHOCK WORKING PRESSURE IN PSIG BY CLASS					
		150	300	600	900	1,500	2,500
-20 a 100	-29 a 38	275	720	1,440	2,160	3,600	6,000
200	93	235	620	1,240	1,860	3,095	5,160
300	149	215	560	1,120	1,680	2,795	4,660
400	204	195	515	1,025	1,540	2,570	4,280
500	260	170	480	955	1,435	2,390	3,980
600	316	140	450	900	1,355	2,255	3,760
650	343	125	440	885	1,325	2,210	3,680
700	371	110	435	870	1,305	2,170	3,620
750	399	95	425	855	1,280	2,135	3,560
800	427	80	420	845	1,265	2,110	3,520
850	454	65	420	835	1,255	2,090	3,480
900	482	50	415	830	1,245	2,075	3,460
950	510	35	385	775	1,160	1,930	3,220
1,000	538	20	365	725	1,090	1,820	3,030
1,050	566	20	360	720	1,080	1,800	3,000
1,100	593	20(a)	305	610	915	1,525	2,545
1,150	621	20(a)	235	475	710	1,185	1,970
1,200	649	20(a)	185	370	555	925	1,545
1,250	677	20(a)	145	295	440	735	1,230
1,300	704	20(a)	115	235	350	585	970
1,350	732	20(a)	95	190	290	480	800
1,400	760	20(a)	75	150	225	380	630
1,450	788	20(a)	60	115	175	290	485
1,500	816	15(a)	40	85	125	205	345

Notes:

- At temperatures over 1,000°F, use only when the carbon content is 0.04% or higher.

(a) For welding ends valves only. Flanged ends ratings terminate at 1000°F (538°C).

DESIGN BASIS

All of WALWORTH's Valve Designs, when applicable, follow one or more of the following standards.

API Standards	American Petroleum Institute
• API-6D	Steel gate, ball and plug valves for pipeline service
• API-6A	Wellhead and Christmas Tree Equipment
• API-6FA	Specification for Fire test for Valves
• API-598	Valve inspection and testing
• API-599	Steel and Ductile Iron Plug Valves
ANSI Standards	National Standards Institute
• B16.5	Steel pipe flanges and flanged fittings
• B16.10	Length of ferrous flanged and welding end valves
• B16.25	Butt-welding ends
• B1.20.1	Pipe Threads, General Purpose.
• B16.34	Valves - Flange, Threaded and Welding End
ASTM Standards	American Society for Testing and Materials
• ASTM A126	Gray Iron Castings For valves, flanges and pipe fittings.
• ASTM A193	Alloy-Steel and Stainless Steel Bolting Materials for High-Temperature Service
• ASTM A194	Carbon and Alloy Steel nuts for bolts for High-Pressure and High-Temperature Service
• ASTM A216	Steel Castings, Carbon, suitable for Fusion Welding for High-Temperature Service
• ASTM A276	Stainless and Heat-Resisting Steel Bars and Shapes
• ASTM A307	Carbon Steel bolts and studs , 60,000 psi Tensile
• ASTM A320	Alloys - Steel bolting materials for Low-Temperature Service.
• ASTM A352	Steel Castings, Ferritic and Martensitic, for Pressure-Containing Parts. Suitable for Low-Temperature Service
• ASTM A487	Steel Castings Suitable for Pressure Service
• ASTM A515	Pressure Vessel Plates, Carbon Steel, for intermediate and High-Temperature Service
MSS Standards	Manufacturers Standardization Society
• MSS SP-6	Standard Finishes for Contact Faces of Pipe Flanges and Connecting-end Flanges of Valves and Fittings
• MSS SP-9	Spot Facing Bronze, Iron and Steel Flanges
• MSS SP-25	Standard Marking System for Valves, Fittings, Flanges and Unions
• MSS SP-44	Steel Pipe Line Flanges
• MSS SP-55	Visual Method
• MSS SP-61	Pressure Testing of Steel Valves
NACE Standards	National Association of Corrosion Engineers
• NACE MR-01-75	Standard material requirements sulfide stress cracking resistant metallic materials for oilfield equipment
ASME Codes	American Society of Mechanical Engineers
• ANSI/ASME B31.1	Power Piping
• ANSI/ASME B31.2	Fuel Gas Piping
• ANSI/ASME B31.3	Process Piping
• ANSI/ASME B31.4	Liquid Transportation Systems for Hydrocarbons
• ANSI/ASME B31.8	Gas Transmission and Distribution Piping Systems
• ANSI/ASME B31.9	Building Services Piping.
Boiler and Pressure Vessel Code:	
• Section II	Material Specifications - Parts A, B and C
• Section V	Non-Destructive Examination.
• Section VIII	Rules for construction of Pressure vessels, divisions 1 and 2
• Section IX	Welding and Brazing Qualifications

HOW TO ORDER COMPENSATOR PLUG VALVES

SIZE	WALWORTH FIGURE					TYPE OF OPERATION	SUPPLEMENTARY REQUIREMENTS
1/2"	1412	Short Pattern	150#	Wrench	RF	1= WRENCH	GO = Gear Operated
3/4"	1413	Short Pattern	150#	Wrench	RTJ	2= GEAR OPERATOR	BS = Bare Stem
1"	1414	Short Pattern	150#	Wrench	WE	3= PNEUMATIC ACTUATOR	MOV = Motor Operated Valve
1 1/2"	1422	Short Pattern	150#	Gear Operator	RF	4= ELECTRIC ACTUATOR	POV = Pneumatic Operated Valve
2"	1423	Short Pattern	150#	Gear Operator	RTJ	NOTE: AT THE MOMENT OF A PO, PLEASE SPECIFY CLEARLY THE TYPE OF OPERATION.	LD = Locking Device
3"	1424	Short Pattern	150#	Gear Operator	WE		NACE MR-01-75
4"	3412	Short Pattern	300#	Wrench	RF		NACE MR-01-03
6"	3413	Short Pattern	300#	Wrench	RTJ	BASE MATERIALS	SP = Special Paint
8"	3414	Short Pattern	300#	Wrench	WE	CARBON STEELS:	SG = Special Gasket
10"	3422	Short Pattern	300#	Gear Operator	RF	A216-WCB (C-Si)	SPK = Special Packing
12"	3423	Short Pattern	300#	Gear Operator	RTJ	A216-WCC (C-Si)	SE = Stem Extension
14"	3424	Short Pattern	300#	Gear Operator	WE	LOW ALLOY STEELS:	XX = Additional Requirements
16"	1512	Regular Pattern	150#	Wrench	RF	ASTM A217-WC9(2 1/4 % Cr-1%Mo)	ENDS
18"	1513	Regular Pattern	150#	Wrench	RTJ	LOW CARBON AUSTENITIC STAINLESS STEELS:	
20"	1514	Regular Pattern	150#	Wrench	WE	ASTM A351-CF3(18%Cr-8%Ni-0.03%C)	RF = Raised Face
24"	1522	Regular Pattern	150#	Gear Operator	RF	ASTM A351-CF3M(18%Cr-12%Ni-2%Mo-0.03%C)	RTJ = Ring Type Joint
	1523	Regular Pattern	150#	Gear Operator	RTJ	AUSTENITIC STAINLESS STEELS:	WE = Weld Ends
	1524	Regular Pattern	150#	Gear Operator	WE	ASTM A351-CF8(18%Cr-8%Ni-0.08%C)	THRD = Threaded Ends
	3512	Regular Pattern	300#	Wrench	RF	ASTM A351-CF8M(18%Cr-12%Ni-2%Mo-0.08%C)	PRESSURE
	3513	Regular Pattern	300#	Wrench	RTJ	ENDS	
	3514	Regular Pattern	300#	Wrench	WE		1 = 150
	3522	Regular Pattern	300#	Gear Operator	RF	RF = Raised Face	3 = 300
	3523	Regular Pattern	300#	Gear Operator	RTJ	RTJ = Ring Type Joint	6 = 600
	3524	Regular Pattern	300#	Gear Operator	WE	WE = Weld Ends	9 = 900
	6511	Regular Pattern	600#	Wrench	THRD	THRD = Threaded Ends	5 = 1500
	6512	Regular Pattern	600#	Wrench	RF	PATTERN	2 = 2500
	6513	Regular Pattern	600#	Wrench	RTJ		TRIM
	6514	Regular Pattern	600#	Wrench	WE	4 = SHORT	
	6522	Regular Pattern	600#	Gear Operator	RF	5 = REGULAR	T1
	6523	Regular Pattern	600#	Gear Operator	RTJ	6 = VENTURI	T2
	6524	Regular Pattern	600#	Gear Operator	WE		T3
	9511	Regular Pattern	900#	Wrench	THRD		T4
	9512	Regular Pattern	900#	Wrench	RF		T5
	9513	Regular Pattern	900#	Wrench	RTJ		T6
	9514	Regular Pattern	900#	Wrench	WE		
	9522	Regular Pattern	900#	Gear Operator	RF		
	9523	Regular Pattern	900#	Gear Operator	RTJ		
	9524	Regular Pattern	900#	Gear Operator	WE		
	5511	Regular Pattern	1500#	Wrench	THRD		
	5512	Regular Pattern	1500#	Wrench	RF		
	5513	Regular Pattern	1500#	Wrench	RTJ		
	5514	Regular Pattern	1500#	Wrench	WE		
	5522	Regular Pattern	1500#	Gear Operator	RF		
	5523	Regular Pattern	1500#	Gear Operator	RTJ		
	5524	Regular Pattern	1500#	Gear Operator	WE		
	2511	Regular Pattern	2500#	Wrench	THRD		
	2512	Regular Pattern	2500#	Wrench	RF		
	2513	Regular Pattern	2500#	Wrench	RTJ		
	2514	Regular Pattern	2500#	Wrench	WE		
	2522	Regular Pattern	2500#	Gear Operator	RF		
	2523	Regular Pattern	2500#	Gear Operator	RTJ		
	2524	Regular Pattern	2500#	Gear Operator	WE		
	1622	Venturi Pattern	150#	Gear Operator	RF		
	1623	Venturi Pattern	150#	Gear Operator	RTJ		
	1624	Venturi Pattern	150#	Gear Operator	WE		
	3612	Venturi Pattern	300#	Wrench	RF		
	3613	Venturi Pattern	300#	Wrench	RTJ		
	3614	Venturi Pattern	300#	Wrench	WE		
	3622	Venturi Pattern	300#	Gear Operator	RF		
	3623	Venturi Pattern	300#	Gear Operator	RTJ		
	3634	Venturi Pattern	300#	Gear Operator	WE		
	6612	Venturi Pattern	600#	Wrench	RF		
	6613	Venturi Pattern	600#	Wrench	RTJ		
	6614	Venturi Pattern	600#	Wrench	WE		
	6622	Venturi Pattern	600#	Gear Operator	RF		
	6623	Venturi Pattern	600#	Gear Operator	RTJ		
	6624	Venturi Pattern	600#	Gear Operator	WE		
	9622	Venturi Pattern	900#	Gear Operator	RF		
	9623	Venturi Pattern	900#	Gear Operator	RTJ		
	9624	Venturi Pattern	900#	Gear Operator	WE		

WALWORTH valves are designed by catalogue figures number which describe their main characteristics. The valve identification system shown herein is intended to assist our Customer in specifying the valve required and avoid mistakes during manufacturing.

1 - 4 - 2 - 2 - T1 - A105

BODY

TRIM (INTERIORS)

ENDS

OPERATOR

PATTERNS

PRESSURE CLASS

WALWORTH valves are designed by catalogue figures number which describe their main characteristics. The valve identification system shown herein is intended to assist our Customer in specifying the valve required and avoid mistakes during manufacturing.



HOW TO ORDER TOP ENTRY PLUG VALVES

WALWORTH valves are designed by catalogue figure numbers which describe their main characteristics. The valve identification system shown herein is intended to assist our Customer in specifying the valve required and avoid mistakes during manufacturing.

1749 - F - T1 - A105

BODY

TRIM (INTERIORS)

ENDS

TYPE OF VALVE & PRESSURE CLASS AS PER FIGURE NUMBER

SIZE (INCH)	WALWORTH FIGURE				TRIM	SUPPLEMENTARY REQUIREMENTS	ENDS
1/2"	1749F	150#	Wrench	RF	T1	GO = Gear Operated	RF = Raised Face Ends
3/4"	1749WE	150#	Wrench	WE	T2	BS = Bare Stem	WE = Welded Ends
1"	1750TH	150#	Wrench	THRD	T3	MOV = Motor Operated Valve	THRD = Threaded Ends
1 1/4"	1760F	300#	Wrench	RF	T4	POV = Pneumatic Operated Valve	BASE MATERIALS
1 1/2"	1760WE	300#	Wrench	WE	T5	LD = Locking Device	
2"	1760TH	300#	Wrench	THRD	T6	NACE MR-01-75	CARBON STEELS:
2 1/2"	1748	600#	Wrench	THRD		NACE MR-01-03	A216-WCB (C-Si)
3"	1752	150#	Gear Op.	RF		SP = Special Paint	A216-WCC (C-Si)
4"						SG = Special Gasket	LOW ALLOY STEELS:
6"						SPK = Special Packing	ASTM A217-WC9(2 1/4 % Cr-1%Mo)
8"						SE = Stem Extension	LOW CARBON AUSTENITIC STAINLESS STEELS:
10"						XX = Additional Requirements	ASTM A351-CF3(18%Cr-8%Ni-0.03%C)
12"							ASTM A351-CF3M(18%Cr-12%Ni-2%Mo-0.03%C)
14"							AUSTENITIC STAINLESS STEELS:
16"							ASTM A351-CF8(18%Cr-8%Ni-0.08%C)
18"							ASTM A351-CF8M(18%Cr-12%Ni-2%Mo-0.08%C)
20"							
24"							
30"							
36"							

TRIMS (INTERIORS)					
TRIM	PLUG	STEM	STEM TO PLUG COUPLING	THRUST BALL	THRUST BALL SEAT
M1	Iron / WCB	SS-410	Steel 4140	Carbon Steel	Steel 4140
M2	A487 grade A	SS-410	Steel 4140	Carbon Steel	Steel 4140
M3	SS-316	17-4PH	17-4PH	Monel	17-4PH
M4	Steel 4140	SS-410	Steel 4140	Carbon Steel	Steel 4140
M5	SS-410	SS-410	SS-410	Carbon Steel	Steel 4140

HOW TO ORDER GAS SERVICE PLUG VALVES

WALWORTH valves are designed by catalogue figure numbers which describe their main characteristics. The valve identification system shown herein is intended to assist our Customer in specifying the valve required and avoid mistakes during manufacturing.

1966 - WE - T1 - A105

BODY

TRIM (INTERIORS)

ENDS

TYPE OF VALVE & PRESSURE CLASS AS PER FIGURE NUMBER

SIZE (INCH)	WALWORTH FIGURE				TRIM	SUPPLEMENTARY REQUIREMENTS	ENDS
3/4"	1966 WE	150#	Wrench	WE	T1	GO = Gear Operated	WE = Welded Ends
1 1/4"	1966 SW	150#	Wrench	SW	T2	BS = Bare Stem	SW = Socket Weld Ends
2"	1967 WE	150#	Wrench	WE		MOV = Motor Operated Valve	BASE MATERIALS
3"	1968 WE	150#	Wrench	WE		POV = Pneumatic Operated Valve	
4"						LD = Locking Device	CARBON STEELS:
6"						NACE MR-01-75	A216-WCB (C-Si)
8"						NACE MR-01-03	
						SP = Special Paint	
						SG = Special Gasket	
						SPK = Special Packing	
						SE = Stem Extension	
						XX = Additional Requirements	

THE WALWORTH COMPANY GENERAL TERMS AND CONDITIONS

ACCEPTANCE: All quotations are for acceptance within 30 days from date of quotation unless extended in writing. In the event a purchase order is placed after this period of time, the WALWORTH Company reserves the right to requote base prices of all valves offered. All orders and contracts are subject to credit approval and acceptance by the WALWORTH Company.

FREIGHT: When prices are f.o.b. point of shipment - no freight allowance - we will attempt to route shipments in the method which will result in the lowest cost unless otherwise instructed. All shipments will be freight charges collect except when stipulated on the purchase order, in which case you will be invoiced for all transportation charges. Delivery of material to a common carrier shall be considered to be delivery to Buyer and shall be at Buyer's risk thereafter. Claims of loss of or damage to material in transit shall be filed by the Buyer directly with the carrier.

PRICES: There will be added to all prices quoted sales, use, occupation or any other excise or similar tax which Seller may be required to pay or collect on or in connection with the sale. Seller shall be established by Federal, State or other government regulation with respect to the product(s) topped by the order which shall be lower than the price(s) specified in the order.

ESCALATION TERMS: Prices shown in this price schedule reflect the costs in effect at the time of publication. These prices will remain firm on all products with a quoted delivery of twenty-six (26) weeks or less. On products which have a scheduled delivery of more than twenty-six (26) weeks, the goods will be invoiced based on the applicable price sheet in effect at the time of shipment. In no event will the invoiced price be less than the price originally quoted.

PURCHASED COMPONENTS: (i.e. motors, gearing, etc.) Prices are quoted on the supplier's price in effect at the time of quotation. Actual invoice price will be adjusted in accordance with the supplier's escalation policy.

DIFFERED SHIPMENTS: If for any reason the customer desires to delay shipments more than 30 days after manufacturing is complete, or to place a on hold or stop to the order during the manufacturing cycle, The WALWORTH Company reserves the right to consider the order cancelled and to invoke cancellation charges per the schedule below.

CANCELLATION: After order acceptance by WALWORTH, items or completed orders may be cancelled and Buyer will be charged for work performed, based on the following schedule:

- Five percent (5%) of prices of stock items.
- Ten percent (10%) of price of stock items ordered in quantities which exceed normal inventory levels.
- Five percent (5%) of prices prior to drawing submittal on made-to-order items.
- 15% after drawing approval, but prior to the start of castings.
- 30% to 50% during casting cycle, depending on the state of completion.
- 55% to 75% during machining and assembly operations, depending on the state of completion.
- 100% after final assembly and test.

REMITTANCES: Remittances must be made to the address indicated on the invoice.

CREDIT TERMS: As quoted. Invoices on balances overdue will be subject to a service charge of 1 1/2 % per month on such indebtedness.

DELIVERIES: Shipments and deliveries shall at all times be subject to the approval of Seller's Credit Department. If the Buyer shall fail to make any

payments according to the terms of the contract, Seller may, in addition to and not in limitation of its other rights and remedies, at its option, cancel all or any part of Buyer's incomplete contracts with Seller, or may defer shipments of deliveries under Buyer's contracts with Seller except upon receipt of satisfactory security or for cash shipment.

All schedule of shipments are estimated as closely as possible and Seller will use its best efforts to ship within the time scheduled, but does not guarantee to do so. Schedules commence with the date Seller receives authorization to proceed with the order, subject to the provisions of the next sentence. The order will not be released for manufacture until complete specifications and approved drawings (if drawing approval is required) are received at the plant of manufacturer and the estimated schedule of shipment will commence with the date of such receipt.

Seller shall not be liable for any direct, indirect or consequential damage or loss caused by any delay in delivery, regardless of the cause of delay.

Without limiting the generality of the foregoing, Seller assumes no responsibility for delays in delivery resulting from fire, flood, accidents, riots, strikes, transportation delays, labor or material shortages, existing or future laws, acts of any governmental authority, or any other cause beyond Seller's control. Items offered from stock are subject to prior sale.

INSPECTION: Final inspection and acceptance of products must be made at the plant of manufacture, unless otherwise provided in the order and/ or in agreed upon specifications. Prices do not include charges for special tests or inspections performed at the request of the Buyer, unless called for in the order and/or in agreed upon specifications.

RETURNS: Permission in writing and return tagging instructions must be obtained from Seller before any goods returned for credit or adjustment will be accepted. Where returned goods are accepted, a minimum charge of 25% of the invoice price will be made, plus freight from both directions and costs of reconditioning the material for resale as new.

WARRANTY: Seller will replace without charge or refund the purchase price of products manufactured by Seller which prove to be defective in the material or workmanship, provided in each case that the product is properly installed and is used in the service for which Seller recommends it and that a written claim, specifying the alleged defect, is presented to Seller. Seller shall in no event be responsible for (a) claims for labor, expenses or other damages occasioned by defective products or (b) for consequences or secondary damages. THE WARRANTY STATED IN THIS PARAGRAPH IS IN LIEU OF ALL OTHER WARRANTIES, EITHER EXPRESSED OR IMPLIED. WITH RESPECT TO WARRANTIES, THIS PARAGRAPH STATES BUYER'S EXCLUSIVE REMEDY AND SELLER'S EXCLUSIVE LIABILITY.

DESIGN, ETC: Seller reserves the right to change design, materials or specifications without notice. There will be a charge for modifying an order after it has been entered when such change or modification results in additional engineering or clerical work for either The WALWORTH Company or our suppliers.

MINIMUM CHARGE: Orders totaling less than \$100.00 net will be billed at a minimum charge of \$100.00. Repair parts will be billed at a minimum charge of \$50.00.

NOTE: We reserve the right to correct obvious clerical errors in quotations, invoices, and other contracts.



WALWORTH®

Since 1842



www.walworth.com

MÉXICO

Industrial de Válvulas, S.A. de C.V.

Industria Lote 16 Sin Número, Fracc. Industrial El Trébol De Tepotzotlán, Tepotzotlán Estado de México C.P. 54610

Phone: (52 55) 5899 1700 Fax: (52 55) 5876 0156 | e-mail: info@walworth.com.mx

USA/CAN AUTHORIZED DISTRIBUTOR

TWC The Valve Company

**13641 Dublin Court, Stafford, Texas 77477 | Phone: (281) 566 1200 Fax: (281) 566 1299 |
www.twcvalves.com | e-mail: info@twcousa.com**



Scan me with your smartphone to get
more info about **WALWORTH** valves





WALWORTH[®]
Since 1842



IRON PLUG VALVES
CATALOG

INDEX

INTRODUCTION

ENGINEERING CONTROL.....	5
QUALITY SYSTEM	5
QUALITY CONTROL EQUIPMENT.....	9

SHORT, REGULAR & VENTURI PATTERN IRON PLUG VALVES

IRON PLUG VALVES.....	11
SHORT PATTERN IRON PLUG VALVES CLASS 200 CWP (SINGLE GLAND)	12
SHORT PATTERN IRON PLUG VALVES CLASS 200 CWP (REGULAR TYPE GLAND).....	15
REGULAR PATTERN IRON VALVES CLASS 200 CWP	20
VENTURI PATTERN IRON VALVES CLASS 175 CWP	25
VENTURI PATTERN IRON VALVES CLASS 500 CWP	28
PLUG VALVE WRENCHES	33
WALSEAL PLUG VALVES SEALANT	34
LUBRICANT ACCESORIES.....	36
PRESSURE-TEMPERATURE RATINGS	38
FLANGE DIMENSIONS AND TEMPLATES.....	39
DESIGN BASIS.....	40
HOW TO ORDER.....	41
GENERAL TERMS AND CONDITIONS	42



YARMOUTH RESEARCH AND TECHNOLOGY



WALWORTH

WALWORTH is one of the world's most comprehensive industrial valve manufacturers. Founded in 19th century by James WALWORTH, the Company has consistently dedicated itself to improvements in design and manufacturing of an array of valves exceptionally suited for the world's fluid control sector. We satisfy all end use industries and comprehensive customer requirements by adhering to the most demanding quality standards.

WALWORTH relies on its broad experience in supplying valves to the petrochemical, oil & gas, petroleum, power generation, pulp and paper, cryogenic and geothermal industries, among others.

Over the years, WALWORTH has produced over 40,000 different types of products and serves as a global supplier to various markets utilizing the expertise of over 500 trained employees.

Our manufacturing system includes: utilization of Company directed raw material warehouses; modern and newly acquired specialized machinery; welding processes such as SMAW, GMAW, SAW, PAW; assembly testing for all low pressure, high pressure, and at low or high temperatures; painting and coating processes; export crating and shipment.

WALWORTH is capable of providing the world's most comprehensive industrial valve line to the North American, Central American, South American, European and African markets. WALWORTH is proud to meet and satisfy the precise demands of our customers throughout the world by providing a quality product, competitive cost, and excellent service.



WALWORTH VALUES

MISSION

WALWORTH manufactures and supplies world-class valves and components for the flow control industry through exceptional service, competitive pricing, and consistently, on-time deliveries.



VISION

To be the world leader of unparalleled valve manufacturing and supply, WALWORTH:

- Set the standard for product quality in the flow control industry.
- Exceed the service expectations of our customers.
- Forge enduring relationships with customers, team members, and community.
- Hire, develop, and retain experienced and dedicated team members.



WALWORTH ENGINEERING CONTROL


WALWORTH products are manufactured following the strict international standards recognized all over the world, such as API, ANSI, ASME, ASTM, MSS, NACE, AWWA, BSI, CSA, among others. Our Engineering team consistently monitors updates to these standards and incorporates any applicable changes that affect the design, regulations and/or performance of our products.

Our designs are made using the most advanced technology and equipment, finite elements, and CAD system programs to ensure proper assembly and performance. From conception to calculation to detailed drawings for manufacturers, WALWORTH is a leader in development of new products that meet the needs of the current valve market.”




WALWORTH QUALITY SYSTEM

Throughout the years, WALWORTH has developed its Quality System which is an integral part of our manufacturing policy. Our primary goal is to provide products that meet and exceed market standards. In this sense, WALWORTH is an ISO-9001 Audited and Certified Company that has achieved major certifications worldwide. Our system includes the selection of raw materials from approved vendors, and rigorous oversight of our manufacturing process that is vital to quality control. The use of serial numbers allows WALWORTH the ability to not only ensure the quality of components used but to monitor and trace the fabrication process as well.



Certificate API-6D No. 6D-0097

Issued by American Petroleum Institute to apply on Gate valves, Plug valves, Ball valves and Check valves manufactured in accordance with API-6D specification.



Certificate API-6A No. 6A-0234

From American Petroleum Institute to apply on valves at PSI, 1 through 4.



Certificate API-594 No. 594-0007
Issued by American Petroleum Institute to apply on Check Valves-Type A; Check Valves Type B manufactured in accordance with API-594 specification.



API-600 Certificate No. 600-0109
Issued by American Petroleum Institute to apply on Bolted Bonnet Steel Gate Valves manufactured in accordance with API-600 specification.



API-602 Certificate No. 602-0024
Issued by American Petroleum Institute to apply on Compact Steel Gate Valves, Compact Steel Globe Valves, and Compact Steel Check Valves manufactured in accordance with API-602 specification.



Certificate ISO-9001 No. 0038
Issued by American Petroleum Institute since April 1999.



Certificate as per PED 97/23/EC Module H
To stamp CE products.



Supplier Qualification Certificate NO. 279/13
 Issued by the Equipment and Materials Testing Laboratory, CFE (LAPEM in Spanish)



Certificate NMX-CC-9001 (Mexican Standards ISO-9001) No. 0552/2007
 Issued by PEMEX in accordance with ISO-9001 Quality Assurance System.

PRODUCT CERTIFICATIONS



Emissions after 500 cycles at ambient and 350 °F
 Issued by Yarmouth Research and Technology Lab for 3 inch Class 300 Gate Valve After 500 cycles the measurement result was less than 50 ppm.



Emissions after 500 cycles at ambient and 350 °F
 Issued by Yarmouth Research and Technology Lab for 8 inch Class 300 Gate Valve After 500 cycles the measurement result was less than 50 ppm.



Emissions after 500 cycles at ambient and 350 °F
 Issued by Yarmouth Research and Technology Lab for 16 inch Class 150 Gate Valve After 500 cycles the measurement result was less than 50 ppm.



YARMOUTH RESEARCH AND TECHNOLOGY
PROJECT SUMMARY

Project Number: 00008
Customer: The Walworth Company
Contact: David Cornelien
Date(s) of Test: 12/9/99 - 12/23/99
Product(s) Tested: One 8" Class 300 Gate Valve with Empak-Mex EAF-100-001 packing.
Purpose of Test: The test was conducted to evaluate the valve's atom sealing performance at ambient and at 350° F as related to the 1990 Amendments to the Clean Air Act requirements. Leakage measurements were conducted in accordance with 40 CFR Part 60, Appendix A, Method 21.
Conclusion: Three thermal cycles from ambient to 350 deg. F were conducted throughout 5000 on/off cycles with the valve presented to 640 psig. The valve was cycled with a 43 RPM gear motor coupled to the handwheel. One packing seal adjustment was required on cycle number 300 to maintain leakage levels below 100 PP50.
At cycle number 3500, the packing leakage was 25-29 PP50s with the stem static. The packing nuts were tightened from 12/13 B.B. back to 28 B.B. and leakage decreased to about 1 PP50s.
See the attached data sheets for more information.
Test Witness: Matthew J. Wasieleski, P.E., President
YARMOUTH RESEARCH AND TECHNOLOGY

Phone or Fax (202) 946-3646
42 East Elm Street P.O. Box 110 Yarmouth, Maine 04096-0110

TÜV Rheinland Argentina S.A.
Servicios Industriales
Certificación Control
San José 53 - 7° Piso
2222BAAU Buenos Aires

TÜVRheinland®

Certificate

Certificate No. TRASA 700-13-0019
Customer: WALWORTH MEXICO - Industrial de Valinox S.A. de C.V.
Av. de la Industria Lote 18
Paseo Industrial El Trebol, S.P. 44000
Tepic, Jalisco, México
Product Tested: API 6D Trunnion mounted body ball valves, carbon steel (A105-WCB) construction, double block and bleed service, primarily used for oil and gas standard and severe applications.
Trademark: WALWORTH
Model / Type: See attached data sheets for more information.
Applicable Standard: ASME B16.34
TUV Report No.: TRASA 700-13-0019
Results: Successful - Leakage: 0.5 - 1.0 ppm
Pressure integrity: Pass
API 6D and applicable construction code requirements for each application.
Safety Function: The Trunnion Ball Valves will meet the design and pressure test and the pressure integrity. The valve performs as designed and meets the design and pressure test.
Specific Requirements: The Trunnion Ball Valves will meet the design and pressure test and the pressure integrity. The valve performs as designed and meets the design and pressure test.
Business Review: January 2000, 2004
Signed: [Signature]
Eing. Mauricio Schwaninger
Note: This TÜV Report No. TRASA 700-13-0019 is an integral part of this certificate.
This certificate is valid only for products tested in accordance with the product name. It is invalid if the product is not tested in accordance with the product name.
Page 1 of 5

Certificates of Ultra Low Fugitive Emissions No. 20985-3, 8 & 16 in accordance with ISO-15848-1 "Industrial Valves" Measurement, Test and Qualification Procedures for Fugitive Emissions "Part 1: Classification System and Qualification Procedures for Type Testing of Valves".

TÜV Rheinland Certificate No. TRASA 700-13-0019
API-6D Trunnion mounted bolted body ball valves, carbon steel (A105-WCB) construction, double block and bleed service, primarily used but not limited to the oil and gas standard and severe applications.

DACOR SERVICES
CONSULTANTS
ENGINEERING • QUALITY ASSURANCE • MANUFACTURING
DAVID J. CORNELIEN, P.E., PRESIDENT

January 22, 2005

Ruben Parades
Walworth - Inval Facility
Av. De la Industria Lote 16 Fracc. Industrial El Trebol
Tepic, Jalisco, Edo. De Mexico
CP 44000, Mexico

Reference: Witness Report - API Spec 6FA Fire Test
Number 01-1/05

This will certify that the following listed valve successfully passed all requirements of API Specification 6FA Fire Test for Valves, Third Edition dated April 1999 and API Standard 607 Fire Test for Self-Seated Quarter-Turn Valves, Fourth Edition dated May 1993. The tests were made and verified on January 21, 2005.

API 6D Trunnion Mounted Ball Valve, 12-inch Class 150 Figure 8122, Serial Number V05B01.

The successful test of the 12-inch Class 150 API 6D Ball Valve qualifies this design/type of valve as meeting the requirements of API Spec 6FA / API Std 607 for sizes 12-inch through 24-inch in pressure classes 150 and 300.

Sincerely,
[Signature]
David J. Cornelien P.E.
President

24002 Mathews Drive • Katy, Texas 77494
Telephone (281) 395-5275 • Telex (281) 395-5275

tuv CERT **TÜVRheinland®**
Precisely Right.

CERTIFICATE
Certificate No.: 01 202 USA-TA-00-79704

Concerning the Agreement with the Technical Requirements in:
TA-Luft 2002, VDI 2440 Nov. 2000, Sec. 3.3.1.3

Test report: 209140 **Date:** 01 December, 2000
Client: Industrial de Valinox, S.A. de C.V.
Manufacturer's Address: Av. De la Industria Lote 18
Paseo Industrial El Trebol,
Tepic, Jalisco, Edo. De Mexico, CP 44000

The stem sealing system and internal flange connection have been successfully tested to meet the tightness criteria of 0.10⁻⁶ mbar x l/s at a helium mass spectrometer under the following conditions. The SPV Valve with the measured mechanical stuff seals fulfills the requirements of Section 3.3.1.3 of The German Clean Air Act (TA-Luft, Leakage Verification) in accordance with Section 3.3.1.3 of VDI 2440 (Nov. 2000).

Kind of Valve:	Walworth API 6D Gate Valve	
Valve Type:	4 inch, Class 150, Figure 8122	
Sealing System:	WCB Body / CR 13 Stem & Stem / HP Seat	
Nominal Size, Nominal Pressure:	4 inch, ANSI 300	
Inspection Media/Pressure:	Helium / 01 Bar	Temperature = Ambient
Switching Cycles (Ones):	8 Cycles	Total Cycles 800
Leakage Rate (mbar x l/s):	5.2e-7 (mbar x l/s)	5.7e-6 (mbar x l/s)
Testing Method:	Helium Leak Test - VDI 2440, Appendix A	

Testing Laboratory:
YARMOUTH RESEARCH AND TECHNOLOGY
Matthew J. Wasieleski, PE
424 Walnut Hill Road, N. Yarmouth, ME USA
www.yarmouthresearch.com

TÜV Rheinland North America, Inc.
Industrial Services Division, Hudson, CT, USA
[Signature]
Klaus J. Bärlein, Jr. - Executive

Fire Test Certificate No. 01-1/05
In accordance with API-6FA and API Standard API-607 for Trunnion Ball Valves in accordance with API-6D.

TA Luft Certificate (Fugitive Emission) Approval
ISO-5211 Top Flange, Anti-Static Device.

QUALITY CONTROL EQUIPMENT

In order to assure that WALWORTH products comply with international quality standards, in-house equipment is kept for monitoring control. Some of this equipment includes:



X-Ray Examination Equipment. WALWORTH has its own Ir-92 source in-house for the radiographic examination (RT) of castings from 0.100" up to 2 1/2" wall thickness to verify the soundness of the casting raw material.

PMI Equipment. A new generation of Positive Material Identification Equipment gives WALWORTH the capability to perform quick chemical analysis on incoming raw materials and on pieces after assembly, to certify that materials used were produced and assembled in accordance with WALWORTH's and our Customer's specifications.



Magnetic Particle Test. On a random basis for standard products or when a Customer requests MT Certification, WALWORTH has Magnetic Particle Test Equipment to perform on ferromagnetic materials.

Penetrant Test Examination. WALWORTH has the personnel and materials to perform PT examination by solvent removable or water washable techniques. NDT personnel are ASNT Certified.



Test Loop. A complete Laboratory Test loop exists for design validation of WALWORTH products. The test is performed at maximum design pressure, advances the valves from 3000 to 5000 cycles, and requires more than four months to complete.

Pressure Gradient Test Loop. This test exposes Plug valves to the extremes of both positive and negative pressure gradients to verify that the plug in a balanced plug design will prevent lock-up in the body.





Metrology Laboratory. WALWORTH developed a calibration and/or verification system in all of the equipment used in its facilities. This ensures our ability to trace measurements, control products, and comply with international standards.

Fire Test Facilities. WALWORTH has the facilities to perform fire tests in accordance with API requirements. The test exposes the valve to a fire flame at 1400 to 1800 °F (761 to 980 °C) to verify proper seal of the valve.



Low Fugitive Emissions Test. This test is performed when a Customer requires low fugitive emissions certification. Our Lab has its own LFE test equipment that is capable of measuring less than 20 ppm in both static and mechanical conditions at either ambient temperature or thermal cycle operations.

Ultrasonic Testing Equipment. Using ultrasonic techniques, we can detect sub surface flaws in materials and evaluate castings and forgings that cannot be radiographed. In addition, we utilize these techniques to measure the wall thickness of castings and forgings.



Tensile Test Equipment. We use this equipment to verify the mechanical properties of materials used for manufacturing. WALWORTH tests samples on a random basis even though we receive MTRs from our suppliers and foundries.

Hardness Test Equipments.- In both lab and shop tests, WALWORTH uses hardness tester equipment, such as Rockwell B, C Brinell or Vickers, to ensure compliance with specifications.



WALWORTH IRON PLUG VALVES

WALWORTH Cast Iron Lubricated Plug Valves are designed to meet the demand for an inexpensive product that incorporates the principal features of the Lubricated Plug Valves.

The Top Entry design is offered in three different patterns: Short, Regular and Venturi from 1/2" (12.7 mm) to 18" (450 mm) - Iron Body and Plug Classes 175, 200 & 500 CWP.

DESIGN FEATURES

- Design in accordance with MSS SP-78.
- Mechanical Balance spring to avoid jamming of the plug.
- Lever or gear operated.
- Bi-directional.
- Locking devices are available as an option
- Tamper proof bolting is available as an option
- Operating extensions and elevations.
- Additional Walseal sealants are available for different applications.
- Sealant Grooves. this system permits sealant injection while the valve is under full line pressure.

PRODUCT RANGE

PATTERN	SIZE	PRESSURE CLASS AS PER API	ENDS
Short	1/2" to 12"	200 CWP	Threaded or RF
Regular	1/2" to 12"	200 CWP	Threaded or RF
Venturi	14" to 18"	175 CWP	Threaded or RF
Venturi	6" to 8"	500 CWP	Threaded or RF



SHORT PATTERN

Provides face to face dimensions that match gate valves.



REGULAR PATTERN

Offers the largest port opening in a trapezoidal configuration – close to a full pipe size.



VENTURI PATTERN

Has a smaller port than the other two patterns. Is lower in cost and flow contours maximize hydraulic efficiency.


IRON PLUG VALVE SHORT PATTERN CLASS 200 CWP

Single Gland

DESIGN FEATURES

Short Pattern WALWORTH design offers big opening port and end to end dimensions same as a Gate Valve.

As in other types of WALWORTH Lubricated Plug Valves, the surfaces of the Single Gland Lubricated Plug Valve are "Pressure Sealed". When the valve is in either the open or closed position, this seal is renewed by forcing lubricant under high pressure into a grooving system which completely encircles the ports.



Design Features


- ① **Sealant Fitting.** Fast Sealant Injection that can be removed under pressure. The system includes Ball Check valves in order to prevent the back pressure and maintain the pressure in the sealant cavity.
- ② **Balancing Spring.** the mechanical spring type grade SS-304 washer is under compression and holds the plug in an equalized pressure position, thus eliminating the possibility of plug taper lock.
- ③ **Sealant Grooves.** this system permits sealant injection while the valve is under full line pressure. WALWORTH recommends that the valves be lubricated with plug in the fully opened or fully closed position for optimum valve performance.
- ④ **Open/Closed Indicator.** quarter turn stop collar also functions as an indicator of the plug's position.
- ⑤ **Diaphragm Gasket.** ensures a complete sealing of the valve against leakage.
- ⑥ **Plug.** WALWORTH Plugs are designed with an specific coating material that reduces the coefficient of friction making the valve to operate with low torque.

IRON PLUG VALVE SHORT PATTERN CLASS 200 CWP

Single Gland (Lever Operated)

Regular Bill of Materials

No.	Description	Material
1	BODY	ASTM A-126 CLASS B
2	GLAND	ASTM A-126 CLASS B
3	PLUG	ASTM A-126 CLASS B
4	COLLAR RETAINER	CARBON STEEL
5	GLAND SCREW	ASTM A 307 Gr. B
6	PRESSURE RING	REINFORCE TEFLON
7	GASKET	STAINLESS STEEL + GRAPHITE
8	WEATHER SEAL	NITRILE BUTADIENE RUBBER
9	GREASE FITTING	COMMERCIAL STEEL
10	RING RETAINER	COMMERCIAL STEEL
11	BALANCE SPRING	STAINLESS STEEL
12	O-RING	NITRILE BUTADIENE RUBBER
13	SEALANT CHECK VALVE	COMMERCIAL STEEL
14	WRENCH	GRAY IRON
15	SET SCREW	ALLOY STEEL




IRON PLUG VALVE SHORT PATTERN CLASS 200 CWP

Single Gland Type (Lever Operated)

Design Features

- Threaded ends in accordance with ASME B1.20.1
- Flat Face Flanged ends in accordance with ASME B16.1
- Design in accordance with MSS SP-78
- Test in accordance with API 598 & MSS SP 78

Figure no.	Operation	Type of ends
1796	Lever operated	THREADED
1797F	Lever operated	FLAT FACE FLANGED



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions				Approx. Weight				WRENCH
										E								
		A		B		C		D		FLAT FACE		THRD		FLAT FACE		THRD		
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb	
1/2	15	3.87	98	1.62	41	0.81	21	2.56	65	-	-	4.5	114	-	-	2.2	4.8	DB D-4
3/4	20	3.87	98	1.62	41	0.81	21	2.56	65	-	-	4.5	114	-	-	2.2	4.8	DB D-4
1	25	3.87	98	1.62	41	0.81	21	2.56	65	5.5	140	4.5	114	3.5	7.7	2.2	4.8	DB D-4
1 1/4	32	4.56	116	2	51	0.9	23	3.12	79	6.5	165	5	127	5.9	13.0	4.2	9.3	DB E-1
1 1/2	40	4.56	116	2	51	0.9	23	3.12	79	6.5	165	5	127	6.1	13.4	3.9	8.5	DB E-1
2	50	4.81	122	2.37	60	1.06	27	3.62	92	7	178	5.87	149	9.9	21.7	6.2	13.7	DB G-1
2 1/2	65	5.62	143	2.37	60	1.25	32	4.12	105	7.5	191	6.75	171	15.1	33.2	10.2	22.5	DB G-1
3	75	6.31	160	3.25	83	1.37	35	4.75	121	8	203	7.62	194	22.2	49.0	15.6	34.3	DB M-1
4	100	7.37	187	4.06	103	1.5	38	5.75	146	9	229	9	229	30.0	66.0	24.5	54.0	DB P-1
5	125	7.68	195	4.5	114	1.5	38	6.5	165	10	254	-	-	40.0	88.0	-	-	DBP-1.1


IRON PLUG VALVE SHORT PATTERN CLASS 200 CWP

Regular Gland Type

DESIGN FEATURES

WALWORTH Regular Gland type Lubricated Plug Valves are designed to control plug adjustment tightening the gland, requesting only a very low maintenance in the field.

These Valves are all provided with separate retainers (cover plate) and adjusting glands; generally sizes 3" and smaller have four-bolt square retainers, while 4 inches and large sizes have round retainers. They all incorporate the Pressure Sealed Lubrication features.



Design Features


- ① **Sealant Fitting.** Fast Sealant Injection that can be removed under pressure. The system includes Ball Check valves in order to prevent the back pressure and maintain the pressure in the sealant cavity.
- ② **Balancing Spring.** the mechanical spring type grade SS-304 washer is under compression and holds the plug in an equalized pressure position, thus eliminating the possibility of plug taper lock.
- ③ **Sealant Grooves.** this system permits sealant injection while the valve is under full line pressure. WALWORTH recommends that the valves be lubricated with plug in the fully opened or fully closed position for optimum valve performance.
- ④ **Open/Closed Indicator.** quarter turn stop collar also functions as an indicator of the plug's position.
- ⑤ **Diaphragm Gasket.** ensures a complete sealing of the valve against leakage.
- ⑥ **Plug.** WALWORTH Plugs are designed with an specific coating material that reduces the coefficient of friction making the valve to operate with low torque.

IRON PLUG VALVE SHORT PATTERN CLASS 200 CWP

Regular Gland Type (Lever Operated)

Regular Bill of Materials

No.	Description	Material
1	BODY	ASTM A-126 CLASS B
2	GLAND	ASTM A-126 CLASS B
3	PLUG	ASTM A-126 CLASS B
4	COLLAR RETAINER	CARBON STEEL
5	GLAND SCREW	ASTM A 307 Gr. B
6	GLAND NUT	ASTM A 194 Gr. 2H
7	GASKET	STAINLESS STEEL + GRAPHITE
8	WEATHER SEAL	NITRILE BUTADIENE RUBBER
9	GREASE FITTING	COMMERCIAL STEEL
10	RING RETAINER	COMMERCIAL STEEL
11	BALANCE SPRING	STAINLESS STEEL
12	O-RING	NITRILE BUTADIENE RUBBER
13	SEALANT CHECK VALVE	COMMERCIAL STEEL
14	PLUG CHECK VALVE	COMMERCIAL STEEL
15	COVER SCREW	ASTM A 307 GRADE B
16	COVER NUT	ASTM A 194 Gr. 2H
17	COVER	ASTM A-126 CLASE B
18	WRENCH	GRAY IRON
19	SET SCREW	ALLOY STEEL
20	WRENCH PIN	ASTM A568




IRON PLUG VALVE SHORT PATTERN CLASS 200 CWP (ANSI 150)

Regular Gland Type (Lever Operated)

Design Features

- Flat Face Flanged ends in accordance with ASME B16.1
- Design in accordance with MSS SP-78
- Test in accordance with API 598 & MSS SP 78

Figure no.	Operation	Type of ends
1718F	Lever operated	THREADED




Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions		Approx Weight		Wrench No.
										E		FLAT FACE		
		A		B		C		D		FLAT FACE				
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	
6	150	11.75	298	6.12	155	1.5	38	8.37	213	10.5	267	69.9	154.0	P-1
8	200	13.5	343	7.56	192	1.75	44	9.62	244	11.5	292	107.6	237.0	R-3
10	250	14.5	368	9.12	232	2	51	10.87	276	13	330	151.6	334.0	T-3
12	300	18.18	462	10.68	271	2.43	62	13.5	343	14	356	263.3	580.0	V-3

IRON PLUG VALVE SHORT PATTERN CLASS 200 CWP (Gear Operated)

Regular Bill of Materials

No.	Description	Material
1	BODY	ASTM A-126 CLASS B
2	GLAND	ASTM A-126 CLASS B
3	PLUG	ASTM A-126 CLASS B
4	GLAND SCREW	ASTM A 307 Gr. B
5	GLAND NUT	ASTM A 194 Gr. 2H
6	GASKET	STAINLESS STEEL + GRAPHITE
7	WEATHER SEAL	NITRILE BUTADIENE RUBBER
8	GREASE FITTING	COMMERCIAL STEEL
9	RING RETAINER	COMMERCIAL STEEL
10	BALANCE SPRING	STAINLESS STEEL
11	O-RING	NITRILE BUTADIENE RUBBER
12	SEALANT CHECK VALVE	COMMERCIAL STEEL
13	PLUG CHECK VALVE	COMMERCIAL STEEL
14	COVER SCREW	ASTM A 307 GRADE B
15	COVER NUT	ASTM A 194 Gr. 2H
16	COVER	ASTM A-126 CLASE B
17	GEAR OPERATOR	COMERCIAL STEEL
18	GEAR OPERATOR SUPPORT	CARBON STEEL
19	GEAR OPERATOR BOLTING	ASTM A 307 Gr. B
20	STEM EXTENSION	ASTM A 322 GRADE 4140
21	COLLAR RETAINER	CARBON STEEL




IRON PLUG VALVE SHORT PATTERN CLASS 200 CWP **(Gear Operated)**

Design Features

- Flat Face Flanged ends in accordance with ASME B16.1
- Design in accordance with MSS SP-78
- Test in accordance with API 598 & MSS SP 78

Figure no.	Operation	Type of ends
1727	Gear Operated	FLANGED FLAT FACE



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions		Approx Weight	
										E			
		A		B		C		D		FLAT FACE			
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb
6	150	18.68	474	6.12	155	23	584	18	457	10.5	267	99.9	220.0
8	200	18	457	7.56	192	23	584	21	533	11.5	292	131.7	290.0
10	250	20.06	510	9.12	232	23	584	27	685	13	330	204.3	450.0
12	300	22.68	576	10.68	271	23	584	31	787	14	356	263.3	580.0


IRON PLUG VALVE REGULAR PATTERN CLASS 200 CWP

Regular Gland Type (Lever Operated)

DESIGN FEATURES

WALWORTH Regular Pattern Plug Valve provide largest port opening in a trapezoidal configuration with the close dimensions to a full pipe size.

These Valves are all provided with separate retainers (cover plate) and adjusting glands; generally sizes 3" and smaller have four-bolt square retainers, while 4 inches and large sizes have round retainers. They all incorporate the Pressure Sealed Lubrication features.




Design Features

- ① **Sealant Fitting.** Fast Sealant Injection that can be removed under pressure. The system includes Ball Check valves in order to prevent the back pressure and maintain the pressure in the sealant cavity.
- ② **Balancing Spring.** the mechanical spring type grade SS-304 washer is under compression and holds the plug in an equalized pressure position, thus eliminating the possibility of plug taper lock.
- ③ **Sealant Grooves.** this system permits sealant injection while the valve is under full line pressure. WALWORTH recommends that the valves be lubricated with plug in the fully opened or fully closed position for optimum valve performance.
- ④ **Open/Closed Indicator.** quarter turn stop collar also functions as an indicator of the plug's position.
- ⑤ **Diaphragm Gasket.** ensures a complete sealing of the valve against leakage.
- ⑥ **Plug.** WALWORTH Plugs are designed with an specific coating material that reduces the coefficient of friction making the valve to operate with low torque.

IRON PLUG VALVE REGULAR PATTERN CLASS 200 CWP (Lever Operated)

Regular Bill of Materials

No.	Description	Material
1	BODY	ASTM A-126 CLASS B
2	GLAND	ASTM A-126 CLASS B
3	PLUG	ASTM A-126 CLASS B
4	COLLAR RETAINER	CARBON STEEL
5	GLAND SCREW	ASTM A 307 Gr. B
6	GLAND NUT	ASTM A 194 Gr. 2H
7	GASKET	STAINLESS STEEL + GRAPHITE
8	WRENCH PIN	ASTM A568
9	GREASE FITTING	COMMERCIAL STEEL
10	RING RETAINER	COMMERCIAL STEEL
11	BALANCE SPRING	STAINLESS STEEL
12	O-RING	NITRILE BUTADIENE RUBBER
13	SEALANT CHECK VALVE	COMMERCIAL STEEL
14	PLUG CHECK VALVE	COMMERCIAL STEEL
15	COVER SCREW	ASTM A 307 GRADE B
16	COVER NUT	ASTM A 194 Gr. 2H
17	COVER	ASTM A-126 CLASE B
18	WRENCH	GRAY IRON
19	SET SCREW	ALLOY STEEL




IRON PLUG VALVE REGULAR PATTERN CLASS 200 CWP (Lever Operated)

Design Features

- Threaded ends in accordance with ASME B1.20.1
- Flat Face Flanged ends in accordance with ASME B16.1
- Design in accordance with MSS SP-78
- Test in accordance with API 598 & MSS SP 78

Figure no.	Operation	Type of ends
1700	Lever Operated	THREADED
1700 F	Lever Operated	FLANGED FLAT FACE




Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions				Approx Weight				Wrench No.
										E				FLAT FACE		THRD		
		A		B		C		D										
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	Kg	lb	
2	50	7.37	187	3.25	83	1.25	32	4.31	109	7.5	191	6.5	165	14.1	31.0	11.8	26.0	DB G-1
3	75	9	229	4.18	106	1.37	35	5.5	140	9	229	8.06	205	26.8	59.0	25.9	57.0	DB M-1
4	100	10.81	275	5.18	132	1.5	38	8.37	213	12	305	-	-	58.1	128.0	-	-	DB P-1
6	150	13.12	333	7.12	181	2	51	10.87	276	15.5	394	-	-	115.8	255.0	-	-	T-3
8	200	16.5	419	8.43	214	2.43	62	13.5	343	18	457	-	-	207.5	457.0	-	-	V-3

IRON PLUG VALVE REGULAR PATTERN CLASS 200 CWP (Gear Operated)

Regular Bill of Materials

No.	Description	Material
1	BODY	ASTM A-126 CLASS B
2	GLAND	ASTM A-126 CLASS B
3	PLUG	ASTM A-126 CLASS B
4	GLAND SCREW	ASTM A 307 Gr. B
5	GLAND NUT	ASTM A 194 Gr. 2H
6	GASKET	STAINLESS STEEL + GRAPHITE
7	GREASE FITTING	COMMERCIAL STEEL
8	BALANCE SPRING	STAINLESS STEEL
9	O-RING	NITRILE BUTADIENE RUBBER
10	SEALANT CHECK VALVE	COMMERCIAL STEEL
11	PLUG CHECK VALVE	COMMERCIAL STEEL
12	COVER SCREW	ASTM A 307 GRADE B
13	COVER NUT	ASTM A 194 Gr. 2H
14	COVER	ASTM A-126 CLASE B
15	GEAR OPERATOR	COMERCIAL STEEL
16	GEAR OPERATOR SUPPORT	CARBON STEEL
17	GEAR OPERATOR BOLTING	ASTM A 307 Gr. B
18	STEM EXTENSION	ASTM A 322 GRADE 4140
19	COLLAR RETAINER	CARBON STEEL




IRON PLUG VALVE REGULAR PATTERN CLASS 200 CWP (Gear Operated)

Design Features

- Flat Face Flanged ends in accordance with ASME B16.1
- Design in accordance with MSS SP-78
- Test in accordance with API 598 & MSS SP 78

Figure no.	Operation	Type of ends
1707 F	Gear Operated	Flanged Flat Face



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions		Approx Weight	
										E			
		A		B		C		D		FLAT FACE			
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb
6	150	18.68	474	6.81	173	23	584	20	508	15.5	394	149.8	330.0
8	200	21	533	8.43	214	23	584	22	559	18	457	245.2	540.0
10	250	23.56	598	10	254	23	584	26	660	21	533	419.5	924.0
12	300	27.87	708	11.5	292	23	584	31	787	24	610	594.7	1310.0


IRON PLUG VALVE VENTURI PATTERN CLASS 175 CWP

Regular Gland Type

DESIGN FEATURES

WALWORTH Regular Gland type Lubricated Venturi Plug Valves has a smaller port than the other two patterns. Is lower in cost, flow contours maximize hydraulic efficiency.

These Valves are all provided with separate retainers (cover plate) and adjusting glands; generally sizes 3" and smaller have four-bolt square retainers, while 4 inches and large sizes have round retainers. They all incorporate the Pressure Sealed Lubrication features.




Design Features

- ① **Sealant Fitting.** Fast Sealant Injection that can be removed under pressure. The system includes Ball Check valves in order to prevent the back pressure and maintain the pressure in the sealant cavity.
- ② **Balancing Spring.** the mechanical spring type grade SS-304 washer is under compression and holds the plug in an equalized pressure position, thus eliminating the possibility of plug taper lock.
- ③ **Sealant Grooves.** this system permits sealant injection while the valve is under full line pressure. WALWORTH recommends that the valves be lubricated with plug in the fully opened or fully closed position for optimum valve performance.
- ④ **Open/Closed Indicator.** quarter turn stop collar also functions as an indicator of the plug's position.
- ⑤ **Diaphragm Gasket.** ensures a complete sealing of the valve against leakage.
- ⑥ **Plug.** WALWORTH Plugs are designed with an specific coating material that reduces the coefficient of friction making the valve to operate with low torque.

IRON PLUG VALVE VENTURI PATTERN CLASS 175 CWP (Gear Operated)

Regular Bill of Materials

No.	Description	Material
1	BODY	ASTM A-126 CLASS B
2	GLAND	ASTM A-126 CLASS B
3	PLUG	ASTM A-126 CLASS B
4	GLAND SCREW	ASTM A 307 Gr. B
5	GLAND NUT	ASTM A 194 Gr. 2H
6	GREASE FITTING	COMMERCIAL STEEL
7	DIAPHRAGM	ASTM A240 TIPO 304
8	BALANCE SPRING	STAINLESS STEEL
9	O-RING	NITRILE BUTADIENE RUBBER
10	SEALANT CHECK VALVE	COMMERCIAL STEEL
11	PACKING RETAINER	STEEL
12	COVER SCREW	ASTM A 307 GRADE B
13	COVER NUT	ASTM A 194 Gr. 2H
14	COVER	ASTM A-126 CLASE B
15	GEAR OPERATOR	COMERCIAL STEEL
16	GEAR OPERATOR SUPPORT	CARBON STEEL
17	GEAR OPERATOR BOLTING	ASTM A 307 Gr. B
18	STEM EXTENSION	ASTM A 322 GRADE 4140
19	KEY	ASTM A 108 GRADE 1020
20	BUSHING	ASTM A 322 GRADE 4140
21	COVER GASKET	BLUE GUARD
22	GASKET	BLUE GUARD




IRON PLUG VALVE VENTURI PATTERN CLASS 175 CWP (Gear Operated)

Design Features

- Flat Face Flanged ends in accordance with ASME B16.1
- Design in accordance with MSS SP-78
- Test in accordance with API 598 & MSS SP 78

Figure no.	Operation	Type of ends
1703	Gear Operated	FLANGED FLAT FACE



Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions		Approx Weight	
										E		FLAT FACE	
		A		B		C		D					
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb
14	350	20.37	517	11.87	301	26	660	29	737	27	686	570.2	1256.0
16	400	21.62	549	13.37	340	26	660	32	812	30	762	660.6	1455.0
18	450	23.37	594	14.75	375	30	762	35	889	34	864	858.1	1890.0


IRON PLUG VALVE VENTURI PATTERN CLASS 500 CWP

Regular Gland Type

DESIGN FEATURES

WALWORTH Regular Gland type Lubricated Plug Valves are designed to control plug adjustment tightening the gland, requesting only a very low maintenance in the field.

These Valves are all provided with separate retainers (cover plate) and adjusting glands; generally sizes 3" and smaller have four-bolt square retainers, while 4 inches and large sizes have round retainers. They all incorporate the Pressure Sealed Lubrication features.




Design Features

- ① **Sealant Fitting.** Fast Sealant Injection that can be removed under pressure. The system includes Ball Check valves in order to prevent the back pressure and maintain the pressure in the sealant cavity.
- ② **Balancing Spring.** the mechanical spring type grade SS-304 washer is under compression and holds the plug in an equalized pressure position, thus eliminating the possibility of plug taper lock.
- ③ **Sealant Grooves.** this system permits sealant injection while the valve is under full line pressure. WALWORTH recommends that the valves be lubricated with plug in the fully opened or fully closed position for optimum valve performance.
- ④ **Open/Closed Indicator.** quarter turn stop collar also functions as an indicator of the plug's position.
- ⑤ **Diaphragm Gasket.** ensures a complete sealing of the valve against leakage.
- ⑥ **Plug.** WALWORTH Plugs are designed with an specific coating material that reduces the coefficient of friction making the valve to operate with low torque.

IRON PLUG VALVE VENTURI PATTERN CLASS 500 CWP (Lever Operated)

Regular Bill of Materials

No.	Description	Material
1	BODY	ASTM A-126 CLASS B
2	GLAND	ASTM A-126 CLASS B
3	PLUG	ASTM A-126 CLASS B
4	COLLAR RETAINER	CARBON STEEL
5	GLAND SCREW	ASTM A 307 Gr. B
6	GLAND NUT	ASTM A 194 Gr. 2H
7	GASKET	STAINLESS STEEL + GRAPHITE
8	WEATHER SEAL	NITRILE BUTADIENE RUBBER
9	GREASE FITTING	COMMERCIAL STEEL
10	RING RETAINER	COMMERCIAL STEEL
11	BALANCE SPRING	STAINLESS STEEL
12	O-RING	NITRILE BUTADIENE RUBBER
13	SEALANT CHECK VALVE	COMMERCIAL STEEL
14	PLUG CHECK VALVE	COMMERCIAL STEEL
15	COVER SCREW	ASTM A 307 GRADE B
16	COVER NUT	ASTM A 194 Gr. 2H
17	COVER	ASTM A-126 CLASE B
18	WRENCH	GRAY IRON
19	SET SCREW	ALLOY STEEL
20	WRENCH PIN	ASTM A568




IRON PLUG VALVE VENTURI PATTERN CLASS 500 CWP (Lever Operated)

Design Features

- Flat Face Flanged ends in accordance with ASME B16.1
- Design in accordance with MSS SP-78
- Test in accordance with API 598 & MSS SP 78

Figure no.	Operation	Type of ends
2721	Lever Operated	FLANGED FLAT FACE




Dimensions and Weights

Nominal Size		General Dimensions								End to End Dimensions		Approx Weight		Wrench No.
										E		FLAT FACE		
		A		B		C		D		FLAT FACE				
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb	
6	150	10.56	268	6.18	157	1.5	38	8.37	213	15.87	99.4	219.0	219.0	P-1
8	200	12.25	311	7.62	194	1.75	44	9.62	244	16.5	153.0	337.0	337.0	R-3

IRON PLUG VALVE VENTURI PATTERN CLASS 500 CWP (Gear Operated)

Regular Bill of Materials

No.	Description	Material
1	BODY	ASTM A-126 CLASS B
2	GLAND	ASTM A-126 CLASS B
3	PLUG	ASTM A-126 CLASS B
4	GLAND SCREW	ASTM A 307 Gr. B
5	GLAND NUT	ASTM A 194 Gr. 2H
6	GASKET	STAINLESS STEEL + GRAPHITE
7	GREASE FITTING	COMMERCIAL STEEL
8	BALANCE SPRING	STAINLESS STEEL
9	O-RING	NITRILE BUTADIENE RUBBER
10	SEALANT CHECK VALVE	COMMERCIAL STEEL
11	PLUG CHECK VALVE	COMMERCIAL STEEL
12	COVER SCREW	ASTM A 307 GRADE B
13	COVER NUT	ASTM A 194 Gr. 2H
14	COVER	ASTM A-126 CLASE B
15	GEAR OPERATOR	COMERCIAL STEEL
16	GEAR OPERATOR SUPPORT	CARBON STEEL
17	GEAR OPERATOR BOLTING	ASTM A 307 Gr. B
18	STEM EXTENSION	ASTM A 322 GRADE 4140
19	COLLAR RETAINER	CARBON STEEL




IRON PLUG VALVE VENTURI PATTERN CLASS 500 CWP (Gear Operated)

Design Features

- Flat Face Flanged ends in accordance with ASME B16.1
- Design in accordance with MSS SP-78
- Test in accordance with API 598 & MSS SP 78

Figure no.	Operation	Type of ends
2723F	Gear Operated	FLANGED FLAT FACE



Dimensions and Weights


Nominal Size		General Dimensions								End to End Dimensions		Approx Weight	
										E		FLAT FACE	
		A		B		C		D		FLAT FACE		FLAT FACE	
in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	Kg	lb
6	150	10.56	268	6.18	157	26	660	11	279	15.87	403	133.5	294.0
8	200	12.25	311	7.62	194	26	660	13	330	16.5	419	190.7	420.0

TECHNICAL INFORMATION

PLUG VALVES WRENCHES


TOP ENTRY IRON PLUG VALVES WRENCHES

WRENCH NUMBER	OPENING DIMENSION (B)	HANDLE LENGTH (A)	FOR USE WITH VALVES SIZE, CLASS OR FIGURE NUMBER
DB D – 4	13/16"	9"	1/2", 3/4" & 1" 1796 and 1" 1797F, 3/4" & 1 1/4" 1966 *
DB E – 1	29/32"	9"	1 1/4", 1 1/2" 1796 & 1797F
DB G – 1	1 1/16"	9"	2" 1796, 2" 1797F, 2" 1700, 2" 1700F, 2 1/2" 1796, 2 1/2" 1797F
DB M – 1	1 3/8"	15"	3" 1700, 1700F, 1796, & 1797F
DB P – 1	1 1/2"	17"	4" 1796 & 1797F, 4" 1700F
R – 3	1 3/4"	36"	8" 1718F & 2721F
T – 3	2 1/16"	36"	6" 1700F, 10" 1718F
V – 3	2 7/16"	48"	12" 1718F
P – 1	1 1/2"	17"	6" Fig. 1718 Fig. 2721
DB P – 1.1	1 1/2"	17"	5" Fig. 1797



2" SQUARE OPERATING NUTS USED IN TOP ENTRY IRON PLUG VALVES

OPERATING No.	VALVE SIZE	FOR USE WITH VALVES SIZE, CLASS OR FIGURE NUMBER
DB LN-1	1/2", 3/4", 1"	1/2", 3/4" & 1" 1796 and 1" 1797F, 3/4" & 1 1/4" 1966 *
DB LN-2	1 1/4", 1 1/2"	1 1/4", 1 1/2" 1796 & 1797F
DB LN-3	2", 2.5"	2" 1796, 2" 1797F, 2.5" 1796F & 1797F
DB LN-5	3"	3" 1700, 1700F, 1796, & 1797F
DB LN-6	4"	4" 1796 & 1797F, 4" 1700F
DB LN-6.1	5"	5" 1797F
LN-7	8"	8" 1718F, 2721F, 2723 & 1727
LN-6	6"	6" 1718F, 2721F, 2723 & 1727



CORRESPONDING OPERATING NUT AND RECTANGLE OPENING SIZE

OPERATING NUT	OPENING DIMENSIONS (B)
ON.1 DB LN - 1	Ø 1.250" x .907"
ON.2 DB LN - 2	Ø 1.5" x 1.000"
ON.3 DB LN - 3	Ø 1.6" x 1.120"
ON.4 DB LN - 5	Ø 2.00" x 1.356"
ON.7 DB LN - 6	Ø 2.2" x 1.375"
ON.8 DB LN - 6.1	Ø 2.4" x 1.750"
ON.9 LN - 6	Ø 1.532" square
ON.10 LN - 7	Ø 1.760" square

TECHNICAL INFORMATION

WALSEAL PLUG VALVES SEALANT

FUNCTION AND PROPERTIES OF WALSEAL SEALANTS

To assure thoroughly satisfactory service, WALWORTH Walseal Sealants should always be used with WALWORTH Plug Valves.

Function: The sealant minimizes friction during operation of the valve and protects seating surfaces from corrosion. Because the ports of valves are completely encircled with sealant grooves, leakage is prevented by the Walseal sealant.

Properties: Walseal sealants have the necessary properties to serve a variety of purposes.

1. Have lubricating value to allow the valve to turn easily.
2. Have sufficient body to resist dilution by line fluids and still assure tight sealing.
3. Are chemically inert in the fluids for which they are specified and have the ability to adhere to the metal of the finished seating surfaces to protect from corrosion.
4. Remains in a plastic state over a wide range of temperature conditions to act as a hydraulic medium, and provide for lubrication and corrosion protection.
5. Contain a minimum of Ingredients that might solidify from temperature or chemical reactions and clog the groove system.

2. **Color.-** Where discoloration of the line contents must be guarded against, select a white sealant. If available. In special cases consult a WALWORTH representative.
3. **Contamination -** Sealant for use with foodstuffs or pharmaceuticals must be non-toxic, taste and color-free and chemically inert.
4. **Temperature -** As a general rule, choose the sealant with the lowest maximum temperature rating. Such a sealant will usually have greater lubricating value at normal temperatures than one with a higher limit. This is important as it affects the ease of operation of the valve.
5. **Compromise -** If a sealant is required for a mixed service condition, a good practical rule is to select the sealant recommended to the predominating part of the pipe-line contents.
6. **Nitrating Acids -** It is dangerous to use certain sealants on nitrating acids. Please contact your WALWORTH representative for this application.

Proper sealant maintenance:

The amount of maintenance required depends upon the frequency of operation of the valve.

Regular maintenance: Preserves the seating surfaces and prevents leakage. Definite periodic service gives the best results. Any valve not regularly operated should be serviced at least every six months.

SELECTION AND MAINTENANCE OF WALSEAL SEALANT

How to select a sealant:

1. **Line Contents -** Select a sealant recommended for the particular service requirements.

Ordering Information:

1. State whether jumbo, stick or bulk sealant is desired.
2. For bulk sealant give Walseal number and container size.

STICK	STICK SIZE	AVAILABLE IN WALSEAL NO.
B (24/box)	318' X 1 1/2' (Box approx. 1.2 lb.)	10, 20, 40 and 60
C (24/box)	7/16' X 2 1/8' (Box approx. 1.2 lb.)	10, 20, 40 and 60
D (24/box)	1/2' X 2 1/4' (Box approx. 1.2 lb.)	10, 20, 40 and 60
G (24/box)	518' X 3 1/2' (Box approx. 1.2 lb.)	10, 20, 40 and 60
CARTRIDGE - (Box of 4 - 1 lb. each)		All TYPES
BULK		
J-Jumbo Jr. (6)	1 3/8' X 8 1/2' (Box approx. 3.2 lb.)	10, 20, 40 and 60
K-Jumbo (12)	1 1/2' X 10 1/2' (Box approx. 9.2 lb.)	10, 20,40 and 60
Gun Pack (Box-6 GP)		All TYPES
10 pound (5 quart can)		
40 pound (5 gallon can)		
400 pound (55 gallon drum)		

TECHNICAL INFORMATION

WALSEAL PLUG VALVES SEALANT

WALSEAL #10

Temperature range from -20F to 500F Stick / -40F to 500F Bulk
Dark Gray

Service: General purpose sealant intended for use in natural gas and liquid petroleum services including crude distillates, combustible fuels such as gasoline, jet fuel, and heating oils. Used as assembly sealant in all WALWORTH plug valves unless otherwise specified.

Not intended for use in: Solvents (aromatic), strong acids and alkalies, and steam.

WALSEAL #20

Temperature range from OF to 650F Bulk / 30F to 690F Stick
Color red

Service: High temperature general purpose sealant for use in acids, alkalies, alcohols, amines, asphalt, aqueous solutions, fats, glycerine glycols, soap, steam, and water service having continuous exposure to temperatures above 400F.

Not intended for use in: Aromatic solvent light liquid hydrocarbons, nitrating acids.

WALSEAL #40

Temperature range from 1 OF to 350F Stick / -10F to 350F Bulk
Color light brown

Service: Specifically formulated for resistance to all octane gasolines, aviation and jet fuels, kerosene, fuel blending ingredients, and water. Approved for government use per MIL-G-6032.

Not intended for use in: Strong acids and alkalies.

WALSEAL #50

Temperature range from -50F to 300F
Color beige

Service: Low temperature general purpose sealant for use in services similar to Walseal #10. Recommended for continuous exposure to temperatures below 0°F.

Not intended for use in: Solvents (aromatic and chlorinated), strong acids and alkalies.

WALSEAL #60

Temperature range from 1 OF to 350F Stick / 0F to 300F Bulk
Service: Suitable for water, acids, alkalies, alcohols, and amines. May be used in food or pharmaceutical applications if approved by user. Certified by the National Sanitary Foundation.

Not intended for use in: Hydrocarbon solvents.

Continued use of any sealant at either the low or high temperature limit is not recommended.

For more information concerning these sealants or recommendations for a particular service contact your WALWORTH representative.

WALWORTH VALVE FLUSH

For hard-to-operate valves

-20°F to 400°F

(-28°C) (204°C) BLACK

VALVE FLUSH is not a sealant; however, it is compatible with any lubricant or sealant. It contains molybdenum disulfide for added lubricity. VALVE FLUSH may be applied with conventional lubricating equipment.

VALVE FLUSH will work through any fitting that is not completely plugged. In other words, if VALVE FLUSH cannot be injected past the fitting, it will not free the valve. If the fitting is plugged, then it is recommended that fitting be removed and replaced with the appropriate WALWORTH fitting.

WALWORTH "VALVE FLUSH" JUMBO, JR. BAG 6/BX

WALWORTH "VALVE FLUSH" JUMBO, BAG 6/BX

WALWORTH "VALVE FLUSH" 1 CARTRIDGE 12/CTN

WALWORTH "VALVE FLUSH" 10LB. (5QT.) CAN.

WALWORTH "VALVE FLUSH" 20 LB. (3GAL.) PAIL

WALWORTH "VALVE FLUSH" 40 LB. (6GAL.) PAIL

TECHNICAL INFORMATION

LUBRICANT ACCESORIES

1002 WALSEAL HYDRAULIC DELTA STICK SEALANT GUN, FOR USE WITH "K" SIZED SEALANT.

1699 HIGH PRESSURE LUBRICANT GUN

1699 G HIGH PRESSURE LUBRICANT GUN WITH GAUGE

Where a number of valves are installed under the same, or related, service conditions it is advantageous to lubricate them with a **WALWORTH High Pressure Lubricant Gun**.

The WALWORTH High Pressure Lubricant Gun is the only portable gun that can handle full-bodied valve lubricants in stick form.

The gun is self-priming and may be used in any position. The pump handle is detachable and has a hole drilled near one end.

By detaching the handle and placing the hole over the protruding button on the charging cap, the cap can readily be removed and replaced.

The handle is also used as a pusher for returning the piston to the bottom of the cylinder for the purpose of charging the gun.

To charge the gun the by-pass is opened and the piston pushed down as far as it will go. The by-pass valve is then closed and two


sticks of WALWORTH Jumbo Size Lubricant inserted. Then the charging cap is replaced, using the pump handle and protruding button on the cap to tighten it, and the gun is ready for use. The lever handle is then pumped until sealant appears at the end of the hose.

During operation of the gun, should the pressure created lock the coupling to the button-head filling, the pressure can be relieved and the coupling disconnected by opening the bypass valve. Relief fittings are provided on the hose and within the gun to prevent valve damage should the lubricating system be clogged, or prevent damage to the gun itself in the event it is operated when empty.

HIGH PRESSURE GAUGE

For use with Sealant hand guns and pumps. An essential accessory to indicate when sufficient Sealant pressure has been developed.

Gauge needle pulsation goes up by steps until valve is completely filled with Sealant. When Sealant pressure reaches a certain point, the gauge needle begins to drop showing that the valve is full. Gauge also indicates valve adjustment and other service required.



TECHNICAL INFORMATION

WALWORTH LUBRICANT FITTINGS

Most types of WALWORTH Lubricated Plug Valves are regularly provided with the WALWORTH Lubricant Fitting illustrated. It is a Giant Button-Head Fitting to which the lubricant gun may be coupled easily for a leakproof connection. These fittings may also be used as regular lubricant screws with standard size lubricant sticks.

One size of Button-Head Fitting is used for all Compensator Plug Valves. The Button-Head figure number for other WALWORTH Plug Valves is the same as the "Sealant Stick Size" listed on the catalog page for each valve type and size.



WALWORTH BUTTON-HEAD LUBRICANT FITTINGS	LUBRICANT FITTING SIZE	WALWORTH LUBRICANT FITTING NUMBER
For Standard Compensators	1/4"	BH1
For NACE MR0-01-75 Compensators	1/4"	BH1-N
For valves with Sealant Stick Size: B	1/4"	BH2
C	□	BH3
D	1/2	BH4
G	3/4	BH5

DOUBLE BALL CHECK VALVE ASSEMBLIES	
No.	Valve Size
B	1/2 to 2"
C	2 1/2 to 3"
D	4 & 5"
G	6" & up

TECHNICAL INFORMATION

PRESSURE AND TEMPERATURE RATINGS





FLUID TEMPERATURE °F	CAST IRON PLUG VALVES ASTM A-126 CLASS B		
	175 CWP	200 CWP	500 CWP
-20 to 150	175	200	500
200	165	190	460
225	155	180	440
250	150	175	415
275	-	170	395
300	-	165	375
325	-	155	355
350	-	150	335
375	-	145	315
400	-	140	290
425	-	130	270
450	-	125	250
TEST PRESSURES PSI, MIN.			
HYDROSTATIC SHELL TEST	350	400	1000
SEAT (CLOSURE) TEST	275	300	750

Maximum allowable working pressures, derived from API 599, API 6D, ANSI B16.34 and/or MSS SP-78 are shown. For intermediate temperatures, linear interpolation may be used. Ratings for threaded valves smaller than 1" and for 175 CWP valves are manufacturer's. Application of ratings is subject to the temperature limitations of the sealants used. Applicable Codes and Standards should be consulted for restrictions on pressure, temperature and usage of the valves. Further reference should be made to individual description pages for additional comments or restrictions.

TECHNICAL INFORMATION

FLANGE DIMENSIONS AND TEMPLATES

CAST IRON FLANGE DIMENSIONS AND DRILLING TEMPLATES ANSI B 16.1



CLASS 125

NOMINAL PIPE SIZE	FLANGES		DRILLING		BOLTING		LENGHT OF MACHINE BOLTS F
	FLANGE DIAMETER A	FLANGE THICKNESS MIN B	DIAMETER OF VOLT CIRCLE D	DIAMETER OF BOLT HOLES E	NUMBER OF BOLTS	DIAMETER OF BOLTS	
1	4 1/4	7/16	3 1/8	5/8	4	1/2	1 3/4
1 1/4	4 5/8	1/2	3 1/2	5/8	4	1/2	2
1 1/2	5	9/16	3 7/8	5/8	4	1/2	2
2	6	5/8	4 3/4	3/4	4	5/8	2 1/4
2 1/2	7	3/4	5 1/2	3/4	4	5/8	2 1/2
3	7 1/2	15/16	6	3/4	4	5/8	2 1/2
4	9	15/16	7 1/2	3/4	8	5/8	3
5	10	15/16	8 1/2	7/8	8	3/4	3
6	11	1	9 1/2	7/8	8	3/4	3 1/4
8	13 1/2	1 1/8	11 3/4	7/8	8	3/4	3 1/2
10	16	1 3/16	14 3/4	1	12	7/8	3 3/4
12	19	1 1/4	17	1	12	7/8	3 3/4

Bolt lengths are for flanges of thickness shown herein. Bolt lengths should be checked for the thicker flanges shown in some individual valve description pages. When flanges integral with valves or fittings, the bolt holes, which are in multiples of four, are drilled to straddle the center lines unless otherwise ordered. Class 125 cast iron flanges have plain faces.

CLASS 250

NOMINAL PIPE SIZE	FLANGE THICKNESS			DRILLING		BOLTING		LENGHT OF MACHINE BOLTS F
	FLANGE DIAMETER A	FLANGE THICKNESS MIN B	DIAMETER OF RAISED FACE C	DIAMETER OF VOLT CIRCLE D	DIAMETER OF BOLT HOLES E	NUMBER OF BOLTS	DIAMETER OF BOLTS	
1	4 7/8	1 1/16	2 11/15	3 1/2	3/4	4	5/8	2 1/2
2	6 1/2	7/8	4 3/16	5	3/4	8	5/8	2 3/4
3	8 1/4	1 1/8	5 11/16	6 5/8	7/8	8	3/4	3 1/2
4	10	1 1/4	6 15/16	7 7/8	7/8	8	3	3 3/4

The 1/16-inch raised face on the Class 250 cast iron flanges is included in the dimension B for thickness of flange.

Bolt lengths are for flanges of thickness shown herein. Bolt lengths should be checked for the thicker flanges shown in some individual valve description pages.

DESIGN BASIS

All of WALWORTH's Valve Designs, when applicable, follow one or more of the following standards.

API Standards	American Petroleum Institute
	• API-598 Valve inspection and testing. • API-599 Metal Plug Valves - Flanged, Threaded and Welding.
ANSI Standards	National Standards Institute
	• B16.1 Cast Iron Pipe Flanged and Flanged Fittings • B16.10 Length of ferrous flanged and welding end valves • B1.20.1 Pipe Threads, General Purpose. • B16.34 Valves - Flad, Threaded and Welding End.
ASTM Standards	American Society for Testing and Materials
	• ASTM A126 Gray Iron Castings For valves, flanges and pipe fittings. • ASTM A193 Alloy-Steel and Stainless Steel Bolting Materials for High-Temperature Service • ASTM A194 Carbon and Alloy Steel nuts for bolts for High-Pressure and High-Temperature Service • ASTM A216 Steel Castings, Carbon, suitable for Fusion Welding for High-Temperature Service • ASTM A276 Stainless and Heat-Resisting Steel Bars and Shapes • ASTM A307 Carbon Steel bolts and studs , 60,000 psi Tensile • ASTM A320 Alloys - Steel bolting materials for Low-Temperature Service. • ASTM A352 Steel Castings, Ferritic and Martensitic, for Pressure-Containing Parts. Suitable for Low-Temperature Service. • ASTM A487 Steel Castings Suitable for Pressure Service • ASTM A515 Pressure Vessel Plates, Carbon Steel, for intermediate and High-Temperature Service.
MSS Standards	Manufacturers Standardization Society
	• MSS SP-6 Standard Finishes for Contact Faces of Pipe Flanges and Connecting-end Flanges of Valves and Fittings. • MSS SP-9 Spot Facing Bronze, Iron and Steel Flanges • MSS SP-25 Standard Marking System for Valves, Fittings, Flanges and Unions. • MSS SP-44 Steel Pipe Line Flanges • MSS SP-55 Visual Method • MSS SP-61 Pressure Testing of Steel Valves • MSS SP-78 Cast Iron Plug Valves, Flanged and Threaded Ends
NACE Standards	National Association of Corrosion Engineers
	• NACE MR-01-75 Standard material requirements sulfide stress cracking resistant metallic materials for oilfield equipment
ASME Codes	American Society of Mechanical Engineers
	• ANSI/ASME B31.1 Power Piping • ANSI/ASME B31.2 Fuel Gas Piping • ANSI/ASME B31.3 Process Piping • ANSI/ASME B31.4 Liquid Transportation Systems for Hydrocarbons • ANSI/ASME B31.8 Gas Transmission and Distribution Piping Systems • ANSI/ASME B31.9 Building Services Piping.
Boiler and Pressure Vessel Code:	
	• Section II Material Specifications - Part A, B and C • Section V Non-Destructive Examination. • Section VIII Rules for construction of Pressure vessels, divisions 1 and 2 • Section IX Welding and Brazing Qualifications

HOW TO ORDER

SIZE (INCH)	DESCRIPTION BY FIGURE NUMBER	BASE MATERIAL	SUPPLEMENTARY REQUIREMENTS
1/2"	1796= SINGLE GLAND TYPE; CWP 200, SHORT PATTERN, WRENCH OPERATED, THREADED ENDS.	CAST IRON ASTM A126 GRADE B	BS= Bare stem prepared for actuator.
3/4"			MOV= Motor operated valve.
1"	1797F= SINGLE GLAND TYPE; CWP 200, SHORT PATTERN, WRENCH OPERATED, FLANGED RF ENDS.		POV= Pneumatic operated valve.
1 1/4"			LD= Locking device.
1 1/2"	1718F= REGULAR GLAND TYPE; CWP 200, SHORT PATTERN, WRENCH OPERATED, FLANGED RF ENDS.		SP= Special Paint.
2"			SPK= Special packing.
2 1/2"	1727F= REGULAR GLAND TYPE; CWP 200, SHORT PATTERN, WORM GEAR OPERATED, FLANGED RF ENDS.		XX= Additional requirements.
4"	1700= REGULAR GLAND TYPE; CWP 200, REGULAR PATTERN, WRENCH OPERATED, THREADED ENDS.		
5"			
6"	1700F= REGULAR GLAND TYPE; CWP 200, REGULAR PATTERN, WORM GEAR OPERATED, FLANGED RF ENDS.		
8"			
10"	1703F= REGULAR GLAND TYPE; CWP 175, VENTURI PATTERN, WORM GEAR OPERATED, FLANGED RF ENDS.		
12"			
14"	1707F= REGULAR GLAND TYPE; CWP 200, VENTURI PATTERN, WORM GEAR OPERATED, FLANGED RF ENDS.		
16"			
18"	2721F= CWP 500, VENTURI PATTERN, WRENCH OPERATED, FLANGED RF ENDS.		
	2723F= CWP 500, VENTURI PATTERN, WORM GEAR OPERATED, FLANGED RF ENDS.		

10"- 1796 - X

SUPPLEMENTARY REQUIREMENTS.

GLAND TYPE, PRESSURE CLASS, PATTERN STYLE, TYPE OF ENDS & PRESSURE CLASS.

SIZE OF THE VALVE IN INCHES

THE WALWORTH COMPANY GENERAL TERMS AND CONDITIONS

ACCEPTANCE: All quotations are for acceptance within 30 days from date of quotation unless extended in writing. In the event a purchase order is placed after this period of time, the WALWORTH Company reserves the right to requote base prices of all valves offered. All orders and contracts are subject to credit approval and acceptance by the WALWORTH Company.

FREIGHT: When prices are f.o.b. point of shipment - no freight allowance - we will attempt to route shipments in the method which will result in the lowest cost unless otherwise instructed. All shipments will be freight charges collect except when stipulated on the purchase order, in which case you will be invoiced for all transportation charges. Delivery of material to a common carrier shall be considered to be delivery to Buyer and shall be at Buyer's risk thereafter. Claims of loss of or damage to material in transit shall be filed by the Buyer directly with the carrier.

PRICES: There will be added to all prices quoted sales, use, occupation or any other excise or similar tax which Seller may be required to pay or collect on or in connection with the sale. Seller shall be established by Federal, State or other government regulation with respect to the product(s) topped by the order which shall be lower than the price(s) specified in the order.

ESCALATION TERMS: Prices shown in this price schedule reflect the costs in effect at the time of publication. These prices will remain firm on all products with a quoted delivery of twenty-six (26) weeks or less. On products which have a scheduled delivery of more than twenty-six (26) weeks, the goods will be invoiced based on the applicable price sheet in effect at the time of shipment. In no event will the invoiced price be less than the price originally quoted.

PURCHASED COMPONENTS: (i.e. motors, gearing, etc.) Prices are quoted on the supplier's price in effect at the time of quotation. Actual invoice price will be adjusted in accordance with the supplier's escalation policy.

DIFFERED SHIPMENTS: If for any reason the customer desires to delay shipments more than 30 days after manufacturing is complete, or to place a on hold or stop to the order during the manufacturing cycle, The WALWORTH Company reserves the right to consider the order cancelled and to invoke cancellation charges per the schedule below.

CANCELLATION: After order acceptance by WALWORTH, items or completed orders may be cancelled and Buyer will be charged for work performed, based on the following schedule:

- Five percent (5%) of prices of stock items.
- Ten percent (10%) of price of stock items ordered in quantities which exceed normal inventory levels.
- Five percent (5%) of prices prior to drawing submittal on made-to-order items.
- 15% after drawing approval, but prior to the start of castings.
- 30% to 50% during casting cycle, depending on the state of completion.
- 55% to 75% during machining and assembly operations, depending on the state of completion.
- 100% after final assembly and test.

REMITTANCES: Remittances must be made to the address indicated on the invoice.

CREDIT TERMS: As quoted. Invoices on balances overdue will be subject to a service charge of 1 1/2 % per month on such indebtedness.

DELIVERIES: Shipments and deliveries shall at all times be subject to the approval of Seller's Credit Department. If the Buyer shall fail to make any

payments according to the terms of the contract, Seller may, in addition to and not in limitation of its other rights and remedies, at its option, cancel all or any part of Buyer's incomplete contracts with Seller, or may defer shipments of deliveries under Buyer's contracts with Seller except upon receipt of satisfactory security or for cash shipment.

All schedule of shipments are estimated as closely as possible and Seller will use its best efforts to ship within the time scheduled, but does not guarantee to do so. Schedules commence with the date Seller receives authorization to proceed with the order, subject to the provisions of the next sentence. The order will not be released for manufacture until complete specifications and approved drawings (if drawing approval is required) are received at the plant of manufacturer and the estimated schedule of shipment will commence with the date of such receipt.

Seller shall not be liable for any direct, indirect or consequential damage or loss caused by any delay in delivery, regardless of the cause of delay.

Without limiting the generality of the foregoing, Seller assumes no responsibility for delays in delivery resulting from fire, flood, accidents, riots, strikes, transportation delays, labor or material shortages, existing or future laws, acts of any governmental authority, or any other cause beyond Seller's control. Items offered from stock are subject to prior sale.

INSPECTION: Final inspection and acceptance of products must be made at the plant of manufacture, unless otherwise provided in the order and/ or in agreed upon specifications. Prices do not include charges for special tests or inspections performed at the request of the Buyer, unless called for in the order and/or in agreed upon specifications.

RETURNS: Permission in writing and return tagging instructions must be obtained from Seller before any goods returned for credit or adjustment will be accepted. Where returned goods are accepted, a minimum charge of 25% of the invoice price will be made, plus freight from both directions and costs of reconditioning the material for resale as new.

WARRANTY: Seller will replace without charge or refund the purchase price of products manufactured by Seller which prove to be defective in the material or workmanship, provided in each case that the product is properly installed and is used in the service for which Seller recommends it and that a written claim, specifying the alleged defect, is presented to Seller. Seller shall in no event be responsible for (a) claims for labor, expenses or other damages occasioned by defective products or (b) for consequences or secondary damages. THE WARRANTY STATED IN THIS PARAGRAPH IS IN LIEU OF ALL OTHER WARRANTIES, EITHER EXPRESSED OR IMPLIED. WITH RESPECT TO WARRANTIES, THIS PARAGRAPH STATES BUYER'S EXCLUSIVE REMEDY AND SELLER'S EXCLUSIVE LIABILITY.

DESIGN, ETC: Seller reserves the right to change design, materials or specifications without notice. There will be a charge for modifying an order after it has been entered when such change or modification results in additional engineering or clerical work for either The WALWORTH Company or our suppliers.

MINIMUM CHARGE: Orders totaling less than \$100.00 net will be billed at a minimum charge of \$100.00. Repair parts will be billed at a minimum charge of \$50.00.

NOTE: We reserve the right to correct obvious clerical errors in quotations, invoices, and other contracts.



WALWORTH[®]

Since 1842



www.walworth.com

MÉXICO

Industrial de Válvulas, S.A. de C.V.

Industria Lote 16 Sin Número, Fracc. Industrial El Trébol De Tepetzotlán, Tepetzotlán Estado de México C.P. 54610

Phone: (52 55) 5899 1700 Fax: (52 55) 5876 0156 | e-mail: info@walworth.com.mx

USA/CAN AUTHORIZED DISTRIBUTOR

TWC The Valve Company

**13641 Dublin Court, Stafford, Texas 77477 | Phone: (281) 566 1200 Fax: (281) 566 1299 |
www.twcvalves.com | e-mail: info@twcousa.com**



Scan me with your smartphone to get
more info about **WALWORTH** valves

